



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

### Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

### About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>

UC-NRLF



\$B 309 209

# GEOGRAPHIC INFLUENCES IN AMERICAN HISTORY

ALBERT PERRY BRIGHAM

CHAUTAUQUA  
HOME READING SERIES

LIBRARY  
OF THE  
UNIVERSITY  
OF  
CALIFORNIA

















FOREFATHERS' ROCK, PLYMOUTH

# GEOGRAPHIC INFLUENCES IN AMERICAN HISTORY

BY

ALBERT PERRY BRIGHAM, A.M., F.G.S.A.

PROFESSOR OF GEOLOGY IN COLGATE UNIVERSITY



NEW YORK CHAUTAUQUA SPRINGFIELD CHICAGO

**The Chautauqua Press**

MCMIII

COPYRIGHT, 1903, BY  
**ALBERT PERRY BRIGHAM**

---

ALL RIGHTS RESERVED

E 179  
B8  
1903

IN MEMORY OF MY SON

CHARLES WINEGAR BRIGHAM

A LOVER OF TRUTH AND BEAUTY, AN ARDENT READER  
OF AMERICAN HISTORY, WHO PASSED FROM THIS  
LIFE TOO SOON TO FULFIL THE PROMISE OF  
HIS YOUTH, THIS VOLUME IS INSCRIBED



## PREFACE

IN the chapters which follow, an attempt has been made to combine the materials of American history and geography. One must invent a method as he can, for models in this field can scarcely be said to exist. The plan chosen is geographic, as might be expected from a student of earth science. Each division of the book deals with a region which is more or less distinct in its physical development, and which often shows in the end a good measure of historical unity.

Parkman and Fiske have been among the most useful historical authorities; also McMaster, and the "Winning of the West," by Theodore Roosevelt, who, as an official and as a private citizen, has shown an unfailing appreciation of the physical features of our country.

Prof. Charles Worthen Spencer of Colgate University has kindly read the manuscript of the volume and has made valuable suggestions. It should be stated that parts of Chapter I have previously appeared in the *Geographical Journal* of London, and

a few paragraphs of Chapter VIII were originally prepared for the Bulletin of the American Geographical Society.

Many have generously aided me in securing the illustrations. A considerable number have been drawn from the collections of Mr. William H. Rau, Philadelphia. I am also indebted to Dr. F. J. H. Merrill, State Geologist, Albany; Rev. A. K. Fuller, Newburg; Prof. J. T. Draper, Holyoke; Prof. Arthur M. Miller and Prof. H. Garman, State College of Kentucky; Prof. W. B. Clarke, Johns Hopkins University; Prof. Edward M. Lehnerts, Winona, Minn.; Prof. Samuel Calvin, State Geologist of Iowa; Mr. G. K. Gilbert, United States Geological Survey; President Benjamin Ide Wheeler of the University of California and the United States Bureau of Forestry.

Both the physiographer and the historian may often regret omissions or brevity of treatment, but such limits are imperative when a vast and twofold theme is undertaken in a small volume.

ALBERT PERRY BRIGHAM.

COLGATE UNIVERSITY,  
May, 1903.

# CONTENTS

CHAPTER	PAGE
I. THE EASTERN GATEWAY OF THE UNITED STATES . . . . .	I
II. SHORE-LINE AND HILLTOP IN NEW ENGLAND .	37 ✓
III. THE APPALACHIAN BARRIER . . . . .	70 ✓
IV. THE GREAT LAKES AND AMERICAN COMMERCE	105 ✓
V. THE PRAIRIE COUNTRY . . . . .	142 ✓
VI. COTTON, RICE, AND CANE . . . . .	173
VII. THE CIVIL WAR . . . . .	200 •
VIII. WHERE LITTLE RAIN FALLS . . . . .	230 •
IX. MOUNTAIN, MINE, AND FOREST . . . . .	255 ✓





## LIST OF ILLUSTRATIONS

FIG.		PAGE
	Forefathers' Rock, Plymouth . . . . . <i>Frontispiece</i>	
1.	The Palisades of the Hudson . . . . .	5
2.	Adirondacks about Clear Lake . . . . .	9
3.	Hudson Valley and Catskills in Relief . . . . .	17
4.	In the Mohawk Valley . . . . .	21
5.	Clay Beds on the Hudson . . . . .	29
6.	Northern Gateway of the Highlands . . . . .	33
7.	Crawford Notch, White Mountains . . . . .	43
8.	The Holyoke Dam . . . . .	51
9.	Shore of Marblehead Neck . . . . .	54
10.	The Sea from Burial Hill, Plymouth . . . . .	58
11.	View from Mount Holyoke . . . . .	60
12.	Bar Harbor . . . . .	63
13.	Gorge of the Susquehanna, Maryland . . . . .	73
14.	Delaware Water-gap . . . . .	79
15.	Forested Slopes, Southern Appalachians . . . . .	82
16.	Spruce Forest in the Mountains of Virginia . . . . .	85
17.	Pittsburg and the Beginning of the Ohio River . . . . .	91
18.	Alleghany Valley at Franklin . . . . .	93
19.	Cumberland and the Narrows of Wills Mountain, Maryland . . . . .	95
20.	A Blue-grass Meadow in Kentucky . . . . .	101
21.	Waste Streams, Niagara Power Company . . . . .	109
22.	Harbor of Duluth and Superior . . . . .	113
23.	Mahoning Iron Ore Pit, Minnesota . . . . .	119
24.	Ore Docks, Lake Superior . . . . .	125
25.	Cuyahoga River, Cleveland . . . . .	129
26.	Shipping in the Chicago River . . . . .	133
27.	American Locks of Sault Sainte Marie . . . . .	135
28.	Duluth . . . . .	139
29.	Bridge across the Mississippi at St. Louis . . . . .	144
30.	Forests on Bluffs, Iowa . . . . .	149

FIG.	PAGE
31. River Front, Cincinnati . . . . .	156
32. Cottonwoods in Iowa . . . . .	167
33. University of Nebraska . . . . .	171
34. Avenue of Live Oaks, Savannah . . . . .	175
35. Orange Grove, Florida . . . . .	179
36. River Front, New Orleans . . . . .	185
37. Residences on River Front, Charleston . . . . .	188
38. Cotton Levee, New Orleans . . . . .	191
39. Cotton Wharf, Charleston . . . . .	194
40. Mississippi Steamer at Levee, Mobile . . . . .	198
41. Tennessee River and Lookout Mountain . . . . .	203
42. Vicksburg from the West . . . . .	206
43. Vicksburg and the River from the North . . . . .	213
44. Shirley House and Federal Camp, Vicksburg . . . . .	215
45. Chattanooga and Missionary Ridge . . . . .	219
46. Moccasin Bend and Chattanooga . . . . .	223
47. Shenandoah Valley at Luray . . . . .	225
48. Shenandoah River . . . . .	227
49. Cottonwoods in Colorado Springs . . . . .	233
50. Desert Vegetation, Western Utah . . . . .	239
51. Dust Whirl in the Desert . . . . .	244
52. Great Salt Lake . . . . .	245
53. Desert Valley and Dry Lake Bed, Utah . . . . .	252
54. Mountain Road, Ute Pass . . . . .	256
55. Bullion at Leadville Smelter . . . . .	260
56. Panning Gold at Cripple Creek . . . . .	265
57. Marshall Pass . . . . .	271
58. Pike's Peak Trail . . . . .	276
59. Pike's Peak Railway . . . . .	277
60. Appalachian Valley Lands ruined by Floods . . . . .	281
61. Appalachian Slopes denuded by Floods . . . . .	283

# GEOGRAPHIC INFLUENCES IN AMERICAN HISTORY

## CHAPTER I

### THE EASTERN GATEWAY OF THE UNITED STATES

COLUMBUS did not search for a new continent. He sought a new path to an old world. If he had sailed due west from Palos, he would have touched the eastern shore of North America where the Chesapeake Bay opens upon the Atlantic Ocean. But he turned his prows southward to the Canary Islands, that thence he might run due west along the 28th parallel, to the north end of Japan, which, under the name of Cipango, he found upon a map of his time. This point was twelve thousand miles distant, but reckoning the size of the globe too small, and the extent of Asia too great, he counted only upon a voyage of twenty-five hundred miles. Sailing westward from the Canaries, he found himself wafted by the trade-winds. Hence he daily reported to his officers and sailors a smaller number of miles than were really traversed, that they might not be scared by their fearful progress over the Sea of Darkness.

Thus, unwittingly, the discoverers of America were heading toward the West Indies. The Spaniard stumbled in at the Mediterranean portal of our continent; for the great seas which we know as the Caribbean and the Gulf of Mexico lie between the great lands, and are as truly a Mediterranean as those waters that wash the shores of Europe and Africa. Thus the West Indies, Florida, the mouths of the Mississippi, and the coastal plain about Vera Cruz became forever associated with the Spaniard. His power has gone, but he has sprinkled island and shore with geographic names which live.

As early as 1500, European craft began to visit the cod banks of Newfoundland, starting an industry which has been plied until the present time. Among these fishermen were French navigators, and it was not many years before Cartier entered the Gulf of St. Lawrence, sailed up the great river, looked upward upon the promontory where Quebec was to stand, and called at an Indian village at the foot of a small but rugged mountain of volcanic origin, which he named Mount Royal. The Indian village has given way to a great city, and Cartier's name has become Montreal. He is the first of those illustrious Frenchmen who made the map of the Great Lakes, and explored the Mississippi River to its mouth. Champlain, La Salle, Joliet, Marquette, Frontenac, — these are the names: Belle Isle, Montreal, Detroit, Prairie du Chien, St. Louis, Baton Rouge, — such are the memorials of French heroism and French occupation. The gateway was the St. Lawrence and the Lakes.

Meantime, in 1587, Drake had sailed into the harbor of Cadiz, and "singed the king of Spain's beard." In 1588 the sea-dogs of England joined with wind and storm and sunk the Spanish Armada, strewing the shores of the North Sea and of the Atlantic with the wrecks of Castilian greatness. Drake and Hawkins scoured the sea for Spanish treasure. Their hands were harsh, but in no other way could English shipping keep afloat, or English settlements survive in any land. The breaking of Spanish power opened the way to English colonies in America.

Where would the Englishman come upon American shores? The Spaniard held the islands and seas of the south; the French occupied the St. Lawrence; from the St. Lawrence almost to the Gulf stretches a system of mountains; they are not lofty, but they are continuous; they stand back a little from the sea. In the north the hills of southeastern New England lie between the mountains and the Atlantic. From central New Jersey to Georgia we find a flat or gently rolling coastal plain. Behind, everywhere, is the barrier, a low wall, rugged, however, and broad, — the Appalachian Mountains.

The narrow strip of lowland between the mountains and the sea was left to the Englishman. He made his home about Massachusetts Bay, on the Delaware, the Chesapeake, by the rivers of Virginia, and on the low coasts of the Carolinas to the Savannah. He forged the colonies into a chain, and began to push over the mountain barrier and through its passes until he had occupied Tennessee, Kentucky, and Ohio, and driven out the French. Then he

swept across the prairies, adopted the Western mountains as his own, and planted great cities by the harbors of the Pacific.

Conquering the Dutch, who had anticipated him in possessing the best Atlantic harbor of North America, he found a narrow but open and easy road, through the Appalachian wall, between the seaboard and the prairies of the Mississippi. The Eastern Gateway of the United States is the valley of the Hudson and Mohawk rivers.

The history of the Empire State gathers about this gateway. When the voyager from the Old World approaches the chief city of the New, he sees the southern shore of Long Island, and the line of Atlantic Highlands converging toward the Lower Bay. Then he passes the Narrows and enters New York Harbor. Leaving the East River on his right and continuing northward, he enters the lower waters of the Hudson. He may follow its valley for a hundred and fifty miles, and at every point the rise and fall of the tide will remind him of the ocean which he has left behind.

Eastern New York is occupied by a narrow belt of low mountains. In some places these mountains rise to moderate heights, and in others they are worn to their roots and form a region of hills and rocky ledges. These mountain ridges run north-northeast by south-southwest and are a part of the great Appalachian system. The Hudson cuts across them in a long diagonal, in its southward course from Albany to New York. This is most plainly seen in the Highlands. This range, built of hard and ancient



FIG. 1. The Palisades of the Hudson opposite Spuyten Duyvil.



crystalline rocks, enters New York from the northeast and leaves the state to the southwest, where it becomes the Highlands of New Jersey. Through it is cut the gorge of the Highlands, barely wide enough to carry the river, with steep slopes rising to the summits of Storm King, Crow's Nest, and Anthony's Nose.

If Hendrik Hudson had an eye for landscape, he did not lack for variety after he sailed the *Half Moon* through the Narrows. The forested flats and low hills of Manhattan on the east lay in contrast to the precipitous wall of the Palisades that followed him on his left for nearly forty miles. He doubtless did not recognize in their huge columns the outcropping of massive beds of ancient lava. When he reached Haverstraw Bay and saw the river broaden to three miles, we may safely think that his spirits quickened with the hope that the passage to Cathay had been found. But he was doomed to doubt as he began to thread the Highland gorge. When he emerged on the north the river was wide again, and its valley more spacious than he had seen it before. Going northward, the Catskills would fill his vision as he looked westward over a few miles of low country to the strong profile that ruled the horizon far along his course. Eastward he would see rough and rising land, but he could not see that here are the foothills of the mountains of New England. As the voyager passed the hundred-mile limit from the sea, he would find shoal water and many islands, and begin to suspect, what a few more miles of journeying would prove, that he was following a river toward its source,

and that he must turn back and seek in regions yet unknown a passage to the far East.

It remained for others to learn what lay beyond the site of Albany. Succeeding explorers climbed the slopes on which Albany is built, and thence for nearly twenty miles traversed a region of half-sterile sands to the Mohawk River bottoms, where Schenectady now stands. Looking westward, there appears a deep V-shaped gap in the uplands. Through this gap the river pours from the west. By this channel, in the closing times of the Ice Age, flowed the waters of the Great Lakes, depositing in the Hudson Valley the great body of sands that lies west of Albany.

The Mohawk Valley, or that part of it which now interests us, is a trench nearly one hundred miles long, extending from Schenectady westward to Rome, in central New York. Easterly it opens into the Hudson lowlands, westerly it widens into the plains of Iroquois, in other words, the flat bottoms of the greater glacial ancestor of Lake Ontario. Viewed from near the river, the valley appears to be about 500 feet deep, with an average width of flood-plain of a half mile. Seen more truly from the bordering plateau, it is a vast gap, 1500 to 2000 feet deep, its upper slopes several miles apart, lying between the great uplands on either hand. The parting of the waters is at Rome. From that point the streams enter Lake Ontario. Once pass this gateway, and the path is clear across the lake plains and over the prairies and plains to the Rocky Mountains.

South of the Mohawk are the uplands of New York, stretching from the Hudson Valley to Lake

Erie. On the east we know them as the Catskill Mountains. But these are only lofty hills with rolling tops, and descending by a precipitous slope, or escarpment, on the east. Seen from the east, along the Hudson River, this slope, with its crest, appears like a mountain range. It is really the edge, or end, of a plateau. This plateau, which is 3000 feet or more in altitude in parts of the Catskills, falls to an average of 2000 feet in central and western New York. The Mohawk gap lies north of the plateau, or may be said to be cut through the plateau along its northern edge.

North of the Mohawk Valley the land rises, at first moderately, and then more boldly, to the slopes and summits of the Adirondack Mountains. While these mountains, like the Highlands of the Hudson, are ancient and much denuded, they preserve a series of bold northeast by southwest ranges, so that there is no line or avenue, north of the Mohawk, along which a railway could be well constructed. Except for local traffic, the mountains are a perfect barrier to commerce and travel.

The physiographer can look back to an era when no Mohawk Valley existed, when the drainage of the southern Adirondacks crossed the state to the Pennsylvania region, and he can see that there is a Mohawk Valley because a belt of soft and destructible rocks, known as the Utica and Hudson shales, extends from the region of Albany westward, between areas of harder rock on either hand. The valley has a long and intricate physical history which cannot here be told. It must suffice to say that in ancient days there



Copyright by Chester D. Moses & Co.

FIG. 2. Adirondack Mountains about Clear Lake.

was no such valley, that its presence is due to a belt of destructible rocks disintegrating for long periods, that the ice sheet entered it and overrode it, that the waters of the Great Lakes poured through it for a time, until they were diverted to their present course, leaving the valley to become in due time the channel of human intercourse.

As the traveler, going up the valley, passes Rome, the bordering slopes recede on either hand and on the north are soon lost to view. On the south, however, he sees bold hills, to Syracuse and beyond. These form the northern slope of the Catskill-Alleghany plateau. The railway traverses a flat country, the bed of Lake Iroquois. This plain, studded between Syracuse and Rochester with elongated glacial hills, continues through western New York, south of Lake Ontario. It is a region of high fertility, and is now one of the garden spots of the United States.

The explorers and settlers of this part of New York found established here several powerful Indian tribes, — the Iroquois. A few generations before the white man came they banded themselves in a close alliance known as the Confederacy of the Five Nations. They called their country the "Long House." The Mohawks were the most easterly of the tribes, calling their fair valley the eastern gateway of the Long House, and they were its keepers. All the tribes, including Oneidas, Onondagas, Senecas, and Cayugas, were in a comparatively advanced state. They practiced agriculture extensively, lived in neat and comfortable cabins, possessed considerable industrial skill, were eloquent in public counsel,

and were the objects of widespread fear through their prowess in war. Whatever their progress, they were still savages, delighting in torture and given to occasional cannibalism.

Good camping grounds and natural highways have usually been found out by savage tribes, and often by wild animals, long before civilized man appears. Thus the Iroquois had made their own what Fiske calls the "most commanding military position in eastern North America." How far their power was due to qualities which they had inherited and brought with them, and to what measure it came from their environment and opportunity, is a question which neither the geographer nor the ethnologist is yet ready to answer. Whatever be the answer, the European immigrant met these sturdy aborigines, and found himself in alliance or at war. \* One avenue of approach to the Long House was by ascent of the Hudson and Mohawk rivers. A second was through the Champlain Valley from the St. Lawrence. A third lay along the eastern shore of Lake Ontario. Thus, from the first, the rippling waters and bordering flood-plains of the Mohawk were a frequented path, traversed by French, Dutch, and English in various contact of war and peace with the natives of the land. Of these the French were the first to invade the Mohawk country. Not far away, at Ticonderoga, Champlain, the first white actor on this stage, had aided the Hurons against the Five Nations, and had thus, by the enmity aroused, determined for the English the ultimate control of the region. A later invasion was made by the French along the shore of

Lake Ontario, but they were defeated and forced to retire. There were peaceful invasions also, for in the valley captive missionaries endured torture and sometimes death. Most heroic and famous of these is Father Jogues, whose fate has recently been commemorated by a shrine of his church, erected where he perished, on the edge of a glacial terrace south of the river. The final failure of the French to dislodge or convert the natives of the valley was fraught with weighty results in the history of the new continent. Had they won this great highway, they might in later years have maintained themselves on the St. Lawrence, and might now hold the keys of the New World.

It was the Hudson-Mohawk Valley which early guided the Dutch in their effort to carve a slice from the new continent. Under an English commander, Hendrik Hudson, they sailed up the river which bears his name. At the limit of navigation the Dutch later built Fort Nassau below the site of Albany and concluded a treaty with the Mohawk Indians. Its object was trade, and it went far to prevent French control of the valley. They built Fort Orange in 1622, and thus laid the foundations of Albany. In 1642 Arendt van Curler entered the Mohawk country, reported its lands as "the most beautiful that eye ever saw," and was later authorized to buy the "Great Flats," where Schenectady now stands. The old town and family names of the lower Mohawk still bear proud testimony to this wave of immigration, in the ever present Fondas, Schuylers, Sprakers, Sammons, Van der Veers, and Yosts of the river country.

The first white settlement in the upper stretches of the valley was made by the Palatines in 1723. Following the devastating wars of Louis XIV, thousands of these stricken people left their homes on the Rhine and took refuge in England. Some of these were sent to America under a compact to reimburse the English government for their passage and for the allotment of lands. After a period of great suffering, first on the Hudson and then on the lower Mohawk, a final removal brought them to the German Flats Patent, between Little Falls and Utica. Here each family received a liberal allowance of the rich alluvium and adjacent uplands of the valley, and their descendants have been powerful in the history of the state and nation.

The next wave of immigration which swept up the valley was English. In 1784 Hugh White passed the Hollanders of Schenectady and the High Dutch settlement of German Flats, and founded Whitestown on the upper river. His coming was the signal for a lively movement from the stony slopes of New England to the inviting fields of the Long House, to which the Mohawk was the only road. Then came the stream of emigrant wagons, bearing the names of Ohio and Indiana, then in the far distant West.

These successive invasions are vividly recorded in the layers of geographic names that are spread over New York. Manhattan, New Amsterdam, New York, — this is a sample of the record. But in this case one of the names is now only a historical relic. The Indian tribal names have attached themselves to river, lake, town, and county. The student of the



ice invasion gives the name of the Indian confederacy to the earlier and greater Ontario. Ontario itself is one of many melodious aboriginal names beginning and ending in *o*: Owasco, Otisco, Otego, Owego, Oswego, and Otsego. Happily these musical primitive names stay with many of our streams: Chittenango, Chenango, Unadilla, Genesee, Chemung, and Susquehanna.

The Dutch invasion has left plentiful memorials: Harlem, Tappan Zee, Kaaterskill, Stuyvesant, Rensselaer, or in the Mohawk Valley, Schenectady, Amsterdam, Fonda, and Schoharie. Palatine, Minden, Mannheim, and Herkimer, are memorials of the refugees from the Rhine, settling in the Mohawk country. The Englishman marked his presence by names from the mother country, though this habit is by no means so common as in New England, where the first settlers had come, with fresh memories, direct from the old home. Still, we have such names as New York, Westchester, Albany, and Rochester. Then come the records of the pioneer, or prominent citizen: such are Dobbs Ferry, Wappingers Falls, and, in greater numbers as we go west, Whitestown, Gilbertsville, Sangerfield, Smithville, Binghamton, or Coopers-town. Another stratum is composed of names great in our history, as Washington, Madison, Hamilton, Clinton, Steuben, or Fulton. And finally we discover that a curious shower of classical names fell in early days on central New York, the memorials of men who, in a pioneer region, revered the ancient culture. They may be counted by scores: Utica, Rome, Syracuse, Ithaca, Homer, Tully, Virgil, and many more.

The stream of travel has never ceased to flow, but has rather become thousand fold in the century which has passed. Before considering the Mohawk and Hudson valleys as a modern highway, however, it will be well to observe that they were the theatre of important military events in colonial times. English forts had been erected on the upper Hudson by the year 1709, and before the year 1712 the chain had been extended up the Mohawk to Fort Hunter, forty miles from Albany. In 1720, through the influence of William Burnet, son of Bishop Burnet and governor of New York, forts were built at Oswego and farther west at Irondequoit Bay. About the time of the French War, a number were built near the present city of Rome, or in the vicinity of the Oneida carrying-place. "These, and similar efforts on the part of the English, served to divert from the French into English channels a large Indian trade, and to make the route *via* Mohawk River and Oneida Lake, the shorter one between Albany and Canada, the one most generally travelled." The Mohawk and Champlain became thus the great highways trodden by hostile forces in the French and Indian Wars, until the French rule came to its end in Canada in 1760. Local histories are filled with exciting records of midnight attack, weary marches in captivity, and all the terrors of border warfare. Here, too, was fought one of the less-known but most pivotal battles in the struggle between the colonies and the mother country, the battle of Oriskany. On the south slope of the valley, a few miles west of Utica, the Dutch farmers rallied under Nicholas Herkimer, and defeated the

English and the Indians, who would otherwise have gone down the valley and supported Burgoyne in his campaign on the Hudson. The contestants on each side numbered but a few hundred, but the result is thought by many to have been decisive of the main issue of the war.

The control of the Hudson was far more vital to both Americans and British than the holding of the Mohawk. By its connection with the Champlain Valley it became the focus of strategy in the Revolution. While the colonial forces were still about Boston, Arnold had advised Dr. Warren that Ticonderoga and Crown Point be seized, both because they contained military stores and because they stood in the gateway of the north. Before the British army evacuated Boston, it was suspected that New York would be the point of attack, and General Lee, on his urgent request from Washington, was permitted to prepare for the defence of the city and the Hudson. No one can know what might have happened, if Clinton, hovering in the harbor, had not found that Lee was in New York, ready to defend it. To have gained the Hudson at that early day would have cut off New England from the Southern colonies and put to risk the independence of all. Plans for fortification went on after Clinton disappeared. The East River near Hell Gate, the Brooklyn Heights, and the Highlands to the north were included in the scheme.

When the British forces under Howe did make their appearance, in June, 1776, they were not to find the lower Hudson an easy conquest. They could drive Washington out of Long Island, and they could



**FIG. 3.** The Hudson Valley and the Catskills shown in Relief.

sail past Putnam's obstructions of the North River and win at Fort Washington and Fort Lee, but they could not get possession of the upper Highlands. When Sir Henry Clinton, in 1777, failed to subjugate the Hudson and make connection with Burgoyne, coming from the north, the most promising device of British strategy fell to the ground. American victory at Oriskany and Bemis Heights, and British failure on the Hudson, left the great highways of New York in the possession of the colonies. It was four years later, at Dobbs Ferry, on the lower Hudson, that Washington planned the Yorktown campaign. In the same old house, occupied as his headquarters, Washington and Carleton, in 1783, arranged for the departure of the British from American soil. Here the French allies had been received in 1781, and here in 1783, two days after the conference with Carleton, a British warship fired seventeen guns in honor of the American commander. These facts are now inscribed on this old mansion, and typify the importance of the Hudson Highlands throughout the long struggle.

In the pioneer days the Mohawk was considered a navigable stream, and immigrants and freight were conveyed over its waters in boats propelled by poles. Several breaks were, however, necessary; a first beyond Albany, because of the abrupt fall of seventy feet at Cohoes, a second at Little Falls, on account of impassable rapids over the barrier of hard rocks which the stream there encounters, and a third of two miles at the Oneida carrying-place, where the Mohawk is left to the east, and the winding course

of Wood Creek is followed to Oneida Lake. Early legislative authority was given for improving navigation at these points, and soon after 1791 a canal, three miles long, with five locks, was constructed at Little Falls, and a further canal conducted boats across the Oneida carrying-place. We read that the enlarged boats, with five men, could transport, between the terminal points of navigation on the river, twelve tons in twelve days. Long lines of wagons and stages also traversed the bottom-lands, making the valley a busy highway between the East and the expanding West.

A continuous waterway, from the tidal waters of the Hudson to the blue expanse of the Laurentian lakes, became now the subject of serious discussion. Enough of the geography was known to suggest the possibility of such communication, but the following order, issued to a commander on Lake Ontario, in 1814, shows also the extent of the ignorance that prevailed. "Take the *Lady of the Lake* and proceed to Onondaga, and take in at Nicholas Mickle's furnace a load of ball and shot, and proceed at once to Buffalo." "That means," said the perplexed officer, "that I am to go over Oswego Falls and up the river to Onondaga Lake, thence ten miles into the country by land to the furnace, and returning to Oswego, proceed to the Niagara, and up and over Niagara Falls to Buffalo!"

The demand for a water-route was strengthened by the danger that the growing commerce of the Genesee country would be diverted, either down the St. Lawrence to Montreal and Quebec, or by the Susque-

hanna to Philadelphia. It is difficult to assign credit for the suggestion of an Erie Canal. Probably the idea was conceived independently in several thoughtful minds. Such a prediction is said to have been made by Captain Joseph Carver in 1776. Elkanah Watson, describing a westward journey in 1788, voiced his "strong presentiment that a canal communication will be opened sooner or later from the Great Lakes to the Hudson." Gouverneur Morris is reported to have said, in 1803, "Lake Erie must be tapped and the waters carried across the country to the Hudson." He thought there should be a uniform declivity between the two, not taking account of locks and summit supplies of water. The legislature took up the matter in 1808, a survey was made, and in 1810 a commission was appointed. The project then fell into abeyance until revived by De Witt Clinton in 1817. Navigation was finally opened between Lake Erie and the Hudson on October 26, 1825. The price of transportation from Albany to Buffalo, about three hundred miles, gradually declined during the twenty-six years after the opening of the canal, from \$88 to \$5.98 per ton. Later, railway competition became effective, and transportation from Buffalo to New York, in 1885, was but \$1.57 per ton. Of the vicinity of Rochester it was said, upon completion of the canal, that her timber found market and floated away. Wheat quadrupled in price. The mud dried up, the mosquitoes, the ague and fever, and the bears left the country, and prosperity came in on every hand. In like manner the salt, gypsum, lime, and grain of Onondaga, where is now the great city of Syracuse,



**FIG. 4.** Down the Mohawk River from Palatine Bridge ; the Four Tracks of the New York Central Railway on the left ; the Erie Canal on the right.



found ready market. But it is not enough to cite these comparatively local results. The meaning of the Mohawk Valley is that the entire region of the Great Lakes and the vast prairie and mountain regions of the West became tributary to the rising metropolis on Manhattan Island.

A similar story has now to be told of railway communication through this valley. There was no railroad in America prior to 1826. In that year a horse railway, four miles long, was built at Quincy, Mass., for the transportation of granite from the quarries. In the same year the legislature of the state of New York granted a charter to the Mohawk and Hudson River Railway Company to build a road from Albany on the Hudson to Schenectady on the Mohawk, a distance of eighteen miles. This was the first chartered railroad in America. It was completed October 31, 1826, and at once carried four hundred passengers daily. This, it will be remembered, was soon after through traffic began on the Erie Canal. In 1833 a charter was granted for a road to extend from Schenectady up the river to Utica, a distance of nearly eighty miles. This division was in running order in 1836. A further link in the westward series, between Syracuse and Auburn, was finished in 1837, and from Utica to Syracuse in 1839. A curious argument was urged for a break in the chain of roads at Utica; namely, that otherwise it would become a mere way-station on a great line and its business would fail to develop. The discussion shows that the consolidation of the future was forecast at an early time. Gradually the line was completed

from New York to Buffalo, 450 miles, and became known as the New York Central and Hudson River Railway, or more commonly as the New York Central, one of the greatest railways of the world. Four tracks lie side by side from Albany to Buffalo, two being used for passenger traffic and two for the conveyance of freight. Owing to the abrupt descent of the valley slopes to the river, but two tracks lead from Albany down to New York. A great number of minor railways pour their tribute into this artery of transportation, and it is hardly true to call Buffalo a terminal point, since many solid trains each day push on without change both south of the lakes and across Niagara, through Canada, five hundred miles farther, to Chicago. Except at West Albany there is not a difficult grade or an embankment or trestle of any importance between New York and Buffalo, and with slight exception this holds good from Buffalo to the Rocky Mountains. Two thousand miles of splendid country are thus made tributary to the harbor of New York through the river gateway which we have described.

About twenty-five years ago a competing line with two tracks was constructed and called the West Shore Railway. It extends up the Hudson on the west side, along the Mohawk on the south side, and then closely parallel to the Central Railway to Buffalo. For the most part the same towns are served by the two lines, and the newer has now become an integral part of the older system, so that the New York Central virtually crosses the Empire State with a line of six parallel tracks. It should be added that the

second telegraph line in America joined Albany and Utica along the Mohawk Valley, being finished on January 31, 1846. A short line between Baltimore and Washington preceded it by two years.

~~\*~~ To sum up, the valley is now threaded by the ancient highways, the Erie Canal, six railway tracks, and innumerable telegraphs and long distance telephones by which New York converses with Detroit, Indianapolis, Chicago, and other Western cities. The passing up and down, day and night, of men, of thoughts, of commodities, is like the ebb and flow of tidal waves, whose course is only stayed as traffic rests on the docks of Europe and of more distant continents.

But it must not be thought that the Mohawk is the only road which has been sought out to the West. It is only a broader gate with a lower threshold. There are other great railways, but none of them passes the Appalachian belt at an altitude, as at Rome, of 445 feet. A brief comparison will be instructive. Take first the roads which traverse the Empire State from the seaboard. Much English capital was invested in the Erie Railway. Perhaps the flow of money would have been less free had its sinuosity and heavy grades been known. At 75 miles from New York it must attain a height of 870 feet to pass the Kittatinny Mountains. At Port Jervis the altitude is 442 feet; at Deposit, 1008 feet; near Elmira, 799 feet; and at Castile, 1401 feet, with some large embankments and difficult bridges. Likewise the New York, Ontario, and Western Railway, running to Oswego and the West, crosses difficult

divides, and rises and falls between low altitudes and heights of nearly 1800 feet. The Delaware, Lackawana, and Western Railway rises to 1932 feet at Tobyhanna, Pa., and in 27 miles descends to 745 feet at Scranton. Thence it passes into New York, where it varies between 846 feet and 1359 feet.

Of the roads which cross the Appalachians south of New York, the conditions are similar. The Lehigh Valley road from Philadelphia maintains a course below 700 feet for 100 miles, then in 30 miles climbs to its summit, 1728 feet, and in 20 miles more drops to 549 feet at Wilkesbarre. The Pennsylvania, one of the finest roads in America, is obliged to make at one point an altitude of 2161 feet, and has one section of five miles whose grade is 80 feet per mile. The Baltimore and Ohio road has its summit at 2620 feet. Farther south the facts are yet more striking, and it is less than twenty years since a railway first crossed the southern Appalachians.

An old writing, dating from 1634, makes reference to a company which bought from its Indian owners "the island of Manhattan, situated at the entrance of said river, and there laid the foundations of a city." Here were available lowlands lying by a secure haven, and they were seized instinctively as the home of a new community. As the inland waterways and passes became known, they showed that Manhattan Island was at one end of a natural highway. [A great terminal city has grown up because of the unrivaled combination of harborage and lines of interior communication.

New York could be no other than the chief city of the Western Hemisphere. Such a center must be on

the Atlantic shore, in the north temperate zone, for there commerce is most favored between America and the great nations of Europe. Manhattan Island has on either side many miles of water front, at whose piers the largest vessels can lie. A similar frontage is afforded across the North River by the New Jersey shore. Miles of wharfage stretch along the Long Island side of the East River. That tidal avenue leads to the protected waters of Long Island Sound, which carry the coastwise trade with New England. Southward the inner harbor leads by a narrow passage down to the Lower Bay, Raritan Bay, and Sandy Hook Bay. When New York shall have become the first city of the world instead of the second, she will still have ample room for the shipping of all nations to rest in her quiet waters.

The perfection of her harbor might not, however, have made her the metropolis but for the inland ways to north and west. Down to the completion of the Erie Canal she was surpassed by Boston and Philadelphia. The latter was the largest shipping point in North America. But when the grain and other products of the West began to float down the Hudson, the race was won for New York. Ships could come to her from foreign shores and get a return cargo on her docks. This was true of no other city. Philadelphia and Baltimore have no such favorable openings into the Mississippi Valley. Boston lies behind the Berkshire barrier. About half of all the foreign trade of the United States passes through the port of New York. If imports are considered, two-thirds enter this gateway.

The human history of the last three centuries was possible through the geographical unfoldings of the later geological periods. Imagine the northeastern United States as standing several hundred feet higher than now. There would be no water in the Hudson channel except what falls in the Adirondacks and on the nearer lands, and runs seaward. The sea border itself would be nearly a hundred miles southeast of New York. Raritan River would join the Hudson from the west. A land stream would come from the northeast, along the line of the East River. There would be no harbor; there might be a modest town at the confluence of the rivers. Now suppose the eastern edge of the continent sinks slowly down to its present position in reference to the surface of the sea. Eighty miles of lowland would be buried by the waters. The fresh water of the rivers would be checked and mingled with the brine of the Atlantic. The tide would ebb and flow among the bays and coves around Manhattan, and its pulse would be felt within the pass of the Highlands and far beyond. Such was the history, long before man, even the savage, appeared. The region was elevated and dissected by the streams. Long courses of rock decay wore down the crystalline masses of New York island to a lowland, only that they might be more fiercely attacked by the drill and dynamite of modern days. The softer rocks that lay over and behind the Palisades lava were disintegrated and swept away. Then came the long submergence and the "drowning" of the streams, giving deep waters for ships. And the tides going in and out serve as a broom to sweep

the channel. And, where the tidal scour is not enough, man anchors a scow and drives a steam shovel through the slime, aiding nature.

We may add another short chapter. At the close of the glacial time the sinking of the land had gone farther than at present. Much of Manhattan was covered with water. The Hudson estuary was deeper and wider than now. In these deeper and broader waters, at many sheltered points, fine muds settled between the present sites of New York and Albany. These muds are often clays, fine, massive, and blue, which make the Hudson Valley the greatest brick-making district in the world. The connection is simple, — unlimited clay, a tidal river, and a metropolis to be built. The muds are not all clays. Often they are coarse and should not be called muds but sands and gravels laid down in deltas, where the Croton, Fishkill, Catskill, Mohawk, and Hoosick discharged into the long body of tidal waters. We read the record again: uplift, and long denudation and valley-making; submergence, greater than now, with soft deposits along the valley; a moderate uplift, bringing in present conditions and followed by the advent of man.

If clay were not enough, a peculiar limestone is found at Rondout, which, when ground, affords the finest cement. The marbles of Tuckahoe, the brown-stone of the Connecticut Valley, and the granites of New England are not far away, and, perhaps most important of all, a half-dozen trunk railways bring the anthracite coal by easy hauls to the docks of the North River. A great city was inevitable.



FIG. 5. Roseton Clay Beds and Brickyards, on the Hudson. The Terraces are due to the cutting of the Clay to Successive Levels. Photograph by H. Ries, in "Bulletin of New York State Museum."



The development of human life along the Hudson and Mohawk highway has been parallel to that of New York. Of forty-one communities, having the rank of a city in the state of New York, eleven are on the Hudson and six are on the Mohawk. If we extend our view from New York to Buffalo, four-fifths of the population and nine-tenths of the wealth of the Empire State are found within the counties bordered or crossed by the Hudson River and the Erie Canal. The east bank of the Hudson is almost a continuous suburb of New York up to the Highlands. Newburg is at the north gate of the Highlands, and Kingston has grown up at the mouth of the Wallkill, a tidal branch of the Hudson, whose valley offers a natural road from the coal region. The Hudson Valley, about the entrance of the Mohawk, forms a natural center of population. Here is the head of navigation, and an open road to the west and to the north. These conditions centered here the lines of travel from New England. There is no good gate opening eastward, but the Westfield and Deerfield valleys of the Berkshires find their best western outlet here. A fall of water due to blockades of glacial origin has given rise to Cohoes, while shipping lines the river borders of Albany and Troy.

The half-dozen cities of the Mohawk are good illustrations of physiographic control. Cohoes has been named. Schenectady, with thirty thousand people, lies on the great flats, where the river issues from the uplands upon the old estuary ground of the Hudson. The river itself has dug away the sands of its ancient delta and smoothed out a few square


miles of alluvial floor. Farther up is Amsterdam, with twenty thousand people, a center for the manufacture of knit goods and carpets. Little Falls, a small but busy city, developed from an ancient carrying-place, and by reason of its water-power, the primal cause being a dislocation of the rocks, which here crosses the river from south to north. The harder, older, and deeper rocks were brought up, and the river has not yet finished its task of grading its valley bottom: hence the "little falls." Utica, a city of sixty thousand people, is determined by an old fording-place, and receives tribute from south and north by railway lines which reach New York across the uplands, and open to the St. Lawrence through the Adirondacks or along the Ontario lowlands. Rome is built at the old Oneida carrying-place, where little cargoes were borne over from the Mohawk and sent down the sluggish waters of Wood Creek toward Oswego.

Going westward, Syracuse originated by reason of the brines found by boring to the underlying gravels, but has other reasons for her growth, among which is her position along the great highway from east to west. A like word may be said of Rochester, while Buffalo finds assured greatness in being the point of transshipment at the foot of Great Lake navigation. Erie in Pennsylvania is the natural correlative of Philadelphia, as Buffalo is of New York. But Erie is small and Buffalo is great. The explanation is the Mohawk-Hudson Valley. So far as Philadelphia has a natural gateway to the west, therefore, it is not Erie but Pittsburg.

If we consider the commonwealths which represent the thirteen colonies, New York, more truly than Pennsylvania, is the "Keystone" state. On the one hand is New England, which, as we shall see in the following chapter, stands in many ways by itself. On the other, Pennsylvania is an Appalachian state and is closely related to Maryland and Virginia. New York, with its harbor, its artery of travel, and its frontage on the Lakes and the St. Lawrence, is the key to the West and the North. She is not hampered by the mountain barriers of the South, nor is her traffic hindered by the Falls of Niagara, nor by the rapids and the winter ice of the St. Lawrence.

We do not yet know how much physical environment molds mental and spiritual life. We cannot trace geographical influences in a complete way, but we gather hints of their power. The Hudson country could not fail to be richer in tradition and riper in its harvest of thought than some other portions of the commonwealth in which it lies. For geographic reasons it has an older civilization than the interior. The old Dutch life was followed by an incoming from England. These elements reacted on each other, as both had felt the shock of migration across an ocean. Their social and their physical environment was new.

Dwellers on the lower Hudson must ever feel a more or less conscious relation to the sea and have a sense of neighborhood to its farther shores. The ebb and flow of the tides and the passing of ships are tokens of a larger life. More tangible in its effects, perhaps, is the near metropolis. Commercial opportunity has brought wealth. In some measure, homes



**FIG. 6. Looking into the North Gateway of the Highlands from a Point near Newburg, N.Y.**

on the Hudson may show how wealth has conspired with the higher tastes to find serene living where nature is beautiful. It would be presuming to assign nature's share in the literary unfoldings of the valley, but its literature cannot be less than a natural growth from soil and atmosphere. The breath of the sea is here. Cities and villages are old enough to have traditions. Mountains, too rugged to bear but a scanty forest, rise from the borders of the river. But a few miles away are the mysterious gorges and untrodden woods of the higher Catskills.

Unless one is plying the river for trade, Irving is the best guide to the Hudson. No other has so fully given speech to her life. We do not know the measure of intimate influence that comes on a writer from his surroundings, but Irving assuredly laid hold upon the traditions and the history of the region, and embodied, or shall we say created, the typical spirit of the great river. Did he not in some measure do both? His birth was in the year in which the British troops left the city of New York not to return. As a youth he voyaged up the Hudson, and made many journeys along the Hudson and Mohawk in the years that followed. In the satires of the Knickerbocker story he reveals his knowledge of every phase of local history and every nook of the Hudson country. His tales of humble domestic scenes in the "Legend of Sleepy Hollow" are pictures, and the woods in which Rip Van Winkle slept are the living forests of the Catskills. The real Hudson becomes more real because idealized and seen through the serener atmosphere of the older time. Not far from the Hudson

lived Andrew Jackson Downing, the landscape architect, forerunner of a generation that is to increase, of men who are to enter into the heart of nature and preserve her freshness and beauty, while subduing her to the uses of man.

The poet has not been forgetful of the river. Halleck's lines in praise of Weehawken may have a strange sound, in the light of modern changes, but Drake's "Culprit Fay" can hardly pass out of date so long as the imagination touches human feeling. This, perhaps, is the poem of the Hudson River, but we turn rather to Bryant. His "Night Journey of a River" must have been inspired by the river of his home, and nothing could better express the subtle ties that bind the river and its greatest city than these lines from "A Scene on the Hudson":—

"River! in this still hour thou hast  
Too much of heaven on earth to last;  
Nor long may thy still waters lie,  
An image of the glorious sky.  
Thy fate and mine are not repose,  
And, ere another evening close,  
Thou to thy tides shalt turn again,  
And I to seek the crowd of men."

Within the domain of the Hudson, also, for many years John Burroughs has lived in his cottage, and gone forth, in winter and in summer, to share and interpret the life of her birds and forests. Curtis made his home where river passes into ocean. He was a lover of the Hudson, and voices his loyalty, if such it may be called, to his own land in his fine parallel between the Hudson and the Rhine. "Its

spacious and stately character, its varied and magnificent outline, from the Palisades to the Catskills, are as epical as the loveliness of the Rhine is lyrical. The Hudson implies a continent behind. For vineyards it has forests. For a belt of water, a majestic stream. For graceful and grain-goldened heights it has imposing mountains. There is no littleness about the Hudson, but there is in the Rhine. . . . The Danube has, in parts, glimpses of such grandeur. The Elbe has sometimes such delicately pencilled effects. But no European river is so lordly in its bearing, none flows in such state to the sea."

## CHAPTER II

### SHORE-LINE AND HILLTOP IN NEW ENGLAND

NEW ENGLAND is a geographical province. The Berkshire barrier runs from southern Connecticut to its culmination in the Green Mountains of northern Vermont and divides New England from New York and the West. Northward, the St. Lawrence is the natural boundary, though its lowlands belong to another political division. On the east and the south is the sea.

- It has, however, other elements of geographic unity. It is, with small exceptions, a very ancient land, as the geologist counts time. Some of its areas have a rocky foundation which is among the oldest known, comparing with the Adirondacks, the Piedmont and Blue Ridge of the South, the core of the Black Hills, or the ancient lands between the Great Lakes and Hudson Bay. Other parts of New England have a less but still incomprehensible antiquity; such are most of the Green Mountain and Berkshire region and the districts about Boston and the Narragansett. The rocks of the Connecticut Valley in Massachusetts and Connecticut are much younger, yet their age must be reckoned in millions of years. Geologically youthful are parts of Cape Cod, the



larger islands, and the barrier beaches and marshes of the southeast.

It may be a more useful description, if we say that about all of New England has felt the disturbing forces that build mountains. Most or all of the region was once a sea bottom, receiving waste from other lands. These sea floors became land by uplift, and by powerful folding of the sheets of rock, forming mountains, of which the Green and White Mountains are but remnants. But these were not the only regions roughened by elevation. If we study the rocks of Rhode Island, or about Boston or Worcester, we shall find them as much disturbed and tangled as on the slopes of Greylock or Mansfield. And they are usually crystalline, for by crushing, by the action of water, and in some cases of heat, they have been changed from their original condition. The limestones have become marbles in Vermont and along the Housatonic; the sandstones, made from waste of still older rocks, have turned into schists, and the muds have become shales or slates.

If such has been the change within, the change of outer form has been as great. A land of bold mountains has become a region of rough hills. This is one of the ways in which the great age of the land might be determined. Southern Maine and New Hampshire, eastern Massachusetts, southern Connecticut, and all of Rhode Island, are a rough lowland. Northern and western New England may originally have been higher than the south and east, — we cannot know, — but all was lofty and perhaps Alpine. Time enough has passed to make the beds of rock, transform them

into mountain ranges, and wear them down nearly to the level of the sea.

At some epochs of this history volcanic fires were active, lavas were poured out, and explosive eruptions, like those of Krakatoa and Pelée, sent forth clouds of gases and spread sheets of ash over land and water. Cones were built, which have been long destroyed. Their roots may be found at many points along the rocky shores and far inland. Sheets of ash and lava still bear testimony to these days of fierce changes when New England was an unstable region like the Caribbean and Mediterranean.

The reliefs of northern New England are not so well known as those of Massachusetts and the region to the south. The three more southern states have been completely covered with mapping by the system of contours, while in the northern states only patches here and there have been thus surveyed. In northern New England we find the Green Mountains. On the one hand are valleys and lowlands leading to the Champlain and Hudson, and on the other are the slopes and narrow, fertile terraces and flood plains of the Connecticut. Rising to the heights of the White Mountains, we pass on to the moderate elevations of central and northern Maine, culminating in Katahdin; southern Maine and New Hampshire are like southern New England.

Through Massachusetts and its southern neighbors the crests of the uplands fall in with one another so well that we may call the general surface a plateau. Viewed from the uplands in western Massachusetts, the surrounding uplands have an even sky-line, and

we may imagine a continuous surface, which has later been broken by cutting valleys through it. We can thus think of an upland passing from the Berkshires across the present Connecticut Valley, merging with the lower region, where Worcester stands and from which Wachusett rises. Then we can picture the upland slanting still farther down, east through Massachusetts, and southward through Connecticut and Rhode Island, to the sea. In other words, if we could fill up all the valleys, we should have a plateau descending from the Vermont and New York border to the sea. It would be about two thousand feet above the sea in western Massachusetts, about one thousand feet around Worcester and in eastern Connecticut, and of less altitude toward the Atlantic and the Sound. Physiographers have given attention to this slanting land surface. Not seeing how it could otherwise have been formed, many think that the ancient mountains were worn nearly to sea-level, that the resulting lowland was uplifted, and more to the northwest, and that the Connecticut, Westfield, Housatonic, and other valleys have since been sunk into it. Whatever be the truth, this conception helps us to see geographic forms truly, and to avoid supposing that southern New England is an orderless jumble of rugged lands.

Interesting results follow from these contrasts between northern and southern New England. Forests prevail in one and homes in the other. Maine has the size of the other five states combined, but only one in eight of the inhabitants. Vermont has two towns of more than ten thousand people; Rhode Island has

eight. Maine has seven such centers; Massachusetts has forty-seven; while New York has but forty-five. Northern New England has no city of sixty thousand people, and southern New England has fourteen such communities.

The chief drainage systems have a common direction—the greater rivers flow southward. They are mainly longitudinal streams, by which geographers mean that they follow the lines of mountain foldings. Parallel ridges and troughs result from such disturbances, and such troughs controlled the ancient streams. These may have slowly shifted their courses in the ages of their development, but they have not departed from parallelism with the mountain ranges. All the great streams are tidal at their mouths, but some have sunk their inland valleys more effectively than others. Thus the Connecticut has graded its course close to sea-level across Massachusetts, while the bed of the Housatonic at Pittsfield is a thousand feet above the tide.

In another way New England has geographic unity; it was all invaded by land ice in the Glacial Period. For detailed accounts of the Ice Age, the reader should look to special works; it is within our province here to see in a general way the changes wrought on the face of the land. The chief movement was from the north and northwest, down upon the Sound and the Atlantic. That the ice was thick, we know, because it overswept Katahdin, Washington, and Mansfield. And we have more startling proof in the fact that it disregarded the southern trend of the western mountains and valleys, and flowed freely

across them on a diagonal. Many years ago this was shown by Sir Charles Lyell and others, who observed trains of boulders near Richmond, Mass., which were carried and distributed in this manner.

We know that the enveloping mantle crossed the place of the present Long Island Sound, and heaped its parallel belts of moraine in Long Island. These moraines run from east to west, and similar belts are found in southern Rhode Island, from Point Judith to Watch Hill; along the southern part of Cape Cod, from Buzzard's Bay to Nauset Beach; and along the shores of Martha's Vineyard and Nantucket. These and others are the terminal moraines of the New England ice sheet. More full of meaning in our present study is the heavy scoring which the surfaces of soil and rock everywhere sustained. In a country which has not been plowed by the ice, soils develop by the wasting of the rocks for long periods. Hence, below the proper soils, the surface rocks are discolored or half-disintegrated. Nearly everywhere in New England these old soils and corroded rocks were pared away, and a new cover of "drift" laid upon the freshly exposed and unchanged bed-rock. This drift was formed by mingling, in and under the glacier, the rock fragments eroded by the ice, and the preglacial soils lying to the north and northwest. We are not to understand that this new and mixed material had been pushed for long distances. Some of it was far-traveled, as we know by boulders from remote ledges, but most of it came to rest again within a few miles of the place of its origin.

The records of this scoring are often to be seen



**FIG. 7. Crawford Notch, White Mountains.**

when the bed-rock is stripped. They are the glacial grooves, or *striæ*, and also the rounded or elliptically carved crests of exposed rocky hills, which were attacked and polished into their present forms by the overriding ice. We are not to suppose that the glacier removed a large thickness of the rock from the general surface. But exposed and narrow elevations may have been planed away for many feet, and valleys may have been deepened where powerful ice masses occupied them for a long time. Thus the complexion of the country was changed not a little by giving the surface rocks and soils a hard push and a new distribution.

Much of the drift consists of clay and stones of various size, promiscuously mingled and spread, sometimes evenly, over the land. Moraine heaps and the smoother cover of this stony clay are often thickly sprinkled with the great boulders which are so common a feature in the landscape of New England. Sometimes these great stones are delicately perched, and some are known as rocking-stones, whose many tons may be swayed by the push of a hand. Professor Shaler has ingeniously shown, from these, that no violent earthquake could have visited New England since the Glacial Period, else would these stones have rolled over and assumed a more stable position.

There are other sorts of glacial accumulation of land waste. Glacialists give the name *drumlin* to hills of curving crest, parallel to each other and trending in the direction in which the ice moved. Such are the islands of Boston Harbor, though their curves have been marred, as sea waves have trimmed

the outer edges of these half-submerged glacial hills. They abound, unaltered, however, about Boston and Worcester and along the lower Merrimac. Such a hill is a mass of the boulder clay, or "till," modified in form by the ice moving over it. It was formed under the ice, therefore, while the moraines gather chiefly about its edge. Long gravel ridges occur in some parts of New England; they often have steep slopes, a sharp crest, and are serpentine in their curves; they may be flanked by swamps, and thus the crest line has not seldom been adopted as the line of a roadway; ridges of astonishing length are found in southern Maine. They were usually deposited in the beds of streams coursing in tunnels under the ice sheet.

Interruption of the direct flow of surface waters to the sea is a most striking result of ice work. Sections of old valleys were clogged with drift. Lakes formed behind the dam, and in sinking new outlet courses, rapids and waterfalls have been formed. In a variety of other ways lakes came into existence, and thus to the glacier we must attribute the thousands of lakes or tiny ponds that form the eye of the landscape everywhere and minister in many ways to the needs of man.

Thus two sorts of geological events have affected — New England everywhere, — the ancient mountain building and the recent invasion of the ice. These have deeply influenced human life in the few centuries in which civilized men have dwelt here. The rocks are, as a rule, profoundly changed by disturbing forces, or they are deep-seated masses brought to the



surface by denudation. Hence granites, marbles, and slates abound and furnish the best building materials.

As early as 1737 the Boston builders began to gather and dress granite boulders. The walls of King's Chapel in Tremont Street grew thus out of the fields.

In 1825 the quarries at Quincy were opened, the chief occasion being the building of the memorial on Bunker Hill. Then the use of granite began to be general, until every New England state opened its stores of this rock, soon to appear in every eastern city and burial ground. Great excitement was aroused, when, in 1697, some one found limestone at Newbury, in Massachusetts. Thirty teams a day were soon hauling it from the newly opened quarries, for heretofore the colonists had depended on the shells of the seashore for their lime. But most of New England limestone is in the form of marble and lies along her western border, in Connecticut, Massachusetts, and Vermont. Another product of geologic change is the beds of slate, made from ancient deposits of clay. As Vermont leads all the states in marble, so it is second only to Pennsylvania in this product, while a few quarries are open in Maine and Massachusetts. Isolated mineral industries are afforded by the mica deposits of Grafton County in New Hampshire and the corundum of Chester, Mass.

The soils are the waste of these ancient rocks, stirred by the glacier and mingled with the products of plant decay. It is not merely a modern notion that New England soils are somewhat barren. An old writing on Virginia, dating from London in 1649, says of the Northern colony, "Except for the fish-

ing there is not much in that land, which in respect of frost and snow is as Scotland compared with England, and so barren withal that, except a herring be put into the hole that you set the corn or maize in, it will not come up." This would scarcely appeal to the gardeners about Boston, and doubtless the writer had not looked upon the lands that were to become the tobacco fields and peach orchards of the Connecticut Valley.

Yet it is true that the uplands predominate, and the soils of the uplands are not rich. Much of the fine soil material of the preglacial time has been washed into the sea by the streams that flowed forth from the ice sheet. The drift, from which the true surface soil is derived, contains a large proportion of coarse waste, broken mechanically from the bed-rock by the plucking and grinding of the ice, and thus the minerals are not ready for the nutrition of plants. The soils are often thin, or lie on steep and bouldery slopes, and the range of crops is limited by the shorter summer and severer cold of the winter months. The decline of general agriculture has been a central feature in the later history of New England. No end of writing has found here a theme, and a few of the writers have viewed the change with cheerfulness, but more with despair. It is not inspiring to see family mansions decay, farms abandoned, and untended roadways furrowed with incipient ravines, or to find villages in stagnation, with churches neglected, ancient academies abandoned, and the ambitious children of the fathers gone to the cities, the prairies, and the Pacific coast. But the history could not be

different in the geographic unfolding of the United States.

While a compact people of English birth were held together on this first American ground, they forced a living from the soil, and built at last the New England of fifty and a hundred years ago. But the prairies and the great Northwest have settled the case for the farmer in New England. He must change his occupation or give himself to special forms of tillage, and while there is hardship and pathos in the change, the end is not to be deplored. There are weights to be thrown into the other side of the balance. Shaler has shown how the very coarseness of the soil elements insures permanence: these minute, pebbly fragments of rock will gradually disintegrate and yield, in soluble form, the elements needed by plants, and the soils may continue to have moderate fertility long after the soils of the Mississippi Valley are exhausted, or begin to require large use of fertilizers. And it is wholly to be desired that much New England upland should relapse into forest. Mountainous and glacial conditions have combined to fit these lands for trees and for nothing else.

In some neighborhoods new methods of tillage, carried on with greater intelligence, and often involving special crops, for which the soil is fit or for which there is local demand, are beginning to change the face of rural New England. New and better roads will bring into contact with the general life many corners that have been smothered by their isolation. As population grows, the swamp lands, of which there are some thousands of square miles,

will begin to be reclaimed. They are in patches in the interior and along the shore-lines, and are either glacial or tidal in origin. They will be largely reclaimed and become as productive lands as anywhere lie under the plow.

Nature, as we have seen, invites the permanence of the forest in New England, and man has not yet completed his defiance of her will. Fifty years ago it was thought impossible to exhaust the pine forests of Maine; by 1880, however, the Pine Tree State was importing white pine from Michigan and Canada, and her lumbering was mainly upon the spruce, which in early days was left almost untouched. Still, the white pine was not destroyed; for in many areas the second growth has been spared, forest fires have been restrained, and the beginnings of rational forestry are practiced. Intelligence is growing and conviction is deepening in New England, and there is hope that the lumberman's ravages in the White Mountains may be stayed, keeping the crown of glory on the uplands, and saving the valleys from destruction by floods of water and by the hillside waste which devastates the fields of the riverside.

Even Connecticut is a much forested state. Her stirring towns, growing cities, and farms of the lowlands appeal first to our thought; but a forest map of Connecticut carries the green, used as a symbol of the woodland, widely over the state. Such a map seems more green than white, and points to wide areas on the east and west of the central river suited only to the growth of trees.

A recent writer has drawn a picture of the neigh-

boring state,—its western half, — “In Wildest Rhode Island.” A strange title is this for the smallest and most densely peopled of our states, and one of the most ancient, centering in great towns and busy villages with humming spindles, on the waters of Narragansett. But draw a line from north to south, dividing the little commonwealth into halves. West of the line are ten back townships and less than six per cent of the population of Rhode Island. Here are some of the well-worn mountains of New England. Rightly do we call them hills, for they show but a few hundred feet of relief. In five of these townships, during the last century, there was a loss of one-third to more than one-half of the people. All the features of New England rural decline are here; and whether forests, and estates of the rich, or truck farms, towns, and electric railways will cover these lands in future days is a question unanswered.

Yet another persistent thread of New England history began to take form in glacial times. Before these days the streams had flowed so long in their courses that they had smoothed their channels and made easy grades to the sea. When the ice finally disappeared, these old valleys were often left in a condition of blockade. Banks and massive piles of drift lay where the waters had run, and they forced the renewed streams to seek other courses. In a short distance, commonly, the old valley would be resumed, but in passing around the barrier the river would sink its channel upon the rocks, forming waterfalls, or rapids. This concentration of descent has created the available water-power of New England



FIG. 8. The Great Dam at Holyoke ; 35 Feet High, about 1000 Feet Long, and with 12 Feet of Water on the Crest.

and determined the sites of many of her towns and cities.

The Rev. Samuel Peters, who, being a Tory, took refuge in London in Revolutionary days, had visited the Connecticut Valley, and described the river as flowing fast enough at a certain point to float iron crow-bars. Here grew up Bellows Falls, with its factories; and the visitor may read more sure proofs of the river's power in the pot-holes that pierce the rocky bed, and in the terraces that rise like stairs on the slopes above the town.

Several inland cities have a similar origin. Such are Lewiston in Maine, Manchester in New Hampshire, and Lowell, Lawrence, and Holyoke in Massachusetts. Lowell is a splendid example, founded three-quarters of a century ago, and having now nearly one hundred thousand people and about one thousand factories and mills of various kinds. This great center of production was located by a physiographic feature,—the falls of the Merrimac. For a similar reason Holyoke has grown up on the Connecticut River, with its great granite dam, its spacious raceways, and its enormous business, in which, as well as in population, it has become a rival of its near neighbor, Springfield.

Some cities combine the advantages of water-power and tidal highways. In other words, the falls or rapids of glacial origin occur at the head of tide-water, and cities would naturally follow,—such as Pawtucket, Norwich, Fall River, and Augusta. It is to be remembered that in many cases, as notably at Fall River, water-power has been largely supplemented by steam, since, once established, a manufacturing

industry is likely to develop in a center made famous by it far beyond the limits of the available power.

The state of Maine has about 230 miles of shore-line, reckoned in a direct line from Kittery to the St. Croix River. But if one should follow the border of all its bays and headlands, and encircle all the islands, he would traverse more than two thousand miles of beach, so intricate is the labyrinth of the Pine Tree State's ocean border. For the most part it is a rugged shore. Rocky headlands stand out to sea, and meshes of landlocked waters extend inland from ten to forty miles. The only part of the shore-line that is not thus broken is between Kittery and Portland, at the southwest. All the rivers have tidal mouths, and illustrate in their cities, in a small way, the conditions of London, Bristol, and Liverpool. These deep valleys are commonly explained as due to river work when the land was higher than now, with submergence following. It is the same story as that of the Hudson, but we do not know how much the channels were deepened by glacial ice. Glacier, river, and the sinking of the lands may have joined with the sea in fashioning such a shore-line.

Massachusetts has also a rough shore-line, but with more variety than in Maine. Long strips of sandy beach alternate with coves and deep and spacious bays. Cape Ann is a well-worn but still jagged headland, thrust out among the breakers of the Atlantic. Tipped with granite and girded with volcanic dikes, this land is not easily overcome by the onset of the waves. On the south a secure haven has led to the growth of Gloucester; but to the north



are the long, smooth curves of Plum Island and Salisbury Beach, kept apart only by the outflow of the Merrimac. These are low and sandy barrier beaches, built and shaped by wave and wind, and backed by salt marshes and quiet bays, south and north of Newburyport.



FIG. 9. A Rocky Shore, Marblehead Neck.

South of the Cape is Boston Bay, with a ragged shore, but not so broken as in more ancient days. The work of waves and currents tells its own story, if we study a large-scale map. Low and narrow beaches have been built, joining former rocky islands to the mainland, giving us Marblehead Neck and Nahant. The drumlins are wave-worn and have helped to furnish the lines of waste that now offer a continuous succession of curved shores from Point Shirley to Point of Pines. Such is the story of Nan-

tasket Beach from Long Beach Rock to Point Allerton. These beaches and the islands that lie between seclude Boston Harbor from Boston Bay and protect the shipping from Atlantic storms. The Mystic, Charles, and Neponset rivers have shallowed the fringes of the harbor, and man has contributed his own large share to create dry lands for the Eastern metropolis.

Then Cape Cod sends its magnificent curve into L the Atlantic and incloses the waters of Massachusetts Bay. Here the hard rocks give way, and lands of modest altitude are composed of youthful strata mantled with glacial drift and shifting sand-dunes. Lakes and swamps abound, and smooth shore-lines rule from Buzzards Bay around to Provincetown, and, indeed, nearly everywhere, also, on the inner shore of the Cape. The narrow eastern arm of the Cape was once wider than now, but the waves, attacking from the east, have trimmed the shore-line, and the resulting land waste has been swept up and down the shore, or drifted out into deeper waters. Southward, Nauset Beach and Monomoy Island have been formed. Northward, the sands have been carried around to the west and south, building the hooked spit that incloses Provincetown Harbor. Sparse population, little towns, and limited tillage of the soil, — such is the law that nature lays upon this frail and exposed foreland.

Much that may be said of Cape Cod is true of Marthas Vineyard and Nantucket. The eye needs but little training to mark the moulding of waves and currents on these shores. Nantucket is a crescent,

with its concave shore fronting the mainland, trimmed here and built out there, until the lines are smooth and flowing. In old days many shallow bays pierced the southern lowlands of Marthas Vineyard. Every intervening headland, built of yielding materials, has been shortened in, and the eroded material swept across the openings of the bays, making them into lakes.

Turning again to the mainland, we may contrast the ragged outline of Buzzards Bay with the smooth borders of Cape Cod. To the westward, the edge of the lands resembles that of Maine, but is not so continuously irregular. Narragansett waters are, however, deeply landlocked, and represent a "drowned" trunk stream, whose chief branches were the Taunton, Blackstone, and Pawtuxet. Here we have the great physiographic feature of Rhode Island, and it is hardly too much to say that the existence of the state as an independent commonwealth hinges upon it.

In Connecticut a dozen large towns and cities line the waters of bays or stand near the mouths of tidal streams. The Mystic, Thames, Niantic, Connecticut, Quinnipiac, Housatonic, and Norwalk are the tidal rivers, great and small, that enter the sound. The Thames is followed by the tides to Norwich, fifteen miles, and the Connecticut to Hartford, more than forty miles. The fading out of the uplands makes a shore-line railway possible, and the protected waters of Long Island Sound offer a parallel highway for coastwise communication.

New England has been compared with Northern Europe. These regions are alike in important ways,—

in their low and ancient mountains, in the prevalence of the glacial ice, and in their broken shores. Every city of the sea border has a story well worth the telling, and none of more variety and fascination than peaceful and ancient Salem, with its decaying wharves, which no more receive consignments from the remotest lands. As with New York, so in a less striking way here, the lines of inland communication have turned the balance. Boston has a more spacious harbor than Salem, and from Boston the great railways lead out westward. Where the railways meet the shipping gathers also, and Boston is the one great port of New England. Portland, Providence, and New London must be content with coastwise shipping because Boston is the New England link between foreign lands and the interior of our own. But the records of the past may well remind us that Salem once led the shipping of the United States, and Providence sent more vessels from her harbor than set sail from the piers of New York.

Many New England coast towns have seen their life transformed through the decline of fishing. Several causes have led to this decay. Canadian catches have been admitted on more favorable terms; the Chesapeake, the Great Lakes, and the salmon of the Pacific have come into competition; other marine foods have grown in favor; and preservation in various ways has made the rivalry of remote regions effective. Hence the houses of Marblehead may be as quaint and her streets as narrow as they were, but shoes have taken the place of the fisherman's schooner and the sailor's yarns. Yet New England has her

calling from the sea and can never turn her face alone to the land. Even fishing thrives, but centers itself at a few places, as at Gloucester, after the more effective fashion of modern times. Many a fisherman has turned to lobster-catching, which saves him from long and dangerous absences from home, or he fully with-



FIG. 10. The Sea from Burial Hill, Plymouth.

draws himself from gathering sea food, and makes his village, his home, and his skill with oar and sail minister to seekers of rest from the cities.

Like the St. Lawrence country and the Carolinas, New England was discovered from the sea. For our present study it does not matter whether the Vikings came to this shore, or whether "Vinland" was their name for a part of southern New England. The real discoverers are more modern. Fifteen years

before the Pilgrims came, Champlain had sailed from the North and coasted along the shores; he named Mount Desert and entered the Penobscot; the peaks of the White Mountains caught his eye from the northwest, and rounding Cape Ann, he recognized a good harbor, where Gloucester now is, for he called it Beauport. Later he found safety in Plymouth Harbor, and doubling the greater cape, made his farthest south in Nauset Harbor. Three years earlier, Gosnold was exploring the southern shores and gave names to the Elizabeth Islands, Marthas Vineyard, and Cape Cod.

When we study the first occupation and earliest migrations by New England colonists, the broad fact appears that drainage lines did not control. There are no such waves of movement up a river as we see along the Hudson and Mohawk. Had the *Mayflower* come to land in the mouth of the Connecticut River, the history might have been different; but the lines of human movement were transverse rather than longitudinal. Plymouth, Boston, and Salem were natural points of approach, and there history begins. Roger Williams and his followers went across the low hills from the Massachusetts colonies and found a natural resting-place in the first great valley and at the head of Narragansett. The next wave of population crossed the low plateau to the westward and found the fertile lands of the Connecticut Valley; beyond rose the Berkshire barrier, and life gathered along the river, clearings grew, towns rose, and there was a forecast of the home of men, of industry, and of education, which now lies between



FIG. 11. Looking Southward from Mount Holyoke, showing the Trap Ridge in Relief above the Lowlands of the Connecticut Valley. Mount Tom and the Great Ox Bow are across the River.

Long Island Sound and the north border of Massachusetts. Here are at least six institutions of higher learning, a network of railways, mills without number, and scenery, not Alpine, but in its own way magnificent. Let one stand on Mount Holyoke and look into the geologic past; go far back in the record which lies about and below, and there will be a spacious gulf between lofty uplands on either hand and leading down to the sea; the tides go in and out, and streams bear in waste from east and west,—ancestors of the Westfield, Deerfield, and Chicopee rivers. Curious reptiles throng the mud-flats when the tide is out and leave their tracks to be un-

covered in later times, and sometimes volcanic eruptions cover the muddy bottoms with sheets of lava. As time passes, the lands are elevated, the muds are hardened, the resulting shales and sandstones and sandwiched beds of lava are tipped to the eastward and south-eastward. Then the softer sands and shales are etched away by long processes of weathering and stream work, and the western edges of the thick, hard lavas form mountain ridges, the hanging hills of Meriden, or Mount Tom, steep and columnar on the west and sloping on the east. Curving to the east, where the Connecticut cuts the range, we have Mount Holyoke, which disappears southward from Amherst. The glacial ice, the glacial floods, the terraces, flood plains, and ox-bows of the river, — these represent the later history, leading to man's advent.

The aborigines also regarded the Berkshires as a barrier, protecting them in some measure from the fiercer savages of the Long House. But as now, so then, the wall was not impassable, for sometimes the elders of the Iroquois came across to collect their tributes of wampum. The massacres of the valley mark its lowlands as then a border country, and from that time until late in the last century we have had a migrating frontier, something which belongs only to a young and expanding nation.

The early colonists may well have felt surprise, if not dismay, at the severity of the winters that greeted them. They had come from a mild climate in latitude  $52^{\circ}$ ; and here in latitude  $42^{\circ}$ , ten degrees nearer the equator, they met the keen cold and fierce changes of New England winter. We must not forget the dif-



ferences, however, between north and south in this region. The Northmen might have found soft winter weather south of Cape Cod; for even the waters show a difference of temperature, and bluefish and some other marine creatures abound south of the Cape and are absent from more northern seas.

New England could not be the key of Eastern America in war. Her valleys do not lead to the heart of the continent, but northward into rugged lands by the St. Lawrence. On the west is a mountain barrier which has never been crossed by a large body of armed men. Causes that lay in the people, and not in their land, gave to New England the opening events of the American Revolution. In that first short act certain geographic features came into the settings of the stage. Among these were the drumlins; such are Breed's Hill and Bunker Hill; and it was the modest heights of Dorchester whose fortification by Washington made Boston untenable for the enemy. After the latter withdrew to New York, New England was almost a stranger to military operations.

✓ We have already discovered some of the trends of New England life and have seen how they flow from her physiographic conditions. The decline of the old agriculture was inevitable and need not be regretted. The sons and daughters of the farmers have gone to the factory, to business in the cities, to the prairies. Boulder fences have fallen down, houses are deserted, and fields grown with saplings; but population has increased, towns and cities are everywhere, railways and trolley roads and better highways thread the country, and much of New England



FIG. 12. Bar Harbor, from Bar Island.

will become suburban. The forests will be fostered, and the willing immigrant will subdue again the farms that have not already become the summer homes of urban people. The decline of New England is temporary, and the hardships and losses belong only to the period of transition.

The center of cotton manufacture is shifting from New England to the South. In the southern Appalachians and along the streams that flow from them, King Cotton will widen his sway from the fields of the Gulf plains. There is the cotton, the coal, the water-power, and the iron, and short hauls bring the one to the other. New England cotton mills cannot long meet such conditions as the rising South affords; but wool can take the place of cotton, and the shoes and brass and paper of New England will not suffer.

If fishing has lost its relative place, and lumbering also, the stores of granite, marble, slate, and brown-stone are limitless, and the wealth of the cities pours into the mountains and along the shores, during the heat of summer and the bright days of autumn. We see the process of final adjustment to geographic conditions. There is stress in the changes, but higher development and a richer civilization in the end.

"Man is what he eats;" "Character is a function of latitude;" "History is nothing more than an echo of the operation of geographic laws;" such are some of the sweeping affirmations that have been made about man's relation to the earth. They are too strong, and sure to confuse rather than to guide.

That environment influences character need not be asserted; but we cannot be sure in weighing this influence. Did the lands about the North Sea shape Teutonic character from time immemorial? And were some of these Teutons transplanted to a similar geographic province in the New World only to have the type perfected? But suppose the Puritan had gone not to New England but to Virginia. Would he not as easily have made the New England type of civilization in a more genial climate and with a more generous soil? Thus may physical features find limits to their efficiency; and none may so wisely recognize this as those who seek to trace the lines of physiographic control. The first New Englanders were picked men; the average man did not leave the eastern shires of Britain, but those who would have founded a state anywhere.

Now we may freely concede what nature has done, so far as we can read it, for New England life. If sturdy men could have been tempted to indolence, the short summers and rough fields left them no opportunity for such indulgence. Whether the climate is more a breeder of sturdy constitutions, or of consumption, may be left an unanswered question; but none can doubt that the geographic features of this province are pronounced and that they have colored all the life of her people, and have been in a large way the channel of its expression. We have seen how her works and days, her products and her industries, have hinged upon her shore-lines, her streams and waterfalls, her soils and forests. And beyond this, the garb, at least, of New England feel-

ing and thought, is woven in the loom of her fields and skies.

This we can trace in her literature. And yet we do not think that nature is a mere cloak, put on and off at will by the New England writers. The appreciation that we mean, whether found in her prose or verse, is essentially poetic. The best example of this is Emerson, a prose poet everywhere, and nowhere more truly than in his "Nature." If deepest sympathy with the outer world be our test, Emerson is the poet of New England. In the forest "is sanctity which shames our religions, and reality which discredits our heroes." "The mind loves its old home; as water to our thirst, so is the rock, the ground, to our eyes, and hands, and feet." "We nestle in nature and draw our living as parasites from her roots and grains." "The fall of snowflakes in a still air, the blowing of sleet over a wide sheet of water, the reflections of trees and flowers in glassy lakes, the crackling and sporting of hemlock in the flames,—these are the music and pictures of the most ancient religion." These are flash-lights upon New England, but her fields and woods and storms are deep with meaning.

We may leave to the critics Emerson's rank in poetry, pass his faults of meter, and call him "a great man who wrote poetry"; but this, at least, we shall find,—the transcendentalist was not lifted off his native soil, and "the secret of the land was in the poet." None can mistake the coming of New England spring in May-day or feel himself in any other land when —

“Announced by all the trumpets of the sky,  
Arrives the snow, and, driving o’er the fields,  
Seems nowhere to alight; the whited air  
Hides hills and woods, the river, and the heaven.”

A poet of the prairies would scarcely personify the  
sea, thundering on its border : —

“I drive my wedges home,  
And carve the coastwise mountain into caves,” —

nor would he seek the deep and rocky forest : —

“The watercourses were my guide;  
They led me through the thicket damp,  
Through brake and fern, the beaver’s camp,  
Through beds of granite cut my road.”

The physiographer has adopted Monadnock as the  
name of a typical form of land; and here our poet  
has also found a song : —

“Every morn I lift my head,  
See New England underspread  
Anchored fast for many an age,  
I await the bard and sage.”

Less intuitional and prophetic, but more simple and  
full in his pictures of the New England country, is  
Whittier. His biographer has made him tell of his  
early suffering from the fierce winter cold; and he has  
given us further proof of the tardy and difficult fashion  
in which the New England fathers adapted or failed  
to adapt themselves to a severer climate, “toughening  
themselves and their children sitting in cold churches,  
and deeming flannel garments no necessity.”

He, too, has immortalized the winter snows, but in a tale of domestic life, and tells of the uncle : —

“ Himself to Nature’s heart so near  
That all her voices in his ear  
Of beast or bird had meanings clear.”

Whittier, too, has his : —

“ Monadnock lifting from his night of pines  
His rosy forehead to the evening star.”

He sees it from Wachusett, and here also draws a sweet story of human faithfulness. He could not, living on its banks, fail to touch the Merrimac with his fancy. Other rivers he had seen, the Potomac, the Hudson, and —

“ Have seen along his valley gleam  
The Mohawk’s softly winding stream ;  
Yet wheresoe’er his step might be,  
Thy wandering child looked back to thee.”

To a blue water in New England belongs his “Summer by the Lakeside.” Here is the same refuge in nature that we found in Bryant by the Hudson ; and in the closing lines we have a double picture, — the landscape and the deep seriousness of the old New England life.

Thoreau was a poet also in keen vision and strong-lined reflection of his native fields and woods. His “Week on the Concord and Merrimac rivers” will surely leave one remembrance in the reader’s mind, — the still, scarcely flowing waters of the lesser stream. He lived too soon and was too little systematic to

know or care that this little stream belongs to a group of north-flowing rivers in Massachusetts, or the "still rivers" of Connecticut, which are sluggish because, since their valleys were excavated, the lands have tilted a little to the south, impeding their flow, and sending with a rush to the sea their south-flowing neighbors. But Thoreau could see, with eyes often lacking to the geographer, deep into the mystic meaning of out-of-door New England, and he who would know the land should go with him, "half college graduate, half Algonquin, the Robinson Crusoe of Walden Pond," to his hut in the woods, or walk with him down the soft sands of Cape Cod to Provincetown, or beneath the green arches of the Maine woods.



## CHAPTER III

### THE APPALACHIAN BARRIER

✓ WE are still to view the stage on which the scenes of early American history were enacted. As with New England, we look out upon it from the sea. The floor of the stage is the Atlantic lowland. Behind it are painted the crags and woodland slopes of the Appalachian Mountains. But the foreground is not the same in the South as in the North: in New England it is worn mountain land, in the South it is coastal plain. The one is a country of hills, the other a land of smoother aspect, flat or gently rolling, and showing low platforms alternating with shallow stream valleys. In one the rocks are of fabulous age, toughened in fiber and gnarly in face. In the other they consist of scarcely cemented land waste spread out in even sheets, often bearing marine shells, and thus giving proof of their recent emergence out of the sea. These beds of sand, gravel, marl, and clay slant gently toward the sea border and continue far beneath its waters, as would appear if we could remove the covering waves and dig valleys to reveal the structure. If the eastern part of our continent should come up a hundred feet, there would only be more of this flat country. And if it should go down a hundred feet, the ocean would only be conquering again a part of its former domain. Such a coastal

plain is not alone a feature of our land but borders parts of many continents. And in central New York or Wisconsin the geologist finds proofs of ancient coastal plains, now lifted and roughened beyond recognition, except to the initiated.

In typical form this lowland does not begin until we go south of New York Harbor and enter New Jersey. Of that state it makes the central and southern parts. Then it includes all of Delaware and most of Maryland, except where the latter state reaches a long and slender arm out across the ridges and valleys of the Appalachians. And here are all the low-lying plantations of Virginia, alone rivaling New England in its harvests of colonial record and tradition. Going south, we find it still, a hundred miles or more in width in North Carolina; and at this distance from the sea it has attained a height of but three hundred feet, or a little more, above the ocean level. The rivers are tidal far within the shore-line, and merge into sounds, as Albemarle and Pamlico. Outside of the sounds are long barrier beaches, theaters of wave and wind, protecting the waters within, and opening here and there for communication with the outer seas. So flat are parts of the coastal plain that "the Wilmington and Weldon Railroad has a stretch of 40 miles, where there is neither curve, excavation, nor embankment."

South Carolina tells the same story, only the coastal plain is wider, about 150 miles. So low and flat is this region that swamps abound, especially along the streams and shore-line. The alligators are at home in the rivers, and the names of the forest trees have

a tropical sound. The old story of tidal rivers is told again, and the towns—Charleston, Port Royal, Beaufort—remind one in this respect, at least, of New London, New York, or Philadelphia.

➤ The mountains do not rise at once from the plain. Lying between, in Maryland, Virginia, and the Carolinas, is a belt of hilly country, a little more than plain in some parts and a little less than mountain in others. In North Carolina this strip is two hundred miles wide, and begins to rise abruptly from the coastal plain on the east. Falls, or swift reaches, amounting to two hundred feet of descent, mark the eastward passages of the streams across this boundary, which physiographers have long called the Fall Line. The line runs southward into Georgia and northward to the Delaware. Up to this limit on the east, the rivers are sluggish, if not tidal. Down to this limit on the west, they are swift of flow. The hilly belt has also its physiographic name,—it is the Piedmont region, lying at the foot of the Blue Ridge. It is well-worn mountain land and is much like southeastern New England. If we could lift the New England region and expose her sea bottom it would be like the South Atlantic country; it would have a coastal plain, a Piedmont region, and its mountain ranges.

“Tide-water” Virginia and Maryland lie between the Fall Line and the sea. Within this region is the Chesapeake with its tributary waters. As in Maine, or on the Narragansett, or the Hudson, we are dealing now with a “drowned” river system. Perhaps the Chesapeake is the finest example, and on any map it looks like a swollen river with over-



FIG. 13. View from Wildcat Point, Maryland, showing Gorge and Islands of the Susquehanna River, a Short Distance South of the Pennsylvania Line. It is the Region of the Piedmont Plateau.

widened branches. Raise the land, and see how the salt waters would retire, and how the Potomac, York, and James would join the lengthened Susquehanna and enter the Atlantic somewhere to the east of Norfolk. But things were as they are long before the memory of man; and when the early navigators entered the gateway of Cape Charles and Cape Henry, a wilderness of quiet waters was before them, and they could make long voyages within sight of green shores, and for hundreds of miles thread narrow, tidal inlets shadowed by the overhanging forests. Captain John Smith gave the summer of 1608 to such voyages of exploration, going up the bay and entering the Susquehanna, Patapsco, and Potomac rivers. "Chesapeake Bay is a bay in most respects scarce to be outdone by the universe, having so many large and spacious rivers, spreading themselves to immeasurable creeks and coves, admirably carved out and contrived by the omnipotent hand of our wise Creator, for the advantage and conveniency of its inhabitants." Good as this is, Fiske, who quotes the above from an old writer, has drawn a picture in yet stronger lines. "The country known as 'tidewater Virginia' is a kind of sylvan Venice. Into the depths of the shaggy woodland, for many miles on either side of the great bay, the salt tide ebbs and flows. One can go surprisingly far inland on seafaring craft, while with a boat there are but few plantations on the old York peninsula to which one cannot approach very near." So easy and convenient were these ready-made highways as to retard the making of roadways across the lands and through the woods.

No single influence molded the life of the colony of Virginia. The beginnings in a wilderness are never easy. But this was no such land to struggle with as the Puritan found. Its climate was genial, its virgin soils were rich, and the battle with the winter's cold did not consume the energies that were sorely needed in other ways. If there had been no other differences, tobacco was enough. The world was calling for the new-found weed. The soils were suited to it. It was good currency when there was little other, and it was raised in fields that were washed by navigable waters. Direct to many plantations came the ships that loaded it for London. Or, if not, it was small trouble to raft it down the more shallow inlets to wharves that ocean-going sails could reach.

Plantations developed rather than towns. The prevalence of tobacco, the introduction of slave labor, the absence of land roads, and the facility of the waterways, — all favored the scattered, rural life. But no more here than in New England are geographic causes all; for the Cavalier, and not the Puritan, came to Virginia. The one was proud, given to amusement, an aristocrat, building a mansion, and surrounding himself with a landed estate like those of his native England. The other worked with his hands, had Yankee curiosity and invention, was frugal, and lived with his fellows in towns or on small neighborly farms. Each could understand the other's defects better than he could his points of excellence; and these two unlike men came into singularly contrasting environments to found a home across

the seas. Where the two lived were the two foci of colonial history, and the causes of the unfolding might baffle a complete analysis, either by the geographer or the historian.

Such is a glimpse of the tide-water country, the coastal plain. We must have such a view that we may know the meaning of the barrier that looms behind. Not all the lowland life is rural, though country is more than city as one goes farther south. But at the inner edge of the coastal plain, at the head of navigation, close by water-power, at the Fall Line, — here cities could but grow. Here, then, is the seaboard rival of New York, seated by the estuary of the Delaware. And here is the fourth of the great Atlantic quartette of cities, on the Chesapeake. And then come Washington, below the falls of the Potomac, Fredericksburg, Richmond, and Petersburg in Virginia, and Raleigh, Camden, and Columbia in the Carolinas. Narrow lowlands everywhere, and cities grown up by the side of short, tidal rivers, — such is the Atlantic border of the United States.

The barrier itself is not a single elevation, nor is it a disorderly group of heights, but has, as all mountain systems have, a plan that can be analyzed. It is indeed a mountain *system*. The shortest description of it is that it consists of parallel ridges and valleys which, as a group, but not as individuals, reach from eastern New York into Alabama. As in New England, so here, the downwear has been great. The ridges are not in relief because they have been elevated relatively to the valley bottoms, but because the valleys have been dug between them.

These very general statements will be clear if we look more specially at the barrier in three regions, — first in Pennsylvania, then in Virginia, and finally in North Carolina and Tennessee. We will note the elements in a profile of the country seen by one who goes from Philadelphia to Erie or Pittsburg. We go across the lowlands to Harrisburg. Here we are in a broad and fertile valley which runs far to northeast and to southwest. In New York it is the Wallkill Valley. In Pennsylvania, Easton, Bethlehem, Allentown, Reading, Lebanon, Harrisburg, Carlisle, and Chambersburg lie in it. Toward the Maryland line it is called the Cumberland Valley. In Maryland, Hagerstown is in it, and in Virginia it is the Shenandoah Valley. It is not the trench of a master river; for the rivers commonly flow across and not through it. It is often a dozen miles or more wide. It is due to the etching out of softer shales and limestones, leaving harder masses on either hand as mountains. Because the rocks are shales and limestones, the soils are rich, the farms are productive, towns are many, and railways cross and thread the valley everywhere. Physiographers know it as the Appalachian Valley.

To call it a valley will not puzzle the traveler who looks north from Allentown or Harrisburg. The even crest of Blue Mountain follows the horizon as far as he can see, ranging from twelve hundred to nearly two thousand feet above the ocean. On the southeast the mountain range that should bound the valley is in places worn away, but it appears in South Mountain, east of Chambersburg. It is worth our while to remem-



ber this name, for this modest elevation grows and rises southward until it becomes the Blue Ridge, and at last includes the strong and lofty mountain masses of the Carolinas. To the northeast it reappears again also, and becomes the Highlands of New Jersey, and the Highland Range of New York, cut by the Hudson. If even this were all, we should not have a barrier of historic importance. But, returning now to Pennsylvania, beyond the Blue Mountain are other ridges like itself, following it in long parallel walls, and separated from each other by longitudinal valleys. As a rule, the small streams run along these valleys and enter at right angles larger rivers which cut boldly across or through the mountains. Such are the Delaware, Lehigh, Schuylkill, and Susquehanna. Sometimes a large stream runs between ridges, as the east branch of the Susquehanna from Scranton to Northumberland, or the west branch past Williamsport. Such an arrangement of streams gives a rectangular or trellised pattern to the drainage. How it comes to be so is too long a story to be told here.

The Susquehanna crosses all the ridges. Why, then, is not its valley as good a doorway to the interior as the Hudson offers? Because the river is shallow, and beyond the mountains its head waters fringe out and are lost in the heights of the Alleghany plateau. To this we must turn to try to correct a most persistent misunderstanding about the land forms of Pennsylvania. Here are meant the unnumbered references to the "Alleghany Mountains," as though there was, in Pennsylvania, a range of that name, rugged, and thousands of feet in height.



FIG. 14. Delaware Water-gap. Photograph by W. H. Rau, Philadelphia.

From near Williamsport, far to the southwest, runs the Bald Eagle Valley. It is narrow and slightly curved to the southeast. On this southeast side it is flanked by a mountain ridge. The rocks are disturbed and tilted, and it is in all respects like the other ridges of the region. On the northwest rises a wall of equal height, about one thousand feet from the bed of the stream, but the rocks in it are not disturbed; they are piled one on the other in horizontal beds. This great wall, or escarpment, is made rugged by weathering and gashed by ravines. Follow up one of these and we come, not upon a mountain crest, but upon the eastern edge of the plateau which makes western Pennsylvania a surface about two thousand feet above sea, only lower in its valleys and where, at the northwest, it slopes down to Lake Erie. The "Alleghany Mountains" are nothing but this rough and steep wall that faces the southeast, and it seemed like another mountain range to those that came to it from the seaboard. If we follow the Alleghany escarpment northeast, it becomes obscure in that part of Pennsylvania, but reappears in New York, where it is known as the Catskills. Neither Catskill nor Alleghany, therefore, is the name of real mountains, but both, of the edge of a plateau, and the drainage, not being controlled by upturned beds of rock, is arranged like the branches of a tree. If we follow the Alleghany front southeast, we shall find it in West Virginia, Virginia, and Tennessee; and here again this long wall, facing southeast, has long been called the Cumberland Mountains, but ought to be called, and is becoming known as, the Cumberland

escarpment. If the reader will remember that this wall, whether it be steep slope or sheer cliff, extends from the Hudson River into Alabama; that the rocks are horizontal and form a plateau back of it, while all the proper mountains of the Atlantic seaboard are southeast of it, — he will have a key to the form and structure of the Appalachian region.

Returning for a moment to Pennsylvania, the barrier embraces South Mountain, the ridges from Blue Mountain to Bald Eagle Valley, the Alleghany escarpment, and the uplands of western Pennsylvania. The meaning of it will be somewhat appreciated if the path of the Pennsylvania Railroad be carefully traced from Philadelphia to Pittsburg.

Let us place ourselves at Harpers Ferry in Virginia. A river flows by us to the southeast. It is north of the town and is the Potomac. Barely east of the village it passes through a gorge, and in two miles comes out upon lowlands again. It has passed the Blue Ridge, whose severed heights rise in strong slopes nearly a thousand feet on either hand. Harpers Ferry is barely within the Blue Ridge on the west. From the southwest another river flows along the western base of the Blue Ridge and joins the Potomac at the east end of the town, which lies in the fork. It is the Shenandoah, and this is the Shenandoah Valley. To the north and east we should cross Maryland and come up to Harrisburg. To the southwest we should follow a broad and rich vale to the head waters of the Shenandoah beyond Staunton. It is a part again of the Appalachian Valley. As in Pennsylvania, it has towns, railroads, and fertile fields,

and the Potomac, like the Susquehanna, crosses it. Like the Susquehanna, too, it gathers its waters in longitudinal streams among the mountain ridges, and, turning, crosses them and the Shenandoah Valley to the southeast. Unlike the Susquehanna, however, the Potomac does not gather tribute from far over the plateau, for there the Monongahela holds sway.



FIG. 15. Characteristic Forested Slopes in the Southern Appalachians.  
Linville Gorge.

The great barrier, then, in Virginia, is the Blue Ridge, the Appalachian ridges, the Alleghany escarpment, and the plateau, and we may appreciate it by tracing again the line of a railway, the Baltimore and Ohio, which, like the Pennsylvania, starts on a tidal bay, crosses the Atlantic lowlands, the several parts of the Appalachian barrier, and comes down into the Ohio Valley.

Let us place ourselves at Knoxville in Tennessee.

A few miles to the southeast bold mountains rise and lie well over into North Carolina. It is a rudely triangular tangle of ridges, peaks, and high, intermontane valleys. More peaks than can be counted on the fingers of a hand rise above six thousand feet, and Mount Mitchell passes that limit by more than seven hundred feet. It is more than four hundred feet loftier than Mount Washington, and is the highest point of the United States east of the Rocky Mountains. These heights are built of the ancient crystalline rocks and are the southern continuation of the Blue Ridge. But the ridge so easily passed by the Potomac River has become a geographical province, broad and high. Locally the name Blue Ridge is used of the eastern range of the group, and the western range is the Unakas, and here are the loftiest peaks. But both together and all between connect through Virginia with the old New York Highlands. Atmospheric effects tell their story here, for in the distance the ridge is "Blue," and in poem and story, as in the common speech, the Unakas become the Great Smoky Mountains.

But not forgetting that we are at Knoxville, we travel to the northwest a few miles, and we are at the foot of the Cumberland escarpment. We may climb it and wander across the upland and come down to Nashville or into Kentucky. If we follow the foot of the wall north to the Tennessee-Kentucky line, we can ascend to the uplands through the historic Cumberland Gap.

Up and down the great valley past Knoxville extend the Appalachian ridges, but they are not so

high or persistent as in Pennsylvania. Going between some of these ridges to the north, we may follow the Holston or Clinch rivers to their head waters in Virginia. To the southwest we go down the Tennessee. At Chattanooga the river leaves the valley and winds through a trench in the plateau, later to make its curious swing to the north and to the Ohio. But if we pass Chattanooga and Lookout Mountain on our right, we shall be still in a broad valley, whose walls begin to fade, and we come upon the waters of the Coosa, which would take us southward to the Gulf.

The Clinch and Holston do not alone contribute to the trunk river. These follow longitudinal valleys; but from the southeast, out of the mountains, come most of the waters of Hiwassee, Little Tennessee, and the French Broad. And these streams reach across the higher Unakas far to the east, and bring the waters from the Blue Ridge as well. Taking the Tennessee system, therefore, even with the important longitudinal flow above and below Knoxville, its general flow is westward, like the Kanawha farther north. The southern Appalachians have westward drainage. The northern Appalachians drain eastward.

In the South the barrier consists of crystalline mountains, ancient and massive, a series of ridges alternating with valleys, an escarpment, and a plateau. Comparing the north, middle, and south parts, the general profile is the same, but there are many differences. The Blue Ridge is worn out opposite Harrisburg, it is conspicuous at Harpers Ferry, it is high and wide in the south. The younger but yet



**FIG. 16.** Spruce Forest near the Summit of White Top Mountain, Virginia. Photograph by U.S. Bureau of Forestry.



ancient ridges between the Blue Ridge and the plateau are high and persistent in Pennsylvania and Virginia, but weaken at Knoxville and disappear southward. It may yet be added that the long, wide belt of ridge and valley land between the Blue Ridge and the Alleghany-Cumberland escarpment is known to physiographers as the "Greater Appalachian Valley."

We have dwelt upon the physiographic aspects of the Appalachian region because they are usually left by historical writers to the reader's imagination. Those writers, unfortunately, do not all have Parkman's appreciation of geographic setting or the artistic skill with which he makes pictures of the land rise in perspective and color out of his pages.

This great rampart of the East does not seem difficult now, when the forests have been so largely cut away, when engineers have found reasonable grades for steam passage, and when electricity bids defiance to grades of every degree. But the greatest influence of the barrier goes back to the time when the forest was everywhere, when the wilderness was nearly unknown, and when even a country highway belonged to the future. The explorer, finding a gap, might encounter another mountain in front of him, for the ridges often "break joints," like bricks in a wall. And if he hit on the Susquehanna or the Potomac, it would lead him to the mazy wilderness of the Alleghany plateau. In addition to the physical difficulties of entering the mountain belt from the Atlantic plain, the pioneer must be ready for the prowling savage and count on the hostility of the French garrisons as he neared

the Ohio River. Only the adventurer, or the man with a serious public errand, would be likely to leave the fertile fields of Penn's country, or the tidal lowlands of the Chesapeake, for the hard trails and doubtful goals of the Appalachian wilderness. It has required more than two centuries to clear the forests, lay the roads, and open the regions fully to civilized man. Even down to 1880, there was a stretch of 350 miles, from the Roanoke southward, that had never been crossed by a railway.

¶ If, without a mountain barrier, the Atlantic plains had merged into a land like the prairies, it would be hard to say how American history would have shaped itself. If the fierce aborigines of the Southwest and the Northwest had been in the same relative positions, the new colonies would have been for them a more easy prey. And the colonists would have scattered, seeking the best lands, tending to individual rather than community life. This, in a medley population drawn from all the nations of Northwestern Europe, would have kept civilization back, and deferred the founding of coherent states. But the new Americans were pressed between the sea and the base of the mountains, forced to be neighborly, to assimilate each other's ideas, provide for common defense, and build up common institutions. Kept on the sea border, the centers of life were maritime, and there was, for those old days of slow-going ships, active interchange of ideas and products between the Old World and the New. The education of the mountains and forest came later. Now the people were held somewhat to their ancestral tutor, — the wide sea.

If the unity thus enforced was useful, so also was the diversity fostered by physical conditions. The Atlantic strip of colonial land was cold-temperate at the north and subtropical at the south. Boston and Charleston could not be the same. And almost every colony had a natural home differentiating it from the rest. Massachusetts Bay, Narragansett, Hudson, Delaware, Chesapeake,—these need no comment. With Roundhead, Dutchman, Quaker, Romanist, and Cavalier, other diversities came in, and came in so strongly that final unity for the colonies was by no means to be taken for granted. There was portentous uncertainty as to how New York and Pennsylvania would go in the Revolution. But the barrier held the colonies together in the first flush of individualism, when, escaping one yoke, they were unduly afraid of putting their heads into another. It has been said that even in 1700, barely three-fourths of a century after American ground began to be occupied in New England and Virginia, one could go from Portland to the Potomac and sleep every night in a "considerable village." The people had to live close enough to each other to insure organic life for each of the colonies, and in the end, for all, moving surely on to what Fiske calls a "continental state of things."

No English settlements had been made beyond the central and southern Appalachians at the beginning of the Revolution. A century and a half had been spent in building the states by the Atlantic. Thirty years later the president of the Republic would send Lewis and Clark to the mouth of the

Columbia River. Within eighty years a half-dozen railway surveys would be run from the Mississippi River to the Pacific Ocean. In a century and a quarter great cities would stand by the Golden Gate and by the bays of the Northwest. The public men of the colonies did not much appreciate the country beyond the mountains. But we need not wonder, for it was to them unknown. They had, indeed, heard of the Lakes and the French forts, and may have served in frontier wars, but they never dreamed that the destinies of the nation were there. There were exceptional men who saw more than others. Such was Spotswood of Virginia, who, in 1716, crossed the Blue Ridge in central Virginia, and thus wrote, "We should attempt to make some settlements on y<sup>e</sup> lakes, and at the same time possess ourselves of those passes of the great mountains, which are necessary to preserve a communication with such settlements."

This was the call of a clear trumpet, but no one was aroused by it. The Virginia colonists had too much to do and to be interested in nearer home, and two generations were to pass before there would be a nation. It was not the fault of the colonists that when they awoke to it they did not find another great nation across the mountains. Great movements work out in the silent chemistry of events. Neither individuals nor peoples plan their greatest deeds. This has nowhere been more true than in "the winning of the West."

How the Appalachian barrier was crossed, we must now inquire. Most physiographers think that an

ancient river system had its head waters in West Virginia, its middle course in Pennsylvania, and discharged into a great valley, where Lake Erie now lies. By the strange changes of the ice invasion, the system was so broken up and rearranged that two broad streams, the Allegheny from the north, and the Monongahela from the south, coming together at a sharp angle, form the Ohio, and carry many waters of West Virginia and southwestern New York to the Gulf of Mexico. Covering the narrow point between the rivers, and stretching along their banks and eastward over the uplands, is Pittsburg, the "Gateway of the West." Washington had prophetic visions of the meaning of this place, but the French were too strong. Fort Duquesne, Braddock, Fort Pitt, — these are the early chapters. A permanent settlement was made in 1773, and the tides of life began to flow. A million people now belong to the city and its environs. No more powerful geographic causes can be found in any land than group themselves here, — navigation on three rivers, valleys inviting railways, and mineral products close at hand, making this the North American metropolis of petroleum, of natural gas, of bituminous coal, and of iron.

But we wish most to see how the overflow from the East centered upon Pittsburg and passed down the Ohio River. From the head of the Delaware and Chesapeake bays paths were sought between the Potomac and the upper waters of the Susquehanna, or in the belt of country now lying between the Pennsylvania and the Baltimore and Ohio Rail-



FIG. 17. Pittsburgh : Union of the Allegheny and the Monongahela forming the Ohio River.

ways. Such paths must lead across the Hagerstown-Harrisburg Valley, across the Appalachian ridges, and over the plateau east of the Monongahela River. But there is no natural highway. The Mohawk route was a steady menace to the trade of Philadelphia during the early decades of the nineteenth century. An Albany firm, as told by McMaster, owned a Hudson River line of packets, and offered to carry freight from New York to Pittsburg for six dollars a ton, while wagon lines from Philadelphia, with tire-some efforts, could scarcely meet the price. To go around and come down the Allegheny River, or up the streams from Lake Erie, was easier than to come over the barrier. The New Yorkers, at the same time, insured the goods and gave easier terms of payment. Thus they held the advantage and looked forward to even better days, for the Erie Canal was under way.

The men of Philadelphia in those days thought that they held the geographic key to the inland trade. By one scheme they would go on rivers, lakes, and short canals, by Elmira and Seneca Lake, to Lake Ontario. Or they were going by the Susquehanna to the Allegheny, the Conewango, and Lake Erie, or by the Juniata to the Allegheny and the Ohio. But why wonder that they saw visions of fleets on shallow rivers and obscure creeks, when Washington himself had visited, years before, the Oneida carrying-place, and had considered the pass from Otsego Lake to the Mohawk, and had grown eloquent upon the navigable waters of central New York.




**FIG. 18.** Valley of the Allegheny, sunk below the Even Surface of the Alleghany Plateau. Oil Refinery at Franklin, Pennsylvania.



While New York and Philadelphia strove, danger for both loomed in the far Southwest. Would not the farmers and traders of the new West send their goods to New Orleans? What was to prevent the Southern town, lying between the prairies and the sea, from winning in the race? Sugar and cotton had already come to the seaboard by way of Pittsburg. Thus the call grew loud for roads and canals across the mountains; and the statesmen joined in, for they said, we cannot form into a compact nation lands that are divorced in trade and have scant intercourse with each other. "State after state heard the cry, and an era of internal improvements opened, which did far more to cement the Union and join the East and West inseparably than did the Constitution and the laws." <sup>1</sup>

That the old roadways from Philadelphia and the Chesapeake country to the Ohio River were so various shows that nature offered no commanding route. There was a northern highway, if we may so dignify it, leading from Philadelphia almost directly westward. It ran at no great distance from the future field of Gettysburg, crossed the Appalachian Valley at Shippenburg, passed out of the mountain belt beyond Bedford, and, bearing more to the north, led down into the muddy hamlet of Pittsburg; but in the years following the Revolution it guided multitudes to the west. The other routes were farther south, and led along the Potomac in western Maryland, then up into Pennsylvania to the Youghiogheny, and down by this river and the Monongahela to Pittsburg. Such were

<sup>1</sup> McMaster, "History of the People of the United States," IV, 397.



**FIG. 19.** Cumberland and the Narrows of Wills Mountain, Maryland. Wills Creek has cut a Typical Appalachian Water-gap, and enters the Potomac here. At this Point was the Old Fort Cumberland, on the Natural Road between Virginia and the West.

Washington's road and Braddock's road, which often followed a still older Indian trail. Washington, too, was watching New Orleans, and was anxious to tap the Ohio Valley for the Potomac and the James. For this a road across the mountains was needed, a true highway, and not the difficult path which he himself had so often trod. Not long after his death the national government undertook the building of the Cumberland Road. We have described its general course, and often it was identical with the roads that Washington had known. It was opened in 1818; and in a few years more the Chesapeake and Ohio Canal was finished, doing thus what was possible to concentrate the streams of commerce and immigration in this region.

Thus along many lines, in Virginia, Maryland, and Pennsylvania, the westward migration went on. The mountains were like a sieve, with openings enough, though small; and everything that went through centered, as if in a funnel, in the upper Ohio Valley. Here, as we have seen, was Pittsburg, which had become a city a few years before the Cumberland Road was finished. She had already begun to dig the coal from her neighboring hills and drive her smoking furnaces. The puff of the steam whistle was heard on the waters of the Ohio, and goods and men went down the valley as freely as did the waters gathered from the Alleghany plateau. But multitudes had not waited for steam. They had been going for a generation, from the close of the Revolution, in canoes, scows, and on rafts, bound for Kentucky or the settlements north of the Ohio.

We have now seen how the white man went west-

ward by the Mohawk Valley. How great this avenue was will appear again when we follow the shores of the Great Lakes and look out over the prairies. We have seen, too, that the Ohio Valley was a door to the West; but we have yet to follow another stream of migration along natural highways that open farther to the south. Through these highways went the men who founded Kentucky and Tennessee and shaped the destinies of the Southwest.

We may now recall the longitudinal valleys of the Appalachians, of which the greatest is that which leads by Harrisburg and Hagerstown up the Shenandoah. When the early settlers had occupied these fertile lands in Pennsylvania, and the stream of life must flow farther, it was easier to follow the valleys to the southwest than to cross the ranges and to come out on the west. Hence before the rush toward Pittsburg began, there had been for many decades a longitudinal movement into Virginia, and then beyond to the head waters of the Tennessee, the Watauga, the Holston, and the French Broad. Among those who thus went southwest were the Scotch-Irish, a people to whom American historians are now beginning to render justice. In great numbers these people, English in speech, Scotch in blood, Irish by adoption, Presbyterian in faith, came to America. Philadelphia and the Pennsylvania lowlands were full of them. Princeton University is their memorial in New Jersey. They entered the Appalachian valleys, largely populated West Virginia, and were the backbone of the young commonwealth that sprang up on the Tennessee and the Cumberland. "They formed the kernel of the

distinctively and intensely American stock who were the pioneers of our people in their march westward, the vanguard of the army of fighting settlers who, with ax and rifle, won their way from the Alleghanies to the Rio Grande and the Pacific."<sup>1</sup>

Southwestern Virginia lies for a hundred miles along the northern boundary of Tennessee. This boundary is purely arbitrary, for the valleys, the mountain ridges, and the streams cross it. In one of the valleys runs the Norfolk and Western Railway, leading up to Roanoke, and thence east, across the Blue Ridge, to the sea, or one may continue northeast through the Shenandoah Valley. The head waters of the Holston are in Virginia. We must remember that what is now Tennessee was in early days a part of North Carolina, an ultramontane country. Now we can understand how the backwoodsmen of Virginia went down the Holston, built their cabins, girdled the big trees, felled the little ones, planted corn, fought the savages, and thought they were still in Virginia. When they learned their mistake, they sought to be taken under the wing of the North Carolina government; and their wish was granted, perhaps with reluctance, for they had a name worse than their deserts. They were the makers of a new commonwealth; they had wives to support; they had no time to wear gloves or to consume in deciding what to do with Tories who stirred up the red men. Thus they founded the Holston, or, as sometimes called, the Watauga settlements, one of the two early seed grounds of the state of Tennessee.

The Holston community was also the nursery for

<sup>1</sup> Theodore Roosevelt, "Winning of the West," I, 134.

another commonwealth, long to anticipate Tennessee in becoming a member of the Union, — the state of Kentucky. On the north this state has a natural boundary, the Ohio River. On the south she is geographically one with Tennessee; and the Cumberland River, rising in the more northern state, passes south of the boundary by a long bend, and returns again toward the Ohio River. If the two form a single province, their history likewise begins with the same people, the same fierce battles with savages, the same heroic endurance of a wilderness more remote than other American colonists had known. To the settlements on the Atlantic, Europe was almost neighborly in comparison.

The eastern boundary of Kentucky, for a considerable distance, is formed by the Cumberland escarpment. Eastern Kentucky is plateau, and it overlooks the valleys of Virginia. Just where the three states now come together — Virginia, North Carolina, and Tennessee — is one of the most famous points in early American history. There is a break in the escarpment, — it is the Cumberland Gap. By it, in 1775, Daniel Boone and his companions climbed out of the Appalachian Valley from the settlements on the Holston and began to blaze an equally famous highway, — the Wilderness Road. They pushed their way through the forest, had a preliminary skirmish or two with the red men, and founded the state of Kentucky. Having carried the American frontier well down upon the Ohio River on the very eve of the Revolution, the ground was American at its close, and was the outpost of freedom in the struggle for the

West that followed. Boone was more than a hunter ; he was one of the builders of a new nation.

By the close of the war the new colony was well established. It is not within our purpose to describe its growth or character, but rather to follow the strong lines drawn by nature, along which the migrating hosts passed. For hosts they were, when the cessation of hostilities left the people free to turn to the pursuits of peace. Then a never ending procession of boats floated down the Ohio from Pittsburg, and a perpetual caravan of men, women, and children, of packhorses and cattle, filed under the rocky cliffs of the Cumberland Gap and followed the blazed trees and now worn path of the Wilderness Road. In 1769, six years before he planted the permanent settlement, Boone had made his first journey through this gap to the valley of the Kentucky River. He was returning, therefore, to a land which he knew, a land whose richness and beauty has won all beholders from that day to this. Open prairie and shaded woodland were there then as they are to-day. But there were uncounted buffalo also, and elk and deer, as well as wild creatures of fiercer kinds. In a few years the buffalo ceased to visit the salt licks, and the settlers came and availed themselves of the salt, — a product that in those days had to be carried far and was costly. It is not her grains and fruits that distinguish Kentucky from other states, but the meadows and pastures of the "Blue-grass region." Says Professor Garman, writing in an agricultural bulletin, "The phrase, 'down in Old Kentucky,' conveys to the wandering Kentuckian a picture in which




FIG. 20. A Blue-grass Meadow in Kentucky. Photograph by Professor H. Garman.



are sunny slopes of soft, green grass; grazing horses and cattle, sleek and beautiful. . . . Blue-grass Kentucky is a delightful bit of the world in May and June. . . . And it is largely the result of the profusion with which the little plant, blue-grass, grows in her limestone soil." The same writer proceeds to say that a bulletin on forage plants would be little needed if all Kentucky were like this favored fifth around Lexington. The student will find no better illustration of geographic control—agricultural, social, and even political—than this famous region.

The reader of "In the Tennessee Mountains," or of "The Prophet of the Great Smoky Mountains," finds true pictures of the forests and hazy mountain slopes of the southern Appalachians. But he finds also a human type not to be met elsewhere in the United States. He is farmer, hunter, blacksmith, shopkeeper, or rude preacher. He is courageous, original, reads the sky and forest in lieu of books, and is little troubled by the outside world. He could not raise cotton, he did not own slaves, and his sympathies were with the North rather than with the South in the Civil War. His family lives as his great-grandfather's family lived, for change is almost unknown. Division of labor has little place in such a society, where homespun still prevails. These men are the descendants of the backwoodsmen, who came from the Old World, from Pennsylvania, from Virginia, and the Carolinas, to the Holston, the French Broad, the Kentucky, and the Cumberland. Retired from all the world, they reveal the effects of a stable environment in a remote region.

There is peculiar continuity of conditions throughout the long range of the southern Appalachians. There run valleys and forested ridges from Virginia into Alabama. There an archaic and almost fossil type of life has come into being. A temperate climate prevails far southward, run in like a wedge between the hot lowlands of the Carolinas and the Mississippi Valley. The isothermal lines of the weather map will sometimes run from New York to Alabama on the eastern slope of the Blue Ridge, and then double and return direct northward to southern Michigan, where they turn off again westward. Mountain, valley, forest, and climate form a realm of upland within lowlands, with strongest industrial, social, and political contrasts. There are counties in North Carolina that do not contain a single negro. But within this land are noble and modern cities,—Knoxville, where the Tennessee is formed by confluent streams, and Chattanooga, where the same river leaves the great valley and goes out through the Cumberland plateau. We shall have occasion, in the chapter on the Civil War, to return to Chattanooga and describe its surroundings with care, but these cities shall now stand for the great industrial unfolding of the last generation in this gateway of the South. From Virginia to Alabama plentiful coal and iron lie close to each other, sometimes “at pistol range.” There is limestone also for flux, and thus the conditions for the making of iron are perfect. There is water-power in many mountain streams, and the cotton belt is not far away. Just outside the gate is Atlanta, predestined by its situation to be a metropolis. The

new life of the South is gradually penetrating the wilds, bringing education and modern invention into the most distant corners of this Southern world, and the sternest commands of nature are in the end softened, if not defied, by man.

## CHAPTER IV

### THE GREAT LAKES AND AMERICAN COMMERCE

NORTH AMERICA has its mountain systems on the east and west. Between them is a vast lowland, wider at the north, narrower at the south, but spacious everywhere. One may follow the Mississippi, the Minnesota, and the Red River of the North, pass Lake Winnipeg and Hudson Bay, and come out on the Arctic Sea. Nowhere in his journey must he be more than one thousand feet above the ocean level. If the great mountains had been massed in the central parts of the continent, their uplands might have been as arid and remote and their inhabitants as strange and averse to intrusion as among the plateaus of central Asia. But North America has the continental type of Europe or South America, with mountain borders and central plains. In South America these plains are threaded by rivers; in Europe seawaters pierce the heart of the lands; but North America has both, and more,—the Hudson Bay, the Mississippi and Mackenzie, and the fresh-water seas of the St. Lawrence. Suppose there had been no Great Lakes; perhaps, before the glacial time, there were none. Suppose there was only a larger St. Lawrence, with many branches, flowing from the region of Superior and Michigan; such, very likely,

there was. Or, suppose the waters of the Lake region had found no gap across the eastern mountains and had become tributary to the Ohio. If we look at a relief map of North America, this seems an easy alternative.

What, in any case, would American history have been? Where would the Frenchman have planted himself, and would there have been a French and Indian War, and where would the battle-ground be found? These are idle questions if we look for answers; but they may mean much if they fix our eyes on the lakes and make us see how large a place they have in the life of man on this continent.

Various European nations were sending vessels to the cod banks of Newfoundland about the beginning of the sixteenth century. There is, according to Parkman, some evidence that Europeans began to fish in these waters before 1497, the year of Cabot's voyage. At all events, the French had learned the road, and it was but little more for them to sail between Cape North and Cape Ray and find themselves within the Gulf of St. Lawrence, with its ample waters and its varied shores. It was Jacques Cartier who, in 1534, had sailed from St. Malo that he might search the unknown regions beyond the fishing-banks. He did not, however, take the broader gateway to the south of Newfoundland, but went up by the east shore and threaded the straits of Belle Isle.

In the year following he was again fitted out that he might ascend the St. Lawrence. He went up to the Indian village of Hochelaga, where now is Montreal. Though he made a later voyage, he did

not succeed in planting a colony on the river — this was left to successors who were more daring, or more enduring, than he. But for us his first voyage is full of meaning. He entered the continent by its northern gateway, and he found the two natural centers of human population on the great rivers; for in selecting a site on which to plant a town, the instincts of the savage were as sure as those of the white man.

Among the later and greater men was Champlain. We have seen him on the New England coast, but his name is written in the St. Lawrence country and in the waters that divide New York and New England; and it was left for others to make known the country of the Lakes. His first project suggests a striking feature of the map of North America. Follow the estuary and river of the St. Lawrence, Lake Ontario, Lake Erie, the Ohio River, and the Mississippi. Almost in a straight line do these waters join the Gulf of St. Lawrence and the Gulf of Mexico. La Salle was at La Chien, above Montreal. The Indians had told him of the Ohio River, and he set out to explore it. His story is rehearsed by the historians, and we may only see how geographic features shaped his courses. To go up the St. Lawrence was inevitable, and they reached the lake, "like a great sea with no land beyond it," writes the pious father who accompanied him.

A few miles east of Rochester, Irondequoit Bay penetrates several miles into the lands of western New York. It is almost shut off from the lake by a sand bar, over which the railway now passes. Through this depression it is believed that the pre-

glacial Genesee entered the valley where Lake Ontario now is. But with the river shifted to the west this landlocked bay invited entrance; and here La Salle found the Seneca Indians, from whom he hoped to secure a guide to the Ohio. This plan did not mature, and he later went to the western end of Lake Ontario, near the present city of Hamilton, where he met Joliet, who had returned from the upper lakes. They did not remain long together, and Joliet and his companions were soon threading the waters of Detroit, and La Salle, as is believed by some, was accomplishing his exploration of the Ohio River. Later he went to the greater lakes, voyaged up Huron, passed Mackinac, and landed at the south end of Lake Michigan. He made the easy pass to the Illinois, but how far he descended it is not known. His planting of a settlement on the Illinois and his voyage down the Mississippi to the Gulf belong to a later period. It was left for Joliet and Marquette to enter Green Bay, pass from the Fox River to the Wisconsin, discover the Mississippi, and float with its current to a point but seven hundred miles from the Gulf.

Few spots in America have so much historic color as Niagara. And the physiographer sees the short centuries of human occupation against the background of ages of physical evolution. Savage, explorer, colonist, soldier, and man of science have gathered here, and now the place seems likely to become the industrial center of the continent; but man's part can hardly be so dramatic and wonderful as the story of Niagara in more ancient days.

When La Salle was, for the time, drawn away from



FIG. 21. After the Waters have been used. Niagara Falls Hydraulic Power and Manufacturing Company.



the Ohio River and went along the lake shore with Joliet, he crossed the lower Niagara, where, a commonplace stream, it flows over the Ontario plain between Lewiston and the lake. He must have heard the roar of the falls and perhaps wondered at the origin of the solemn and pervasive music, but he was not to discover the cataract. It was Hennepin who passed up the left bank of the river, looked down upon the Whirlpool Rapids, and made with his pencil the picture whose conventional rows of trees, and towering Goat Island rocks, have given the ancient priest an immortality which the master of landscape would sigh for in vain.

In 1679 La Salle joined his name to Niagara. Here, above the falls, was built the *Griffon*; a little vessel of forty-five tons, and here she was moored until her master should return with supplies from Fort Frontenac. These necessities had to be carried up the Lewiston Heights, among them the anchor, requiring four men, as Parkman relates, "well stimulated with brandy," to bring it to the plateau above. The *Griffon* went to Green Bay, La Salle went on into the wilderness, and the ship setting out to return, loaded with furs, was lost.

Thus Niagara took its place in the human world. It was a goal, and it was a point of departure. Follow the Lakes, for exploration, for commerce, for war, and you must take account of it. Try to learn the story of the Lakes, to know their beginnings and their history, and a score of geologists must center their studies on Niagara, so large is her part in the making of things.

If there were no rapids above Montreal and no winter ice in the St. Lawrence, would Buffalo be more than a modest town? Rather would not the railways from the west, passing Detroit, cross Ontario and center upon Hamilton, there to load ships for Liverpool, Glasgow, and Hamburg? Possibly, because the mouth of the St. Lawrence is so far north, an Erie Canal might have saved something for Buffalo and New York. Or we will suppose the St. Lawrence as it is, but no Niagara, and a perfect waterway from Erie to Ontario. Would not the interior metropolis of New York then be Oswego? Here would be the eastern limit of navigation and the point of reshipment for the Mohawk Valley. Niagara makes the difference, and hence it is that Lake Erie is swept by the great vessels of the upper lakes, and Ontario is in comparison a lonely water. It is hers to bear a modest freight, a few lines of tourist steamers, and spend the rest of her energies carving cliffs in the massive glacial drift that often borders her shores. The story of her future commerce, however, is not written.

Reference has been made to the Ontario Lake plain, crossed by the lower Niagara; to the cliffs at Lewiston; to the gorge, and to the Niagara plateau. For the reader who has not visited the region, it will be useful to explain more fully the geographical surroundings of the Falls. In an earlier chapter, the lake plains of western New York were distinguished from the Alleghany plateau. But there are really two lake plains. Lake Erie lies in the upper one, which slopes abruptly up into the Alleghany pla-

teau, beyond Dunkirk and Chautauqua, but stretches smoothly eastward from Buffalo for many miles. Lake Ontario lies in the lower plain, and the difference of altitude between the two lake surfaces is nearly three hundred feet. About half of this vertical interval is accounted for by the bluffs at Lewiston. These face north and are known as the Niagara escarpment. This wall runs west, far through Ontario, and east toward Rochester. The famous series of locks at Lockport carries the Erie Canal from the upper to the lower plain. The upper surface, viewed in reference to Lake Erie, is a lake plain, and was formerly flooded with lake waters. Viewed in reference to Ontario, it is the Niagara plateau. Its smooth top is formed upon the flat Niagara limestone, and the escarpment is chiefly the north or exposed edge of this formation. When Niagara began to flow, it fell over the bluff at Lewiston. Cutting away the limestone under the brink, the fall has receded until it is now seven miles south, and the Niagara Gorge is seven miles long—a history which seems simple, and is, in this, its great feature, but in many other ways is an intricate story and difficult to decipher.

On Lake Erie we are 573 feet above the sea. If we go up through the Detroit and St. Clair rivers, upon Lake Huron or Michigan, we are but 8 feet higher. And if we ascend through the locks of the "Soo" to Lake Superior, we add but 21 feet more, and our altitude is 602 feet. A little help from man, therefore, turns the four upper lakes into a single sea, with free navigation between remotest points. Thus, too, we can see how the cutting of the Chicago Drain-



Copyright by Caudall & Fletcher, Duluth.

**FIG. 22.** Harbor of Duluth and Superior, seen from Duluth. See page 137.

age Canal might become a matter of concern, not merely to St. Louis, for fear of sewage, but to Cleveland or Buffalo, if a considerable portion of Niagara should be diverted to the Mississippi. If this be speculation, it serves at least to point out the delicate balance of the lake waters. They are a great sea, and the southwest pass is so low that "tidal waves arising in Lake Michigan sometimes overflowed the dividing ridge. The early explorers of the Great Lakes are known to have passed, during the spring freshets, in their canoes from one valley to the other, by that route which enables the modern Chicago to discharge its sewage into the Gulf of Mexico instead of the Gulf of St. Lawrence."<sup>1</sup>

The chief drainage of the Great Lake region was once carried to the sea by the Chicago outlet. And still later the waters of the upper lakes went through the Mohawk Valley to the Hudson, and later still they went by the Ottawa Valley to the St. Lawrence. Now they go by Port Huron and Niagara. Let us not think that this present arrangement must last forever. We know that in late geological times, even since the close of the glacial period, most of the plain that holds the Lakes has been given an increasing slant toward the southwest. Mr. G. K. Gilbert, following up this suggestion, has shown with an approach to certainty that this tilting is yet going on, with the result that in a few centuries the Lakes would withdraw some of their waters from the Niagara to the Mississippi, and in a few thousand years would leave Niagara dry. The tilting may not, however, go on, and if it

<sup>1</sup> Winsor, "Cartier to Frontenac," p. 4.

does, man can restrain the change of outflow for a long period if he desires.

Vast as the Lakes are, they have seen many revolutions and are still young. They rest in shallow depressions on a widespreading plain, which, so to speak, is so delicately poised that movements within the earth can change the face of things, and might have made quite other than it is, the theater of American history.

It is time for us to tell in a more connected way the story of the Lakes, and to put in their true setting the scattered facts already given. Many questions about their origin cannot now be answered, but the closing events are better known than the early stages of the history. It will be useful, in a preliminary way, to banish false notions about the depth of the lake basins. One thousand feet seems a great depth of water, but Lake Superior is four hundred miles long. The ratio of depth to length is about one to two thousand. With this ratio a lake one mile long would be two and one-half feet deep. If we could drain the basin of Lake Superior, it would present a vast plain, with hardly a variation from the horizontal that the eye could detect. The case would be similar with Michigan, Huron, and Ontario, while Erie is yet more surprising. Her depth is to length nearly as one to seven thousand, and a lake one mile long would be nine or ten inches deep!

We cannot have a fair opinion about the forces that made the basins unless we remember that these basins are mere scratches on the continent, or faint sags, like those that harbor shallow water in a flat

meadow after rain. We should also put the depth of the Lakes in relation to sea-level. All but Lake Erie reach below this horizon, — Superior about four hundred feet, Ontario nearly five hundred feet, Michigan nearly three hundred feet, and Huron about 150 feet. Erie, being so shallow, keeps its bottom 363 feet above the sea.

Look upon the map of the Laurentian waters and imagine the Lakes shrinking in width until they become mere sections of a great St. Lawrence River, rising in Minnesota and on the highlands north of Lake Superior. Let it flow somewhere near the "Soo" and take in a branch from along the axis of Lake Michigan. Let it pass the Huron, to the Ontario country, receiving branches from southern Ontario and northern Ohio, and then go down to the sea. If there was such a greater St. Lawrence, this may not be a true picture of it, but it would probably do for the essentials.

If we could now imagine great sections of these river valleys to be deepened, or to be in any manner shut off from the sea, the surplus rain-waters would gather in them, and we should see the inland seas of to-day.

We have taken this way of approaching what is perhaps the leading theory about the Lakes, that they lie in blocked river valleys. Then the query comes, — what sort of barriers are these, or what could they be? The Lake country is now tipping to the southwest; it is not a very disturbing motion, — about five inches in a distance of one hundred miles in a century. But that would be four feet in a thousand

years, and a thousand years in the earth's history is not much. We can see that such tilting would hinder the flow of Ontario's waters past the Thousand Islands and would make the lake deeper. The basins may, therefore, be partly due to uprising of the lands toward the outlets of the rivers.

But the Lakes are doubtless not due to this single cause. Every foot of the Lake country was occupied by glacial ice. Massive beds of drift, in sheets or morainic heaps, were left when the ice melted away. The moraines show themselves in hills, and the sheets are often revealed by deep borings, or by their covering the country so smoothly and so deeply that in certain regions, bed-rock rarely comes to the surface. Ancient valleys were often shut up by bodies of drift, and multitudes of the smaller lakes lie in such pockets in old valleys. There is no reason why great valleys should not in some places have been barred in the same way. Moving glaciers also remove rocks from beneath them. Their weight is great, and they are shod with sand and boulders. But they do not erode equally everywhere. Where the ice is thickest or is hardest pushed, both from its own weight and the onthrust from behind, there it will dig most. Thus some observers believe that the Great Lake basins are more due to glacial erosion than to anything else. There is no reason why all the causes which have been described may not have lent their aid. ✓


There is another word to be added to this bundle of queries. The relations of the rocks here are such that valley-making seems inevitable in the long



preglacial time. The softer, horizontal strata of the Northern United States abut against the hard, ancient core of North America, found in Canada. Where these flat beds run over the southerly slopes of the crystalline uplands of the north, they would suffer most destruction, and by laws known to physiography, valleys would grow, of which the primitive land forms give no hint. Some sort of a St. Lawrence River system was to be expected from earliest times. Movements of the land, glacial blockades, and glacial erosion have done the rest.

- The later development of the Lakes can be more clearly told. When the historian has pieced together from stray inscriptions and traditions a doubtful story of early man, he may come down to a point where records abound, and libraries give him more material than he can use. Then, if he have diligence and judgment, he can move with firm step. Something like this certainty we have, — when the continental glacier was disappearing, when the lakes were often larger, — and always of forms different from those of to-day. Great bodies of water leave on their
- borders inscriptions which centuries may not destroy or deface. By records of ancient shore-lines, we prove that the Lakes were often larger and had higher levels than they now have. ■

If the reader would know this history, let him clearly trace the line of water partings that separate the St. Lawrence basin from those of the Mississippi and Susquehanna. In Minnesota the head waters of the Mississippi reach close to Lake Superior. Wisconsin is more evenly divided, where the Fox and



Copyright by Crandall & Fletcher, Duluth.

FIG. 23. Part of Mahoning Iron Ore Pit, Mesaba Range, Minnesota. See page 137.

Wisconsin rivers head against each other in the central part of the state. In Illinois the parting is hard by Chicago and is overcome by a few feet of digging. It crosses northern Indiana and northern Ohio, and runs close to Lake Erie, as it enters western New York. In New York the divide is south of the Finger Lakes, and we need pursue it no further except to mark on the map the place of Elmira.

When the ice was at its limits it lay far southward over the line of water partings. The ice-sheet was removed by gradual melting on the south. Sometimes it disappeared from great regions and advanced again. When at any point the ice melted north of the divide, a lake would result. Its basin would be formed by the height of land on the south and the glacial ice on the north. Its form would depend on the turns of the line of water parting and the irregularities of the ice front; the water would be supplied by the melting ice; the outlets would be across the divides into head waters of the Mississippi and Susquehanna.

Now we can understand what was happening at the head of the present Lake Michigan. After the ice began to melt northward, out of the Lake Michigan basin, the site of Chicago was flooded. The overflow went along the line of the Drainage Canal into the Illinois River. The longer the ice melted, the greater became the lake, and the more water poured out toward the Mississippi. Exactly similar things were taking place at about the same time, at the head of the Superior basin. Along the slopes about Duluth the old beaches tell the story. The ice

filled more or less of the lake basin, holding up the waters so that they poured over into the St. Croix, and thus went to the Gulf. If we go to Indiana and Ohio, the conditions are the same, only now we are at the head of the Lake Erie lobe of the glacier. As before it is melting away, and lake waters rise against the divide and flow over, at Fort Wayne, where the ancient channel, now dry, has been traced and has been shown to be in harmony with old beaches in Indiana and Ohio.

At Elmira in New York, or a little to the north, is the lowest southward pass in the state, east of the Hudson, not quite a thousand feet above the sea. Think of the glacier, still massive, where Lake Ontario now is, and reaching well up into western New York. All the basins of the Finger Lakes then held lakes deeper and greater than now. Southward, these lakes were restrained by the divides. Northward, as before, they laved the ice front. And for a time their northern ends coalesced, and they had a common outlet through Seneca Valley, past Elmira, and down the Chemung to the Susquehanna.

We must remind the reader that these lakes at the head of Superior, Michigan, and Erie, and in western New York, may not have been contemporaneous, but they represent a stage in the retreat of the ice, and were not far apart, as the geologist reckons time. As the ice melted yet more, the lowlands of the Lake region were flooded, larger lakes were formed, and some of the old outlets were abandoned because the passes were too high. One of these vast lakes extended from the Finger Lake region westward, over

much of northern Ohio, southern Ontario, and southern Michigan. Its outlet crossed the unsubmerged part of southern Michigan and entered the Michigan basin, whence the waters passed out by the Chicago outlet. This ancient body of water was held to its place by the great glacier that still blocked the Mohawk and St. Lawrence valleys and the eastern Ontario region. The beaches which mark its presence and prove its reality are about 870 feet above the sea, and it is known as Lake Warren.

By various stages these waters were drawn down, the channel across Michigan was abandoned, and we find the outflow taking place by the Mohawk Valley. The outline of the Great Lakes has been revolutionized. Western New York is in great part dry land, but Lake Ontario washes the base of the Niagara escarpment, flows up the Cayuga Valley, absorbs Oneida Lake, and sends its waters to the Hudson. This drainage makes a great river, for it comes not only from the greater Ontario but from a vast upper lake, which, absorbing Superior, Michigan, and Huron, discharges across the Province of Ontario into Iroquois, for this is the name which we should give to the ancestral Ontario. Another great result of the descent of the Warren waters to the Iroquois level was the uncovering of the Niagara escarpment, and the beginning of Niagara River and Niagara cataract. But it will be observed that it was a small Niagara, for the upper waters were going more directly to the sea, by way of the Georgian Bay region and Lake Iroquois.

Later still we find no ice in the St. Lawrence Val-

ley. Here, then, was a lower outlet for Lake Iroquois, and the Mohawk Valley was abandoned, save by the little stream gathered from the New York uplands. At the same time, the upper lake waters had shifted to a more northern outlet and were reaching the St. Lawrence by way of the Ottawa Valley. The whole St. Lawrence region was now so low that the sea flowed freely in, and the tides were felt far up the Ottawa Valley and to the head of Lake Ontario and in the valley of Lake Champlain. Niagara was still a little river and could boast only of the waters of Lake Erie, and Lake Erie was smaller than it is to-day. And now comes the closing scene in this long drama. The eastern country began to rise and the sea to retire from Lake Ontario and the upper St. Lawrence. By and by the uplift had become too great to permit the upper lake waters to flow east by the Ottawa Valley. They swing back to Port Huron and Niagara, and Niagara became the great river which it is to-day.

This is the upward movement of the land which, as Mr. Gilbert has shown, is probably still going on. In our short story of the Lakes we have been able to see how the ice filled their basins and perhaps deepened them, how small lakes were replaced by greater ones, and how successive outflows of their waters have been directed to the southward, westward, eastward, and northeastward. The lands have changed their levels, and Niagara has been born and grown to be what she is.

At Lewiston, N.Y., on the plain below the Niagara escarpment, is a low ridge of gravel running eastward. It is prolonged through several coun-

ties in western New York, and has been used for a line of highway since the days of the earliest settlers. This avenue, leading through rich farming and fruit lands, has always been known as the Ridge Road. It represents in part only the beach of the ancient Lake Iroquois, which has been followed eastward to central New York, and then northward to Watertown. At Lewiston the beach is about 140 feet above Lake Ontario, but at the east end of the lake it is from two hundred to three hundred feet higher than the lake surface. As the old beach must have been horizontal when made, we find here the proof that the region has been given an inclination to the west and southwest. The story of these beaches would be a long one; but when it is read it gives a convincing sense of reality concerning the glacial lakes which we have described. Finding the beaches in Ohio, and girding the slopes of Mackinac Island, or high above the waters of Lake Superior, and surmounted now by the great buildings and busy streets of Duluth, we cannot doubt their meaning. The most skeptical should yield credence, when, correlating with the shore-lines, he finds the outlet channels at Chicago, at Fort Wayne, at Elmira, at Rome, or in the Mattawa Valley leading from Georgian Bay to the Ottawa River.

Where the lands that stretch away from the lake shores are almost flat, the ancient Lakes must have reached far inland. This is true in western New York, northern Ohio, and southern Ontario. And there we find the soils and subsoils consisting of clays and fine silts, that is, of just such material as settles



Copyright by Crandall & Fletcher, Duluth.

FIG. 24. Duluth, Mesaba and Northern Ore Docks.



in the bottom of lakes at some distance from the shore. The plowman is not annoyed by boulders, and the farmer finds smooth and level areas, easy of tillage and rich in production. Transportation is simple and inexpensive, railways are easily built, and the land is foreordained to prosperity. Thus have the Lakes themselves fashioned thousands of square miles of the lands that lie about them, spreading their soils upon their rocky foundations, and now bearing away their harvests to remote cities. Nor are the Lakes without large influence upon the climate of the region. There are nearly one hundred thousand miles of water surface, and the contribution to atmospheric moisture through evaporation is enormous. More than this, the Lakes are deep, and contain six thousand cubic miles of water. The heat that is received into these waters during the warmer parts of the year is stored and gradually set free during the autumn and winter, tempering the atmosphere of surrounding lands. Hence the fields of the Iroquois plain are garnished with forests of peach trees, and vineyards cover the Erie shore plains of the Chautauqua region. Soil and climate alike are the gift of the Lakes. Those who live in the more southern land rarely think of genial climate in Canada, but the Lake region of the province of Ontario abounds in orchards and raises the vine in profusion.

We have approached the Lakes down the long lines of their physical history only that we may better know what they have meant in the life of man during the short centuries since America was found by European people. When the devout missionary

and hardy explorer had ascended the St. Lawrence, the open waters would carry him to the heart of the continent. Or if he pushed up the Ottawa and threaded the rough forests that lay toward the Georgian Bay, he could bid farewell to the bouldery jungle, and paddle his canoe to the Chicago River, Green Bay, or the head of Lake Superior, and thence by easy portages he could find his way into some head water of the great Mississippi. And when the missionary and the trapper were followed by the permanent settler, forts were planted, cabins rose on the prairie and in the forest, towns grew up on bays and in the mouths of rivers, the towns became cities, and the cities sent fleets of vessels up and down these inland seas, bearing the grain of an empire, and at length stores of mineral wealth whose very existence was hidden until our own time.

No other inland navigation in the world compares with that of the Laurentian Lakes, and what it may become in the century just begun it would be rash to foretell. Every lake washes the borders of rich lands, and these lands reach across the prairies and down the Mississippi, over the plains to the far Northwest, and eastward by two great gateways to the Atlantic. Most of the great railways now converge on the Lakes, and it is only sober prophecy to forecast ships of large tonnage sailing from the Lakes to the Hudson and lower St. Lawrence by two or more routes from the Lakes to the Mississippi, and from Superior, by way of Winnipeg, to Hudson Bay. For some of these the surveys are complete, and in at least two instances construction is much more than

✓ (imp.) T.

begun. Far more wonderful would the present have seemed to those who 225 years ago launched the first sailing vessel on the upper Lakes.

The governments, both of the United States and of Canada, have not been slow to see the meaning of the Lakes. As early as 1841 the United States Lake Survey was planned, and its work carried on for forty years. The character of the shores, the nature of the bottoms, and the depths of the water were determined and recorded in maps which are now available to sailors and to all. The work is similar to that of the United States Coast Survey. As with the ocean, so on lake borders, conditions change, bars are built, bays are silted up, new shoals are found, and revision of the older work has been found necessary and has been undertaken.

From the head of Lake Michigan, or of Lake Superior, to the lower part of Lake Erie, the shipman finds nearly one thousand miles of continuous sailing. By the locks on St. Marys River, and by dredging parts of the channel between Huron and Erie, vessels drawing twenty feet of water can now make this voyage. From Buffalo and Cleveland on the east this great highway, forking in upper Lake Huron, finds its western gate in Chicago, Milwaukee, and Duluth.

Down to the present time the lake trade converges eastward upon Buffalo. Here the products of the West are transferred to railway and canal, excepting those which, in boats of moderate draught, go on their way down the Welland Canal to Lake Ontario and Montreal. Soon after La Salle had launched the *Griffon* near by, another Frenchman, Baron La



· FIG. 25. Along the Cuyahoga River, Cleveland.

Honton, saw that the plain at the foot of the lake had meaning for the future, and a fort was built. Nearly a century later the British held the place and called it Fort Erie, and the commerce of the Great Lakes began. The place was not known as Buffalo until 1810, when its first steamboat, *Walk-in-the-Water*, went westward. Its greater development began in 1825, when the Erie Canal was finished.

One hundred and fifty miles up the south shore of Lake Erie is the rival port of the lower Lakes. There seems to be, at first view, no compelling reason why a large city should grow where Cleveland is. It is not at the head or foot of a great lake; it is not so near to extensive mineral deposits as to arouse expectation; it has, indeed, a rich farming land to the south; it is on the lake shore, and a small river, the Cuyahoga, draining a few counties of northern Ohio, enters the lake here. There was a trading post at Pittsburg and another at Detroit. The mouth of the Cuyahoga was nearly on a line between the two, was a convenient halting place, and a trading post was established. In 1796, the Connecticut Land Company sent Moses Cleaveland to survey the ground, and his name, lacking a letter, became attached to it. A real settlement began in 1797, and real prosperity began, when, in 1834, a waterway, the Ohio Canal, joined the place with the Ohio River. No other geographic cause is so compelling in the making of cities as a line of transportation, or, perhaps we ought to say, the convergence of such lines.

Cleveland was, for long, the second city of Ohio, springing to the first place only at the close of the

last century, and offering one example among others of the advantages of lake and seaports as compared with river towns. Fifty years ago a trivial consignment of iron ore was here received from Lake Superior. Nobody heard of it, or if it was known, it stirred no thought. But Cleveland was not, after all, so removed from the treasures of the under earth. Coal was mining in the Mahoning Valley, on the east border of the state. It was coming to Cleveland; and later, also, more ore was brought and coal was made to smelt the iron. At length, also, the trail between trading posts had become a railway, and Pittsburg and Cleveland had been made neighbors. There was unlimited coal about Pittsburg, and the ore, coming in vast shiploads through the deepened canal of St. Marys River, was swiftly transferred at Cleveland and sent to the city of furnaces. Meantime oil and gas developed, pipe-lines were run down from the oil fields, and Cleveland became the greatest of petroleum centers. East and west along the lake shore run the transcontinental railways; and so it turns out that the little valley of the Cuyahoga River is at the crossing of two of the greatest highways in America.

Detroit, named from the narrow water passage between Huron and Erie, is, in its name, a lasting memorial of French discovery and early occupation. There were earlier posts on the Lakes above, but Cadillac had the sagacity to see that the fur trade could best be centered and controlled where Detroit now is. He returned to France, convinced the ministry of his wisdom, and gained a grant of land, "wherever on the Detroit (strait) the new fort should

be established." The settlement came into English possession in 1762, was held by the British for a time in the War of 1812, and had become by 1818 a populous and lively community. Eight years before, *Walk-in-the-Water* had sailed from Buffalo, and now lake commerce was becoming large, and a more settled and refined life was mingling with the rougher elements of the frontier.

For through commerce on the Lakes Detroit would be but a calling-place, and we must not overlook the essential part which the railway has had in her growth. The great east and west highways must go either north or south of Lake Erie. Those that run north of the lake cross the river at Detroit and, entering Canada, divide in like manner upon Lake Ontario. Here, then, as in Cleveland, we have a crossing of the ways, and here also must converge the more local lines of railway which serve the Southern peninsula and carry its traffic to the South and East.

The greatest of lake ports is not at the head of Lake Michigan, but nearly twenty miles north, on the western shore. Chicago is determined by the same cause that guided Joliet and Marquette, La Salle and Hennepin, when they sojourned in this region, or sought the sources of the Mississippi. Here an insignificant river enters the lake, and its short courses lead to the pass whose history lies in the geological past, and whose importance to man is now beginning to be seen. And yet upon this stream, by dredging and by building docks, forty-one miles of frontage have been made available, and the har-

borage outside has been extended by breakwater construction, until fleets can anchor here, where two generations ago a small town lay along a straight shore-line and on two sides of a shallow, muddy, and unknown river. It is now ninety-nine years since the first permanent white settlers occupied Chicago, and



FIG. 26. Shipping in the Chicago River. Photograph by Wm. H. Rau, Philadelphia.

the civilian population was barely a hundred in 1830. In the last decade of the nineteenth century Chicago increased her population by fifty-four per cent and has in the beginning of the twentieth century nearly two millions of people. This was due in no measure to local conditions, for her harbor had to be created and the very ground raised from a swamp. The greatness of Chicago is due to its general geographic



relations and to the combination, as with Cleveland and Detroit, of railway and water transportation.

From the prairies, the plains, and the passes of the northern Rocky Mountains, the railway lines must round the head of Lake Michigan. All passers between East and West must pay tribute here. Traffic from the Southwest is drawn to the Lakes, and all lines from the farther Northwest must come down to Chicago. Whatever diversions may occur at Duluth or along Canadian lines of railway, they cannot injure the lake metropolis, though they may in some ways check its rate of expansion.

Milwaukee compares in an interesting way with its greater neighbor. Its natural advantages of immediate environment are far greater: a good harbor, fine rising ground for her streets and buildings, and a river for water-power. She is also favored by being the center of interest and the capital of a great commonwealth; but not all of these gains can counterbalance the relations which Chicago holds to the entire country. Like Chicago, Milwaukee bears an Indian name, but like the greater city also the French explorers led the way, and the first white settler upon Milwaukee Bay, in 1817, bore the name of Juneau. But no one thinks of France to-day when he enters, on the shore of Lake Michigan, one of the greatest of German-American cities.

The cold and abundant waters that flow out of Lake Superior encounter a tough sill of ancient rocks, over which, in foaming rapids, they leap down to enter the expanse of Lake Huron. Lake Superior could have little more than local commerce until this



FIG. 27. American Locks at Sault Sainte Marie, —the "Soo."

obstacle was overcome. As she is surrounded, not by prairies yielding grain and fruit, but by rough and rocky lands, bearing forests on their slopes and mineral wealth beneath their scanty soils and bare ledges, exchange becomes imperative, for no region of two or three resources, however rich, can live to itself. The governor of Michigan saw the need as long ago as 1837 and stirred the legislature to its task. Baffled for many years by conservative influences in the national government, necessity won at last, and a canal was finished in 1853. It was twelve feet deep, and its completion made possible a continuous passage from the head of Lake Superior to Buffalo. In a few years enlargement was needed, and the national government took up the work. The deepening of the locks and of the approaching channels to seventeen feet was not enough, and the depth has now been carried to twenty-one feet. Similar works have been completed by the Canadian government within a dozen years, and the tonnage that passes this gateway is stated in figures that baffle comprehension. That of the Suez Canal is light in comparison with it; and where small cargoes fifty years ago were laboriously carried around the rapids, a vessel of eight thousand tons, having on board the product of eleven thousand acres of wheat, or a cargo of iron ore, passes in a few moments. But little of the water of Superior is needed for the locks, and power canals have been built on the American and on the Canadian side of the river. The iron, nickel, and other minerals of the region have been developed, and a railway projected to Hudson Bay to open within a few years the lum-

ber, grain, minerals, and fish of that northern region. Varied manufactures and a route of traffic must here build up one more of the great centers of the Lake region.

Not least of these will be the head of Lake Superior. Historic time in this domain is so short that prophecy swiftly leads one on from the brief records of the past. On the steep slopes rising from the chilling waters of the lake is Duluth, another memorial of early French occupation. We might better say visitation, for Captain Jean DuLuth, in 1760, only built a hut, and it was more than a century later when a city was chartered here. Though not yet one of the greatest cities, it is already one of the greatest ports of the Lakes, and no limit can be placed to its possible unfolding. Here is the focal point for the grain of Minnesota, the Dakotas, and the vast northwest provinces of Canada. When deeper waterways shall have been dug eastward from the Lakes, there will be no breaking of bulk between Duluth and New York, Liverpool, or Hamburg. The head of Lake Superior is five hundred miles nearer to the grain-growing empire of the Northwest than is Chicago, and the result is inevitable. Here, too, within a few score miles are the largest iron-ore beds known in America. And most of the ore lies, not in deeply buried veins, but close to the surface, making it possible to mine it with steam shovels in open pits, into which railway tracks are carried, and from which the loaded cars are run down to the docks at Duluth and in its neighborhood, there to transfer their loads to the lake vessels. It reaches its destination in Cleveland or

Pittsburg at a trivial cost which has made possible the enormous development of iron and steel in recent years. Added to the iron ranges of Minnesota are the great stores of iron and native copper in the northern peninsula of Michigan, and the lumber of Michigan, northern Wisconsin, and the adjacent parts of Canada. We shall not forget that other ports on the Lakes — Ashland, Marquette, Port Huron, Toledo, and many others — are great in commerce, being overshadowed somewhat by their larger rivals.

It has often been said that the great cities are made by railroads. This is the more plausible because shallow waterways, like the Erie Canal, have lost their importance. But the railway can never displace the deep waterway in carrying other than perishable freight. We may, therefore, look forward to enormous extension of traffic of the Great Lakes through the ship canals of the future. One of these will open the way from Lake Erie to New York Harbor. By an act of 1897 the United States government undertook an investigation of routes for waterways between the Lakes and the Atlantic Ocean, and an elaborate report of the engineers was transmitted to Congress in 1900. Should this report lead to action, it is proposed to pass from the Niagara River above the Falls to Lake Ontario, either by a route close to the river, and entering it again at Lewiston, or by a line a few miles to the eastward. From Lake Ontario to the Hudson alternative routes are proposed, one by Oswego and the Mohawk Valley, the other by the St. Lawrence, Lake Champlain, and eastern New York. To accomplish such a plan will



Copyright by Crandall and Fletcher, Duluth.

FIG. 28. Duluth ; Railways and Business Section.

go far to perpetuate and increase the commercial superiority of New York City.

Within a few years the Canadian government has completed its great project of cutting a fourteen-foot waterway from Lake Erie to tide-water, by way of the Welland Canal, and by passing around the various impracticable sections of the St. Lawrence River. These channels have a total length of nearly seventy-five miles. Other schemes have been proposed which in the end may mean much to this growing northern empire. A canal from Georgian Bay to the navigable waters of the Ottawa River would give direct passage from Chicago and Duluth to Montreal and Liverpool. If a map be consulted, it will be found that a line from Georgian Bay to Montreal is one side of a triangle, whose remaining sides must be traversed by vessels taking the Port Huron route. This proposed waterway has almost romantic interest because through it passed the waters of the upper Lakes at the close of the glacial period. As railways look back to ancestral trails of savages or wild beasts, so this plan of navigation recalls a yet more distant era.

The Chicago Drainage Canal was not cut across the prairie for a single end. Already it disposes of the sewage and secures greater purity of the lake water-supply, but its twenty-eight miles of channel, cut broad and deep through the drift and solid rock, are to be the first link in a waterway that shall pass through the Illinois River to the Mississippi and join the Great Lakes to the Gulf. This means unhindered communication between the Gulf of St. Lawrence and the Gulf of Mexico. It means more than this; for

when the Isthmian Canal has been built, direct freight service can be had, for exchange of all the products of the Northwest, with the Western coast of America and the entire Orient. Then the dreams of explorers will be more than fulfilled. They sought the East by way of the Great Lakes, and their descendants of the twentieth century will have found the way. No distant future may see Minneapolis sending its flour in shiploads to Duluth and the East; for a route has already been surveyed. From Superior to Lake Winnipeg; from the Mississippi and Minnesota rivers to the Red River of the North; and from Lake Winnipeg to Hudson Bay,—these are among the possible triumphs of the future. Pittsburgh and Lake Erie will be joined, Niagara will merge with Buffalo as the industrial center of North America, the agricultural riches of the Northwest and of the arid lands will have been developed, and the adjustment of human life to its North American environment will enter upon an advanced stage. It has been no part of the present plan to give the statistics of Great Lake commerce, but rather to show some of the laws and centers of its growth. If, however, we remember that the tonnage (not the value) of Cleveland lake traffic has sometimes surpassed that of Liverpool, and that the Detroit River, in the seven open months, exceeds the import and export tonnage of our Atlantic and Pacific ports combined, we shall find that the largest expectations of the coming half-century are sober and reasonable.



## CHAPTER V

### THE PRAIRIE COUNTRY

WE are beginning to see that geographic provinces cannot be sharply defined. The Appalachian barrier grades down to the coastal plain through the Piedmont Hills, and on the west the Alleghany plateau slopes to the level of the prairies. So when we say prairie country, we mean the great northern ✓ central land, whose most characteristic phase is prairie: and yet Ohio and Indiana are but in a small way prairie states. Illinois and Iowa are the typical regions, and we include roughly the lands lying around them: southern Minnesota and Wisconsin, northern Missouri, and the states west of the Missouri River, so far as they are well enough watered to grow crops freely without irrigation. From the uplands of Wisconsin to the mouth of the Ohio, and from the state of Ohio well into Nebraska, lies the land to which we turn. It is the upper Mississippi Valley, shorn, however, of two great regions: one about the head waters of the Ohio, and the other stretching far along the upper Missouri. The former belongs to the Alleghany plateau, and the latter to the Great Plains and the Rocky Mountains. But we cannot draw a line between the prairie and those flat lands that surround the Lakes and once formed part of their bottoms.

Into this great open land civilized man might come by several doorways, and two of them were equally open and inviting. One would have led the explorer up from the Gulf of Mexico. The Spaniard looked in at this door, — indeed, he entered it, and camped just within; but he found no gold, and thus he carried his trails and left the tokens of his language among the mountains and plateaus of the distant Southwest. How blind he was to the seat of empire, we need no special wisdom now to see. He would cede it to his northern neighbor, and it would by and by be sold for a few paltry millions of dollars.

The Frenchman came in at the other open door, along the Laurentian waters. Armed with triple motive, — love of adventure, the gospel of his faith, and zeal for the gains of peltry, — he made the Mississippi Valley for the time his own. If these motives were mingled in some, they burned singly and with pure flame in others. If there were hypocrites among true and suffering heralds of the faith, there were men also mingled with the scoundrels that bartered pelts with the savages and threw off the bonds of decent society in the wilds of the forest. With the mixed motives of common human nature, but always with daring, the prairie country was crossed from north to south and from east to west.

It marked an epoch in the history of the New World when Joliet and Marquette pushed their little craft up the Fox River, toward those head waters from which, by a short portage, they should go over to the Wisconsin. When their canoe was launched again, the Mississippi Valley was won; for they needed

but to give themselves to the current, to pass the Missouri, the Ohio, and the Arkansas, and to have sailed out into the Gulf, had not the risks seemed too great, among swarms of hostile natives. Having run by the mouth of the Arkansas, they turned against the current, but entered, as they returned, the Illinois River, found it easy to overcome its sluggish flow, and came back to Green Bay by the portage at the head of Lake Michigan.



FIG. 29. Bridge across the Mississippi at St. Louis.

It remained for La Salle to assert with larger confidence, and by the warrant of more remote journeyings, the rights of his king in the Mississippi country, a drainage basin which perhaps seems more vast to us who know, than to the explorer who was living in the shadowy realm of the imagination. When La Salle had returned to Paris, he was fully awake to the need of possessing and fortifying the new realm, and said, in almost prophetic language, "Should foreigners anticipate us, they will complete the ruin of New France,

which they already hem in by their establishments of Virginia, Pennsylvania, New England, and Hudson's Bay." Several years before, having visited the Illinois country, he drew a picture of the prairies which may in some points serve as well to-day: "So beautiful and so fertile; so free from forests, and so full of meadows, brooks, and rivers; so abounding in fish, game, and venison, that one can find there in plenty, and with little trouble, all that is needful for the support of flourishing colonies." Indeed the empire would be built and the meadows would be made populous, but the founders of states would come neither by the Lakes nor the Gulf, — they would hew their way across the mountains.

It was in 1682 that La Salle completed the discovery of the lower Mississippi and gave name to the Louisiana country. By the beginning of the next century settlements were made. One of the French centers of population was at Detroit, another was at Vincennes in the lower Wabash country, on the eastern, or what is now the Indiana, side of the river; and the farthest outpost of all was about Kaskaskia, in the river region between Cairo and St. Louis. Here and on the Wabash gathered several thousand French colonists. They were not state builders, as La Salle might have hoped, but lived in easy fashion, bartering furs, rearing their half-breed children, and tilling patches of the soil in their occasional hours of industry. We are not concerned with their story save to see how they passed, with the fall of Quebec, under British rule, so to remain until the close of the Revolution. Here, for a short period, was a population of

French and of savages, governed by a foreign king, who was alien to both, and bitterly hostile to the growth of his rebellious seaboard colonies, as they pushed into the land north of the Ohio. Against this triangular and unnatural union of vacillating creoles, savage aborigines, and wilful king, were pitted the backwoodsmen of Kentucky.

These hardy souls we have met before, as they colonized the valleys and threaded the passes of the Appalachians. They had not learned to use with slack hand the ax and the rifle. They could travel light, follow a trail like a savage, and shoot sure. They took pride in snuffing a candle or driving a nail with a bullet, and two of them, not the best or noblest of their kind, are said to have amused themselves and shown their confidence in each other's skill, by placing a tin cup full of whiskey on the head, and allowing the other, at a range of seventy yards, to puncture it.

The shadowy claims of Virginia and other colonies to this old Northwest counted for nothing against actual possession by British forts and British commanders, and the land had to be won by successful war. In planting the settlements on the Kentucky and the Cumberland, Boone, Robertson, and the men and women who toiled and fought with them, had opened the way for the prairie realm of the future. They were to win it against all odds, while nations that approached it by other highways were to stand aside, and thus to bring fresh proof that geographic opportunity does not of necessity control.

It is here that we meet the surveyor, frontiersman,

and soldier, George Rogers Clark. There is no finer story of frontier history than his. A Virginian by birth, a Kentuckian by adoption, he saw the problem of the Northwest, and went back to Virginia to arouse the government of his native state. From Patrick Henry, the governor, he received a Godspeed; but there was little more for the exhausted colony to give. Almost with single hand he raised a little force, took it down the Ohio, surprised Kaskaskia, won the French by his kindness and the savages by his union of fairness and defiance; marched through cold floods, often breast deep, to Vincennes, and compelled its English commander with superior force to surrender,—this is, in brief, the dramatic story. Every advance of the Middle West in population, in wealth, and in public achievement should add to the fame of this simple, rough man of illimitable personal force. His work made it easy for the new government to claim and hold, in the final treaties, the country north of the Ohio River and south of the Lakes, where now are Ohio, Indiana, Illinois, Michigan, and Wisconsin. It was, for purposes of conquest and occupancy, a geographical unit; it could not be divided, and the winning of it was essential to the winning also of the Northwest that lay beyond, and of the great Southwest.

Such, in its outlines, had been the history down to the beginning of those decades following the Revolution, when the great rush of the people westward was filling the prairie lands with homes and permanent institutions. Before we follow these throngs along their line of march, or see how they adjusted their

life to their new surroundings, we must observe these geographic conditions as carefully as we may, and we will ask the reader to note again the extent and borders of the land.

Ohio on the east is scarcely upland, nor is it lowland, having an average altitude of between eight hundred and nine hundred feet. We may think of it as the Alleghany plateau gently declining to the west, or as the Mississippi plains rising on the east. It has exceedingly smooth lake plains on the north and northwest, and a line of low divides, running north of the middle of the state, turns the streams to Lake Erie and the Ohio River. These streams occupy valleys sunk well down into the low plateau. Ohio is not a prairie state; for she never had more than small areas of open, treeless meadow, to which this name is given. Almost the whole state was originally covered with forests of walnut, beech, maple, buckeye, chestnut, ash, and hickory.

In type of surface Indiana is much like Ohio, with large areas in the east and south, of low plateau, eight hundred to more than one thousand feet in altitude, deeply dissected by valleys leading to the Ohio and the Wabash. In the central and northwestern areas the ground is lower and often a true plain, but, except about one-eighth of the state, is not a prairie, any more than Ohio, and was largely covered in early days with heavy and luxuriant forests, mainly of a hardwood type.

Illinois is prairie, for here La Salle found the open meadows with rank herbage and deep black soil, with shallow valleys and sluggish rivers, which belong to

the name. Nor are trees absent, but as a rule they border the rivers, growing upon their flood plains and fringing their banks with sprawling roots and overhanging foliage. If we cross the Mississippi River, Iowa is much like Illinois, for these, more than all others, are the prairie states.

We will not vex ourselves with the unanswered question, whether the forestless condition was due to Indian burnings, or to qualities of soil or climate, for it is more to our purpose to see how the lands were ready for the plow, were suited to rapid occupation, and were overswept by waves of human life in a small fraction of the time required to clear the forests and grub among the boulders of the New England uplands.

FIG. 30. Low Bluffs in Union Township, Iowa. Characteristic Distribution of Native Trees, the South and Southwest Slopes being Bare. Photograph by Professor Samuel Calvin.





When we have crossed the Mississippi River at about five hundred feet above the sea, we begin to rise again, and in central and northwestern Iowa find ourselves more than one thousand feet in altitude. If we cross the Missouri into Nebraska, we rise still more, on the gentle, prolonged incline that will take us up to the base of the Rocky Mountains. As we approach the central portions of Nebraska the rainfall decreases, and the cornfields give way to less luxuriant pasture lands. Here, in a rough way, we may say that the prairies end. There is no change in the forms of the land, but only a change in climatic condition. Thus we see how difficult it is to bound geographic areas; and yet the geographer is right in distinguishing the Alleghany plateau, the prairies, and the Great Plains. But the language made necessary by usage is misleading. Ohio stands less than a thousand feet above the sea, but it is dissected by valleys and joined to higher areas on the east, and we call it plateau. The arid region, beginning in central Nebraska and Kansas, is three thousand feet and upward in altitude, but is little dissected, and is called the Great Plains. We may better follow, however, the newer name, High Plains. If it were not pedantic, we could say the undissected plateau east of the Rocky Mountains. The prairies again are always rather smooth lands, with shallow valleys, but some are lower and some are higher, while the name especially denotes watered and fertile areas in the forestless condition. Thus we have, in outline, an east and west profile of the central Mississippi region.

Missouri, to a line somewhat south of its great river, is much like the adjoining parts of Iowa. Using our definition of prairies, as a flat country, nearly forestless, but well enough watered for agriculture, we may carry the belt through southwestern Wisconsin, and across southern and western Minnesota and the eastern Dakotas.

Over all this region, from Ohio into Nebraska and from the Ohio River through Minnesota, the Mississippi River holds sway. The single exceptions are the Lake slopes of the Ohio River states, and the valley of the Red River of the North. In its drainage, therefore, the region has unity. It is a surface also beneath which lie, everywhere, sheets of ancient sandstone, limestone, and shale, referred by the geologist to the Paleozoic era. Rarely are these beds disturbed, or in any way modified, except by the slow changes that have consolidated the muds into hard rocks, and raised them by continental movements a few hundred feet above the level of the sea. Long-continued denudation has stripped away the upper sheets to an unknown degree, and planed the rocks down to the strata that remain, and over which the products of rock decay and the glacial waste have been deposited. Thus the character and structure of the foundation rocks also lend unity to the region.

All New England shows the effects of glaciation. This is true also of most of the lands with which we are now concerned, but with this important difference, that here the glacial sheets accomplished their wear and spread their waste upon a comparatively even surface. Some very smooth lands in Iowa, Illinois,

and in northern Indiana and Ohio, are made so by the even spreading, under the ice sheet, of a thick bed of till, or boulder clay, which is the most wide-spread deposit of a great glacier. Often, too, the ice front lay along a smooth surface, and the streams flowing from it were sluggish, and wandered hither and thither, interlocking with each other, and building up wide-spreading aprons of washed clays and sands. Frequently, where the ice front lay for a long time, belts of hills, or terminal moraines, were formed, and now stand as the most conspicuous reliefs of a flat and often monotonous country. In parts of southern Iowa and northern Missouri the glacial cover is a clayey loam, with a peculiar vertical cleavage, and known as loess, similar to formations found in the Rhine Valley and in interior China. By the glacial and associated deposits, the till and sands, the waterlaid clays and the loess, the bed rocks may be completely mantled over for long distances, giving the particularly smooth and unrelieved aspect of much of the prairie region.

But in these spreading mantles of rock waste, we find the secret of the soils. They have not lain on steep slopes of hill or mountain, where their finest and most available nutritive materials were washed away into the sea, but all the gains of weathering and vegetable accumulations have been hoarded through the thousands or tens of thousands of years of post-glacial time. As the surfaces were relatively smooth before the ice swept in, there was less plucking and dropping of large stones and boulders, and hence these do not, as in rougher glacial lands, dissipate the

strength of the plowman and the harvester. Nor is energy consumed in tilling steep hillsides. We have already had reason to see that the drainage of the Great Lakes once went down the St. Croix, the Wisconsin, the Illinois, and the Wabash rivers, and that the Ohio River is far other than it was before the ice invasion. Important changes, too, were wrought in the upper Mississippi.

A most surprising fact about the ice sheets was that none of them covered southwestern Wisconsin. Here is a region, ten thousand miles in area, which is like the Blue Grass region of Kentucky, or like any other region outside of the glacial belt, in showing none of the characteristic proofs of glacial action. Its soils are not made from the drift, but by the decay of the underlying rock, while the ice sheets closed completely around it in Iowa and Illinois. It is not proved, however, that the ice was all around it at the same time. There may have been successive encroachments, now on the east, and now on the west, of the "driftless area."

It is known that some areas of original prairie have been reforested in Indiana since occupation by the white man began. It appears also that some districts in Kentucky had been brought to the prairie condition shortly before civilized society took possession of the ancient hunting-grounds. So far, these facts are favorable to the view that the prairies are mainly due to fires kindled by the native inhabitants of the land. Certain it is that the horizon is more and more broken by woodlands, and that the beauty of the luxuriant ancient meadows will be in some measure restored

in forest and field with the development of an older civilization.

The prairies have their features of climate, and they are as sharp and peculiar as may be found in New England and on the Pacific coast. With little interruption there are lowlands from the Gulf of Mexico to the Arctic Sea. When south winds prevail, the heated air of the tropical belt sweeps unhindered up the Mississippi and Ohio valleys, and the summers are intensely hot in Cincinnati and St. Louis, and they are not cool in Des Moines and St. Paul. For days at a time the thermometer in central Iowa may touch or pass one hundred degrees. And the north winds, in like fashion, take their turn, and bring the extreme winter temperatures of the prairies far below zero. The cyclonic whirls which bring the warm and cold waves sweep from the northwest to the Atlantic coast, following each other throughout the year, and most frequently and fiercely in the winter months. And in these conditions of swift movement of enormous masses of the atmosphere, develops, in the summer months, the dreaded tornado. It is a land of climatic extremes, but the summer heat, with sufficient rainfall and rich soil, brings great harvests, and the tonic of winter's cold is the more efficient because of the drier air that is characteristic of a continental interior. This is more true west of the Mississippi River, where the summer conditions are more favorable than they are in the Ohio River belt.

The prairies display most of their natural riches in the form of soils, a true product of the rocks that lie

below. Silver and gold have they none, save as they gain them by exchange for the wealth of their limitless fields. Nor in general have they iron or other metallic stores. But they have one resource of the under-earth that will mean more and more as their industrial life becomes mature,—they possess, in thousands of square miles, beds of soft coal. In large measure the men of the prairies can afford to plow while others turn spindles and build chimneys, but there must also be some place for the town and the mill. Of waterpower nature has been sparing in this land of low levels and little relief, but she has been generous with her stores of fuel, and hence the central West will not be given over to a monotony of cornfields and grain drills, of threshing-machines and elevators. She can have, in some degree, the diversity which will provide for both her wealth and her culture.

If we consider the people that were to work out its destiny, the Northwest Territory was unoccupied at the close of the War of Independence. There was no settled community of white men in what is now the state of Ohio; unless, indeed, the Moravian missionary settlements of 1772 be counted an exception. But this entire region was in the track of the great migrations of the next thirty years, and its soil and its rivers attracted the first and larger share of these early colonists. Extending from the Lake to the Ohio River, Ohio must be the avenue of all who crossed the Appalachian barrier north of the Cumberland Gap. If they came by the Mohawk Valley, they would skirt the southern shore of the Lakes and

enter Ohio on the north. If they followed the roads laid out in Maryland and Pennsylvania, they would touch the Ohio River at Pittsburg or Wheeling, and enter the region from the south. The first immigrants followed the latter route, for they went out under the Ohio Company, and in 1788 took possession



FIG. 31. River Front at Cincinnati.

of the land where the Muskingum from the north enters the Ohio River. Fort Harmer had already been built on the west side of the smaller river, and the settlers occupied the east bank and founded Marietta. As with other communities transplanted from the East, the traditions of the old home were strong, and the sons of the pioneers, in 1833, founded the school which soon became the Marietta College, thus naturalizing, so far as they could, the spirit of Harvard and Yale on the Ohio River.

Blockhouses were built at Losantiville in 1780, and settlers later came in from New England, New Jersey, and the South. This was far down the Ohio, almost to the mouth of the Miami. This outpost in the western wilderness was soon to be known as Cincinnati; and Moses Cleaveland, a few years later, planted the northern center of the Ohio region at the mouth of the Cuyahoga. By the year 1803 so many people had come in that Ohio was admitted as a state in the Union, and the empire between the Lakes and the Ohio was fairly begun; but it seemed to be thriving at the expense of the East. When foreign trade was active, the people employed, and money plenty, the rush to the West fell off. But when stagnation ruled on the seaboard, the farmers, mechanics, and laborers sold their homes, gathered up what they could, took their children and their goods, in wagons, in carts, and on their backs, and began their weary march from Maine, Massachusetts, Connecticut, and the central Atlantic country to the land of promise beyond the mountains. There fields could be had for little more than the clearing and tilling, there the soil had unheard-of richness, there they would not be put in prison for debt, and there they and their children could start life afresh.

McMaster has gathered from many sources the records and incidents of this early rush across New York and Pennsylvania.<sup>1</sup> From a little Pennsylvania village on the road to Pittsburg, it was reported that a month in 1811 saw the passage of two hundred and thirty-six wagons, with nearly two thousand per-

<sup>1</sup> "History of the People of the United States," IV, Ch. XXXIII.



sons, toward Ohio. Similar stories were told from Auburn and elsewhere in New York. Mount Pleasant in Ohio, from a trivial beginning in 1810, had five hundred people five years later. One hundred and twenty people, from one town in Maine, passed Haverhill, Mass., in a single day, and the westward movement not only stirred the East with fear, but took such proportions in Great Britain as there also to arouse alarm.

In the clearing of the forest, in the rude log-cabin, in the poverty of food and clothing, and in all the hardships of the frontier, the early days of Ohio compare with New York or Massachusetts. It was not a prairie state which could be overrun with a plow in a decade.<sup>1</sup>

Almost the same story is to be told of Indiana, but it came a little later. She already had a populous settlement on the Wabash, but its interest was in the past rather than the future. In her present territory there were twenty-five hundred settlers in 1800; but there were twenty-four thousand in 1810, and seventy thousand in 1816, when she came to statehood. The state had been entered along the three great lines of movement, controlled by geographic features, and now become familiar to us. The first was along the Mohawk Valley and the Lakes, and the stream was soon to become a flood, with the finishing of the Erie Canal. The second approach was by the new National Road, crossing the Ohio River at Wheeling, marked along its course in Ohio by Zanesville, Colum-

<sup>1</sup> The story is well told by King, "Ohio," in "American Commonwealths," Ch. XI.

bus, and Springfield, and entering Indiana at Richmond. The third entrance was from the Kentucky and Cumberland settlements, crossing the Ohio River and coming in on the south.

Illinois had about the same white population in 1800 as her eastern neighbor, and was but two years behind in her admission to the Union, since this took place before the close of 1818. It was but a step to cross the Mississippi. There had long been on its western banks a mongrel population of Spaniard, French, Indians, and negroes, and St. Louis had been a fur-trading post since 1764. But the great inrush followed upon the Louisiana Purchase of 1803, the year in which Lewis and Clark set out from St. Louis on their western exploration. But here, as north of the Ohio, the permanent settlers came from the East. That East, however, was not all on the Atlantic slope, for the sons of the Kentucky backwoodsmen were moving on. More than that, and as if typical of the march westward, Boone himself crossed the Mississippi, lived many years, and in 1820 died on the borders of the Missouri River.

In 1819 Jacob Astor made St. Louis the center of his western fur trade, and in 1821, after stormy times, Missouri became a member of the Union.

At length the stream of population crossed the Mississippi farther to the north and laid the foundations of Iowa. Once a part of Louisiana, later under the wing of Michigan and then of Wisconsin, she was herself to surrender Minnesota and the Dakotas, and in 1846, ten years before a railway crossed the Mississippi, join the sisterhood of states. Iowa has

been called Mesopotamia, and another river crossing set the home seekers over the Missouri, and sent them on the long up-stream trails, by the Platte and the Missouri, that have peopled Nebraska and the Dakotas, and carried the dominion of man to the foot of the western mountains. We may call it about an even century from the time when Boone struck into the Ohio Valley to the day when populous states filled the basin of the Mississippi.

In the eighteenth century the long struggle for the Northwest lay between the East and the Northeast. From the latter realm on the St. Lawrence it had been ruled first by the French and then by the British, with the always uncertain savage now in one balance and then in another. George Rogers Clark, at Kaskaskia and Vincennes, drove the wedge that split the Northwest from the Northeast, and the settlers that poured through the gateways of the Appalachians cemented it to the young nation on the east.

It has been left for the nineteenth century to see whether the prairie country would be tied by the closer bonds to the East or the South, and the answer is not yet given. On the whole, geography favors the South, and there are signs that she may win, or at least divide the spoils of commerce. In those older days, when the frontier was on the western slopes of the Alleghany plateau, both the East and the West shared in the fight for freedom. In the East the more disciplined armies of the thirteen colonies fought the armies of Great Britain. In the West the fiercer fighters of the backwoods won the lowlands of the Mississippi in the critical inch of time that saved the

interior for the Republic. There was enough to do; there was a common foe, and no time for jealousy. But when the war was over, the problems of statehood and of commerce presented themselves, and the Appalachian barrier and the trend of Mississippi waters asserted their power. The conservative East felt that the seaboard had won the struggle, and that her wisdom and her sound judgment were not to be sacrificed to the rough instincts and growing vote of the untutored men across the mountains.

It was not easy to persuade Virginia, in the first years of peace, that she should voluntarily release her subjects, as she regarded them, across the mountains. Nor was it a light task in the face of Indian outbreaks, and the real or supposed neglect of the mother state, to check the self-reliant, and, in some cases, turbulent men, that were for breaking away and setting up an empire in Kentucky. All the motives were hammered to white heat by the talk of cutting off the navigation of the Mississippi. The cleared patches and prairie glades of the Ohio country were beginning to produce more than the hominy needed to feed the pioneer. The trails across the mountains might do as a toilsome road to come in by, but they were no highway to a market. \* New England and the East had no care about boating down the Mississippi. They would be content to preserve the favor of the king of Spain; but not so the Kentucky pioneer, who knew that the water flowed freely to the Gulf, who had timber for flatboats, and produce that he could market in New Orleans, but for a foreign king and a selfish New England. Nor was he

brought to calmness of spirit when one of his bold fellows had taken a flatboat of flour and utensils down the river, had seen it confiscated by Spanish officers at Natchez, had toiled home by land, and had spread over all the transmontane country the story of his wrongs. Such in brief were the conditions, and they were chiefly geographic, that almost carried the West and Southwest to Spanish intrigue and to separation from the states that adopted the Constitution.

But in 1796 a treaty with Spain opened the trade of the Mississippi River, and in 1803 this source of possible disunion was removed by the purchase of Louisiana. But federal writers in the East rung the changes on the folly and iniquity of this vast expansion into remote and alien regions. In particular was the extravagance of the purchase denounced; fifteen millions of dollars for the South and the far West!

When the wheels of statehood and of expansion had been set upon their course, the problems of commerce still arose between the East and West, and they still grew out of the physiography. Water ran downhill, and it was hard to make roads and drag food and clothing and other things across mountains. Hence arose those disturbed cries of Washington and other statesmen of the East, for landways and waterways across the barrier, and thus followed that generation of way-making which has already engaged our attention. When steam had fully established itself on the Ohio and the Mississippi, and the railroads had not come, it would seem that the domain of New Orleans and the South should be complete, and the

prairies become linked to the Gulf of Mexico. But there were at least two causes which threatened, and indeed almost destroyed, the growing and natural union of the north and south Mississippi country. One of these causes lay in the interests which led up by a long road to the Civil War, severing the two sections by loss of sympathy and by several years of actual hostility. The other was the construction of through lines of railway, along easy grades, with swift service, between the prairies and the seaboard. To this of course was added the growth of Lake commerce in connection with railways and canals, and the fact which counts for something, that the Atlantic ports are nearer Europe than are those of the Gulf. With these great unfoldings in the North has gone a relative decline in Mississippi River commerce, and of St. Louis, as compared with Chicago.

But will not the pendulum swing and carry the central states to their natural fellowship with their southern neighbors, giving to geographic conditions their proper control again? Not alone for men is the Mississippi Valley an open road. Professor Shaler has made reference to the resemblances of the animals and the plants for long distances north and south in that country, and to the alternate dominion of tropic heat and arctic cold. The harvesters follow ripening wheat fields from south to north, and the valley is marked out for unity and interchange. Not long hence the prairies may supply the Orient through an isthmian canal; and even a half-dozen years ago we were bidden to look upon the new commercial alliance of the West and the

South, along railways that will carry the surplus products of Nebraska, Kansas, and Oklahoma to Galveston or some other Gulf city by a haul five hundred miles shorter than lies between any of these states and the Atlantic. These projects will be immensely favored as the South develops its manufactures and can provide thus for a haul both ways, making railway traffic profitable, and so much cheaper South than East, that the extra carriage by ship across the Gulf need not be considered. This "probably means decreased revenues for the eastern traffic lines and the related industries, but unless the judgment of the West is at fault, it means better times for the plains. The East may as well realize that its child has come to the years of maturity and is acting for itself."<sup>1</sup> Galveston is nearer by more than two hundred miles to central Iowa than is New York, and there are not wanting signs that here also the north and south lines of movement will in the end be lines of control. Whatever the adjustment be, it will be achieved in another generation, but the prophet may well be cautious, in view of the unforeseen and unforeseeable expansion of artificial waterways.

Passing by the hundred years of fugitive French and British occupation, we may say that the whole West is a product of four generations: it has grown since the War of Independence, and the oldest state north of the Ohio River, reaches this year its hundredth birthday. There is no history here, in the ordinary sense of the term; we have no perspective when we look back, for we are yet in the midst of

<sup>1</sup> Charles Moreau Harger, *No. Amer. Rev.*, CLXV, 383, 1897.

things; and difficult as it always is to separate geographic from other causes, here our perplexities are multiplied, for there has not been time to work out the problems, or, if we may say it, such has been the stirring, that the waters have had no time to clear and let us look to the bottom.

It has been lately said that the East is not the parent of the West, that New England and New York need not boast of so lusty a child, for the South is the real mother. But this is rhetoric, no doubt pleasant to the writer, and as full of fallacy as rhetoric often is. The door was opened by the South, if it was the South that lived on the Holston, the Kentucky, and the Cumberland, and sent forth Boone, Robertson, Sevier, and George Rogers Clark. But we have followed the streams of western migration with little attention, and have read the story of the Mississippi Valley to little purpose, if we do not see that the later fabric, warp and filling, was woven from the East. It was New England and New York that were transplanted to Ohio, Illinois, and Iowa. But Ohio and Iowa did not become a second New England. The stress of a thousand miles of change will strain the most rigid institutions and mold custom and thought into new shapes, even though the material is much the same. Some things were unconsciously lost in the journey along the Seneca Turnpike or the Erie Canal, and other things were as unwittingly taken on from the soil and free air of the prairies. There were no hills to confine the view, and by a very old law, if newly recognized, a change of environment was modifying ancient organs and



unfolding new ones. The East is the parent of the West, but children are different from their parents, and not seldom outgrow them. "Blue laws" could hardly flourish in Illinois, where an exhaustless soil bloomed with glorious color in native meadows, only waiting for the plow to yield a more substantial harvest. Nor were there veins of gold or silver, to lure thousands of daring adventurers and herd them in mushroom cities, where restraint would be abandoned and the worst passions would thrive unhindered. Rather, from the crowded nursery, with its thin soil and doubtful climate, there was a great transplanting, and the prairies gave depth and room and sunlight.

We may take Iowa as a typical prairie commonwealth. Down to 1840 her place in the census is a blank: then she records a little more than forty thousand people; by 1860 she had gained a population of nearly seven hundred thousand, and at the close of the century was the tenth state in the Union, with more than two millions. With this throng of inhabitants, she has one city that passes the limit of sixty thousand. But three others exceed thirty thousand: Iowa is a rural state. A recent writer has perhaps done full justice to the virtues and to the limitations of Iowa:<sup>1</sup> "She is a huge overflow meeting, thronged with the second generation of middle-westerners." So uniform and rich are her soils that scarce an acre in the whole domain need run to waste. Tillage was easy, and the only serious trials in the early days were the prairie fires and the difficult transportation. The latter was solved, as it

<sup>1</sup> "The Iowans," R. L. Hartt, *Atlantic Monthly*, 1900.

seemed, by the railways; but when the short hauls became more costly than the long ones, Iowa "went to grass," saved her soils from running out, and so concentrated her grains into beef and butter that she suffered less at the hands of the railways, and had still before her, as we have seen, an open way to the



FIG. 32. Shade on the Prairies. Cottonwoods in Iowa.

ports on the Gulf. Our writer brings to us another's epitome of Scotland,—"Scott, Burns, heather, whisky, and religion,"—and then gives us his own for Iowa, "corn, cow, and hog." But we will not let him be misunderstood. He does not charge this great commonwealth with dirt and materialism. She may have no history and not yet any material for fiction, but "industry, morality, intelligence, and loyalty," these are hers; and "when your soul is bent upon finding a

happy augury for your country's future, what better can you seek?"

Such traits we may ascribe in part to the type of men and women that would be attracted to such a land to found a home, and in part to steady fellowship with the soil and sky, remote from cities, and set apart to simple and single interests. But the growth of railways did not merely bring an outlet for surplus hoards of grain; it brought inevitable contact with the outside world, and the prairies have not been behind in their crop of social and political ideas. No state in the last generation has been more prolific of public men than Iowa. Prevalent agriculture and the absence of mountains do not mean sordid purpose or narrow vision. The prairies have their own expansiveness and may lure the eye to the horizon when older countries are looking at their own garden patch. A cluster of great universities has grown in the states of the old Northwest. Nowhere has the state fostered the higher education with so steady and so generous a hand. And the small colleges, often too small and too many, have expressed and met the needs of the time, and the fittest will survive. A score of others might be named where we choose one, once a small college, now grown large, — Oberlin, a type of the western school, preserving the integrity and faith of New England, and truly western in its free, modern organization of courses of education.

In political ideas, also, the prairies have not seldom shown the freedom and erratic energy of the frontier, but have invariably swung toward the poise and secure verdicts that are at once as sound and safe as

those of the East, and yet have in them the promise of the future and the courage of action. At first the westerner belonged to the debtor class, and if conditions pressed, he was restless and radical, and impatient with the lenders of the East. It is the land of summer heat and winter cold, with a tornado now and then thrown in, prairie breaths of populism and fiat money, but in the end a nursery of ideas, sound and progressive, outgrowing the vagaries of an infant state, but free from the satisfied conceit and sullen cocksureness of older communities. The man of the prairie is ready for action at home or abroad, balanced by a reasonable culture and poised by an experience whose lessons he does not leave to be learned by his grandsons. Mr. Frederick J. Turner in an excellent discussion of "The Problem of the West,"<sup>1</sup> quotes the assertion of Mr. Bryce, "the West is the most American part of America," and admits that there is force in the claim that if there is a sectionalism in this country, it is eastern; for "the old West, united to the new South, would produce, not a new sectionalism, but a new Americanism."

If we could follow the details of history in these central states, the illustrations of physiographic control would perhaps be as common as they are in New England or New York, unless for this reason, that along the railroads of the prairies towns have been laid out with reference to convenient intervals and sometimes in the complete absence of determining local features. No town was ever so fortunate in a change of name as Cincinnati, whose early appella-

<sup>1</sup> *Atlantic Monthly*, September, 1896.

tion was the unhappy invention of a schoolmaster, L(icking)os-antiville, a thrice mongrel compound, meaning the town opposite the mouth of the Licking.

Like every town by the water, it has come to be the center of many railways, and will retain its greatness though it must now divide its honors with the city by the Lakes. Columbus has no conspicuous geographic causes lying behind its prosperity. It is indeed on the Scioto, it is in the midst of a rich region, but most of all, it is in the center of a rich state and is its capital. It is in part, therefore, due to political causes, and may be briefly dismissed by the geographer. The state has twenty-eight towns of more than ten thousand people, and is thus full of such local centers of trade as must always develop in a great agricultural state. The same is true of Indiana and every upper Mississippi commonwealth. Indianapolis, indeed, is much smaller than the twin cities of Ohio, but added more than sixty thousand to her numbers in the last decade. Like Columbus, she is on a small river, the geographical and political center of a great state, and sends her railways in every direction. Louisville had its beginning in a ledge of limestone in the bed of a river, and in the need of portage, at low water, around the rather high-sounding "Falls of the Ohio." It is a river town, therefore, as well as the metropolis of a state.

St. Louis cannot run in the race with the city by Lake Michigan, yet may hope for great and permanent development as a river town. She is on the Mississippi; is almost at the mouth of the Missouri;

is on the future highway between the prairies and the Gulf, and is in the line of traffic moving between the far Northeast and the far Southwest, and she is at the same time the chief city of a state. Save for Chicago, Illinois is a state of local communities of modest size, and Wisconsin has no interior town of thirty thousand people. These conditions are altogether favorable



FIG. 33. Library and Campus of the University of Nebraska.

for the growth of a strong and clean civilization, saved from the dearth of rural life by the school, the free delivery of mails, and every other means of constant and swift communication. Minnesota has no population centers that compare with Minneapolis and St. Paul, though Duluth, with her fifty thousand people, is a rival in the volume of her business. Aside from these three, Minnesota has but two towns of more

than ten thousand people, and is distinctly a rural commonwealth.

Across the river from Iowa is Nebraska, and Omaha its metropolis. It represents the second tier of states beyond the Mississippi, prairie on the east and arid on the west. It is like its eastern neighbor in its soils, — fine, deep, level, and easily tilled, — and in its dominant agriculture, for its factories are yet to be built. Like Iowa, Nebraska has learned to pasture some of its lands, but here the division is a geographic or climatic one. She found to her sorrow that corn could not regularly be grown west of the middle of the state, and hence adjusted herself to environment, by pasturing the west and plowing the east; and like Iowa, also, she is learning the routes that lead southward, and the bulk of her corn goes to New Orleans. Typical of the progress of this young and physically monotonous state, her state University gathers at Lincoln two thousand of her sons and daughters, and takes no place inferior to cattle or corn in the hearts of the citizen of the plains.

## CHAPTER VI

### COTTON, RICE, AND CANE

IF any reader is disposed to think a blunder has been made in choosing a head-line, no offense will be taken and no defense made. Grain, lumber, and iron would do just as well, and perhaps better, and both together would be better still, for they tell us at the beginning of the old South and the new. Never until now has nature rightly had her way in the Gulf country, but she is fast winning her hold, and that process of adjustment of man to the earth, which takes place in all lands, is here coming about in a day.

The Atlantic plains of tide-water Virginia continue through the Carolinas and merge with like plains about the Gulf. They seem to be separate from each other because the long peninsula of Florida runs so far down into the half-tropical seas, making an outside and an inside realm. But, in a general way, a description of Virginia or South Carolina would answer for Alabama or Texas; for all have outer lowlands and inner uplands. The uplands differ greatly in height and character. South Carolina has little mountain land like Virginia, and no great plateaus like Texas, but they all have the coastal plain, and to the geologist the coastal plain is young, wherever found. Its beds are undisturbed, its surfaces are low



and flat, its rocks are soft, and its rivers often entered by the tides.

The characteristic South of the old days has grown upon this lowland belt, bordering the sea. South Carolina would be as good an example as we could find, for her rivers cross the Piedmont plateau, and, on a dividing line about five hundred feet above the sea, enter the plain belt, and reach the open sea through tidal inlets. The coastal plain makes two-thirds of the state and is more than twice as large as Massachusetts.

In many ways the local life and industries have long been fitted to the land. Sea-island cotton, rice, and truck farming find their place on the marshy plains and low islands of the coast. Between the plain and the plateau is a belt of sandy country, twenty miles wide or more, and the "sand-hillers" live in ignorance and share the poverty of the soil. The "black belt" is along the seaboard plain, for here the cotton, rice, and indigo were grown which made slave labor profitable, often a toil in swamps which the white man was unwilling or unable to endure. Here the blacks vastly outnumber the whites, while in the colder northwest corner of the state, with its poorer soil, its cooler climate, and its absence of rice and cotton, the whites are threefold more numerous than the colored people.

As in the North Carolina lowlands, the railways often run straight toward their destination, as unhindered by physiographic barriers as on the plains of Nebraska. The shore-line of South Carolina, broken like that of Virginia, drew the colonists and gave dis-



FIG. 34. Avenue of Live Oaks, Savannah, Georgia.

tion to its early history. Even if Florida had not been under Spanish rule, she was farther away, and her eastern coast-line was less inviting to emigrants from the more northern peoples of Europe. Georgia was a kind of afterthought to South Carolina, as population extended across the Savannah River westward.

North Carolina is as rich in the gifts of her plains and mountains as her neighbors on the north and south. She has her wide stretch of coastal lowlands, with their fertile soils and genial climate, her Piedmont area of field and forest, and her magnificent mountains. But these counted for little at first, for the land does not present the right front to the sea. The long sand reef that culminates in Hatteras, and the fitful seas outside, cut off easy approach to the mainland; there is no swift retiring, as at Charleston or Cape Henry, into safe and protected waters. Raleigh's colony on Roanoke Island was earlier than any settlement in Virginia or South Carolina, but it did not last, and North Carolina became in the end a resort for the poorer and less intelligent colonists who came to the greater northern neighbor. She was, as Fiske has described her, a kind of backwoods appendage to Virginia. Ignorance, thriftlessness, and disorder long reigned, and it took the colony generations to recover from the unhappy conditions of her early days and become in the end a commonwealth worthy of her domain. All this follows upon the low and sandy rampart which she put in front of the waters of Albemarle and Pamlico.

Florida is altogether a part of the coastal plain, with its low-lying lands and its thousand miles of sea-

coast. Nowhere is there a surface more than a few hundred feet above the level of the sea, and all of its rocks belong to late periods of geological time. From the geologist's point of view, one does not go far back to find the Atlantic shore sweeping around by the Fall Line through South Carolina and Georgia into Alabama, leaving vast tracts of open ocean, where Florida now lies. The old sea bottom has been raised, by the broadest and lowest sort of an arch that can be imagined, to form the wide, flat peninsula that now divides the Gulf of Mexico from the Atlantic waters. Physically so youthful, it is also by far the youngest of the Atlantic states in the growth of civilization, even though the oldest civilized settlement in the United States is on its eastern shore. But this backwardness has no physiographic origin, unless in the rather roundabout reason that the seas brought the Spaniard here for a long and repressive rule. Great Britain held Florida for a few years before and after the war of the Revolution, and in spite of her awkward handling of her American colonies is credited with more advance for Florida than the Spaniard made in two hundred years. No doubt many who have looked with keen feeling upon American doings in Cuba have forgotten, or never knew, that Spain ceded Florida to the United States as late as the year 1821. Great towns have always been few in the South, and Florida is in this more southern than most of her neighbors, for she has but four communities of more than five thousand people. Tampa, Pensacola, and Key West range from fifteen thousand to eighteen thousand, and the metropolis is Jacksonville, with

a little less than thirty thousand, but known far beyond most northern towns of its own size.

That the town will give way to the country in Florida for a long time, and perhaps for all time, may well be believed. She has little water-power, few mineral deposits, and no coal. The only doubtful element would seem to be in her commercial opportunities, which may be very great in the changes that are coming in and about the American Mediterranean. The geographer meets a full share of exceptions to his rules, and one of these comes to light in the flat stretches of this peninsula. He is likely to say that thousands of lakes betoken the recent invasion of ice. But no ice invasion has touched Florida, — nothing colder than killing frosts, — and yet the lakes, in thousands, are here, due, it seems, to the solvent action of water upon the soft limestones of the upraised sea-floor.

And when one goes along the sluggish rivers and lagoons that lie back of the low barriers of the shore, or tries to pierce the thickets of the Everglade swamps, or sees the mangroves dropping their pendent branches to root in the shallow water, or counts the coral keys that link Key West to the mainland, he knows that he is seeing a continent in the making, he has caught the weaver at his work, and about him lies a new fabric, with an unfamiliar stitch and a fresh pattern.

And after all, Florida is not so much unlike the other commonwealths of the South. She is a little more tropical, but is not singular in the fields of cotton, cane, and corn, or in the enormous forests of live



FIG. 35. Orange Grove, Florida. Photograph by Wm. H. Rau, Philadelphia.

oak and pine that afford about half of the annual product of the region. Oranges and pineapples are a little more her own. Florida is something more than a sanitarium for Northern victims of consumption and nervous prostration. The North regards Florida as a comfortable refuge from the blizzards and cold fogs of what is often called spring in those higher latitudes, but when the overcoat has been thrown off, the tourist among the live oaks and drooping mosses may not detect the thrill of business and of new thought that has reached this Land's End. Alligators and even orange orchards are not likely to monopolize a state which has a thousand miles of indented shore-line and thirty-five hundred miles of railroad, with warm skies, rich soil, and plentiful rainfall.

Geologists are familiar with an ancient outline of our southern shore, which comes to mind when mention is made of the Mississippi embayment. This means that sea-waters covered the regions of the lower Mississippi as far north as the mouth of the Ohio River, while a great peninsula of older Appalachian land came down as far as middle Alabama and Georgia. On the west, too, older lands reached into Arkansas. The southern half of all the Gulf states, and all of Florida, had not yet come into being, and the broad, deep gulf of the Mississippi included parts of Tennessee, Kentucky, and Arkansas. Two great lobes of ancient land flanked the embayment. This gulf has filled up, the whole shore-line has moved southward by half the width of the southern tier of states, and Florida is a new land thrown in. And all this young land is coastal plain, continuous around to

New Jersey. There is one exception worth mention, and that is the lowland bordering the Mississippi River. In the old days of the embayment the delta of the Mississippi lay below the site of Cairo; and it has been moving a little farther south ever since that time. The older sea muds of the delta region have been covered up by the muds that came from the prairies and the Rocky Mountains, so that if we dig or bore in the delta we should be apt to find wood and seeds and bones from the land, while if we dig farther west or east we shall find marine shells and other organic growths of the sea.

The Appalachian uplands are even now like a peninsula, — they are a mass of mountain and plateau, reaching out into a plain. In the peninsula the rocks are either folded, or at least much uplifted and hard. In the plain the beds are flat and low and soft. The typical South is this never ending stretch of coastal plain; the opportunity of the South is in its closeness to the useful things on and in the earth within the upland.

In the old days the Arkansas River had its own opening into the sea, and so also did the Red, and whatever represented the Tennessee. But as the gulf filled up, and the edge of the sea was pushed southward, these rivers were joined to the main trunk, so that the Mississippi was growing, roughly speaking, like a tree, at its roots, at its outmost boughs, and by the grafting on of full-grown branches.

Every great river in its lower course spreads down much of the waste that it has gathered in its upland flow. Some of the mud sinks, regardless of the slack



current, far within the banks, and the rest goes out to sea. Every overflow carries the waste widely out on the bottom-lands and builds them up,—the flood plains of the river. The Mississippi has its thousands of miles of these bottom-lands, sloping off from the edge of the river, which drops more waste close by than it does farther away, and, by silting its bed, comes at length to flow on a broad, low ridge of its own making. So we can understand how a break in a levee sends the waters rushing over vast fields of the lower lands.

Of the ten Southern states that border the sea, three, Louisiana, Mississippi, and Florida, belong almost wholly to the coastal plain, and they are throughout low, flat, and young, while all the rest share in the older uplands that lie behind. The average elevation of Louisiana is seventy-five feet, and no point within the state is five hundred feet above the sea. There are twenty thousand miles of river lands, and coast swamps and shallow lakes abound, either lagoons shut off from the Gulf by low barriers, or cut-off lakes left by the wide migrations of the fitful river upon its flood plain and delta. As we might expect in such a land, Florida has but one mineral of importance,—the phosphates; and Louisiana likewise has one,—rock-salt.

The lower Mississippi was to see many changes before it should come to its final place as the southern gateway of a modern and united nation. The Spaniard would come to it first, and, yielding it more than once to the French, would release his final claim almost three hundred years later. Twice after it be-

came, in 1803, a part of the American Union it would be the scene of bloody strife, and only now, as the twentieth century is coming in, is the Louisiana country entering upon the heritage which nature has always held in trust for it. Thus far the accidents of foreign intrigue and the bonds of a social system have laid their restraints upon the land. But now the Gulf plains will be joined to the prairies, the adjoining seas are held in friendly and progressive keeping, the isthmus is to be opened, and New Orleans should become a southern rival of the ports of the East.

The French stamp now borne by the region was given to it in 1700, when Iberville came from the North and planted his colony. La Salle had tried to do what his later countryman did, and in the attempt had come to his tragic end. In the North and in the South, from Minnesota to the Gulf, this race has left the marks of its enterprise and daring, but nowhere has the impress been so deep and so lasting as in New Orleans. Thirty-eight years of Spain, from 1762 to 1800, made little difference, and then Louisiana came back by secret treaty to France, only to be transferred by Napoleon to the new power in the West in 1803.

The Exposition at St. Louis will commemorate this sale, and will, perhaps, recall to some that the Louisiana of that bargain was a narrow strip as now on the Gulf, but widened on the Red River, leaped westward again along the Arkansas, and then took in everything between the Mississippi River and the Rocky Mountains up to the British boundary.

The backwoodsmen of the Appalachians had won Kentucky and then the prairies, and now had faced the issue which led to the acquirement of the west bank of the Mississippi and the Great Plains. If we had not bought this great land, we must in the end have fought for it, for a river is no natural boundary between peoples. It may be difficult to cross it in face of an enemy, and national pride may sigh for such a border, as France for the Rhine, but rivers join more than they divide, and tend to concentrate the life that resides upon their opposing slopes. When, therefore, Jefferson bought Louisiana first, and patched up the Constitution afterward, and, in the same year, sent Lewis and Clark to spy out the new estate and go to the Pacific, he was following the law of reason and of nature.

The river affects the life of the people in very direct ways, and, leaving out the phenomena of the atmosphere, is less easily subdued by man than any other natural feature of our domain. Many years ago Captain Eads devised and planted jetties at one of the mouths of the Mississippi, thus narrowing the channel, making the flow more rapid, and turning the waters into a kind of broom for the maintenance of navigation. Levees are built which restrain the flood, save in exceptional years, and the forewarning of the Weather Bureau adds another element of security to those who live below the level of the river waters. But we may well doubt whether man can ever harness the river with a sure hand. The Mississippi often flows beneath the bluffs that rise from her waters on the east. She has made these bluffs



FIG. 36. River Front, New Orleans.

by encroachment and undermining. Because bluff and stream adjoin each other at certain places, cities have grown at these eastern bends,—Memphis, Natchez, and Vicksburg. But the river is quite capable of forsaking her children by swinging widely to the westward, and it is at least an open question whether man could prevent, or afterward reverse, such a change. It is the willful behavior of the lower river, indeed, which brings in the only grave query as to the future water commerce of the Lake regions and the Gulf. About boats drawing a few feet of water there need be no fear, for skillful pilots from Mark Twain's day until now can "learn the river." Nor does New Orleans as a seaport depend upon the meanders of the stream, save as the produce of the north might in some measure be diverted along lines of rail to other Gulf centers.

Mr. Robert T. Hill, who, more than anyone else, has been the geographer of Texas, has drawn in a few strong lines a picture of her greatness. She is as large as France; or she is equal to the Eastern and Middle states, with Maryland, Kentucky, and Ohio thrown in. She has one-third of the Gulf coast of the United States, and to cross her territory from east to west by rail would accomplish one-third of the distance from Cape Hatteras to Cape Mendocino, or take one from New York to Savannah, Chicago, or Labrador.

In her broad stretch of coastal plain Texas is like other Gulf states. As the plains lead away into the interior they often are interspersed with belts rich in timber. And then the plains rise to vast plateaus,

lofty and arid, bringing the state into relation with the high plains of Kansas and the north. Still farther west Texas embraces an area three-fourths as large as New York, belonging to the southeastern Cordilleras, and culminating in mountains from ten thousand to thirteen thousand feet in height. Texas is therefore a southern and western state, ranging from sandy shore to lofty mountains, with almost every sort of soil, climate, and surface relief.

This vast land illustrates in its own way the progress of empire in America; colonized as a Mexican province by Austin with his emigrants from the north; won to national independence by Houston and his handful of frontiersmen, routing the Mexican army and capturing Santa Anna in a sharp battle lasting eighteen minutes; and coming nine years later, in 1845, freely into the American Union. This is within the remembrance of many who yet live, and marks the movement of our story into a region whose history lies in the future, and in whose bounds man is as yet far from his ultimate adjustment to nature.

The tilling of the soil made Southern history what it was down to the Civil War, and the growth of crops is a matter of soil and climate; it belongs, in other words, to geography. But here also we must be careful not to charge too much to environment. The soils of the South do not shut one up to tobacco, cotton, sugar, and rice; and it was the conjunction of these with the holding of slaves that built up the social system that ruled so long under Southern skies. It was tobacco, which, in the plantations on the Rap- V

pahannock and the James, first showed that Africans could be imported with profit; and then followed the cotton, rice, and cane, in those long belts of semi-tropical lowland which came one after another under the dominion of the colonists. And the better and worse phases of slavery seem also to have followed from geographic diversity; for in the planta-



FIG. 37. Residences on the River Front, Charleston.

tions of Virginia the master lived on the plantation where the slaves wrought, but among the rice and often among the cotton fields of the black belt of South Carolina and the Gulf the master was a non-resident, the toil was severer, and irresponsible overseers were too often left to their own will.

In 1760 North Carolina had two hundred thousand people, of whom one-fourth were slaves. In South Carolina conditions of freedom and servitude were re-

versed,—of one hundred and fifty thousand inhabitants, three-fourths were slaves. The soil of the more southern state was favorable to slave labor.

A chief outcome of this system of things was the great plantation and the great plantation owner. In the cotton belt there could be few small holdings of land, for only the large proprietor could keep a retinue of slaves and grow cotton on a profitable scale. The planter was much like the feudal lord of older days across the seas; he was lord of hundreds or thousands of acres and of the human population dwelling on them. He commanded their service, and he gave them protection, but whether the relation was kindly or otherwise, it was still master and slave. And incidental to this plantation system there had to be another class,—the poor white. He could not acquire land, unless it were a plot of the poorer soil, or back in the mountains; and he could not rise in trade or in mechanical industry, for trade was looked down upon, and manufacture was either primitive and simple, and done on the plantation, or it was elaborate and skilled, and its product brought from England or New England, in return for consignments of cotton.

The Southern gentleman, generous, hospitable, given to public affairs, often imperious and passionate, brought the Old World pattern of society down to the last generation in America. Yet it would not be true to say that the cavalier shaped the entire South. No Southern state is more typical than South Carolina, and the early settlers of South Carolina were in large measure Puritan, and “the economic circumstance which chiefly determined the complexion in



South Carolina was the cultivation of rice and indigo.”<sup>1</sup> The same writer asserts that a single slave could in a year produce more value in rice or indigo than it took to buy him. Remembering human nature, and taking account of the times, the propulsion toward slavery was strong. But taking the South as a whole, we must see that the ancestry of its colonists, the adaptation of its soil, and what we may call the accidental beginnings of slavery, united in ways that defy analysis to produce the old South.

The Southern system promoted the mastery and strength of the few, and produced some towering figures in the early and middle decades of the last century. The family was safeguarded and made permanent, as the sons of the fathers lived on the old plantations and accumulated the ancestral advantages of education, wealth, and social refinement. “In the placid air of their enlightened mediævalism lingered the brave ideals of courage and beauty and gracious dignity . . . and there arose an assertive, sensitive, sincere, dauntless race of men, esteeming life less than honor, and loyalty more than gold, who wrought with a sad, Titanic sincerity for their doomed cause.”<sup>2</sup>

This triangular social system could not develop the riches of the South, for no measure of culture or personal power for the few could atone for the lack of a sinewy, forehanded, and intelligent middle class, and a great army of free, well-paid toilers in field, factory, and mine, whose children might aspire to better things than their fathers could achieve.

<sup>1</sup> Fiske, “Old Virginia and her Neighbors,” II, 325.

<sup>2</sup> Edwin A. Alderman, *Educational Review*, II, 30.

The prevalence and independence of the great plantation, and the absence of an industrial class, caused in the old South a dearth of towns and town life. The men of wealth lived in the country, and for the poor the town had nothing to offer. No general statements can do justice to this condition of the



FIG. 38. Cotton Levee, New Orleans.

South, and we shall have to deal a little in figures. Remembering that the towns have had their great growth since 1865, we will take the nine seaboard states from Virginia to Texas.

There is but one city that compares in size with Cleveland, Buffalo, Pittsburg, or Milwaukee; and New Orleans, with her present population of 287,000, has

gathered more than one-third of her people since 1870. With this exception there is no town of 100,000 people in the nine states, Richmond and Atlanta coming nearest, with 85,000 and 90,000. In 1870 Atlanta had but 22,000, and before the opening of the war she had less than 10,000 people. In this entire chain of states there are 49 towns of more than 10,000 inhabitants, while Massachusetts has 47 such towns. If we seek the totals in both cases of people residing in such communities, the figures stand at 1,525,564 for the nine Southern states, and 2,050,862 for Massachusetts. If we now compare the paltry 8,000 square miles of the New England commonwealth with the 637,000 miles of the nine, the result is little less than astounding. There was vast elbow-room in the early South, and there is still in the new, and a hundred millions of people could live within the valleys and on the wide plains of the old Confederacy.

As the holdings and the tillage of the land were at the heart of the Southern social system, so the first and greatest revolution came in this field at the close of the Civil War. The freeing of the slaves greatly reduced the property of all the plantation owners, and through debts and enforced neglect of their properties for four years, they afterward lost what emancipation might otherwise have left them. They thus could neither own, nor, in the absence of service, till if they did own, great estates, and the lands were in large measure sold and broken up into small holdings, and the building of a new life upon an industrial as well as an agricultural foundation was begun. The mill and the forge and coarse loom of

the plantation must now give way to the factory and the furnace, and such towns must grow as meet the traveler's eye in Connecticut or Pennsylvania. Hence such cities as Atlanta, Columbia, Chattanooga, Knoxville, and Birmingham have sprung into strength, feeling the thrill of new life that followed upon the trying years of first adjustment to the new conditions.

The isolation of the old South has departed with the alien institution of slavery, and with it is passing the conservative spirit that held the states of the Gulf from onward movements of thought. Fiske does not hesitate to say that more Puritanism lingers in the South to-day than is left in New England, but the young South is modern and will be so, as she develops the school, the mill, the farm, and the mine with equal hand. Geographical causes have wrought with power during the last generation to bring the North and the South to common ways of thinking and doing, and perhaps no fair and intelligent person on either side of Mason and Dixon's Line would fail to agree with a son of the South, the Honorable Hoke Smith, Secretary of the Interior in Cleveland's second administration, when he says, "Had it not been for the institution of slavery, checking white immigration and hindering development, the South, with natural resources in its favor in 1860, would have been the greatest manufacturing and mining, as well as agricultural, section of the Union."

Nothing speaks more clearly of the new South than the growth of cotton manufacture. As cotton was first in the ancient system, so it may become in

•

the years of the future. The mill owners of New England do not fear what may be done in Manchester, or anywhere else across the Atlantic, but they must take steady account of what is doing in the Carolinas, Georgia, and Alabama. Before the nineteenth century closed, Massachusetts had sent a commission to inquire into the cotton mills of South



FIG. 39. Cotton Wharf from the Battery, Charleston.

Carolina. The president of a Southern cotton mill rings out no uncertain call to build up the business of the home land: "Every bale of cotton produced in Georgia should be spun in Georgia. There is no such thing as too many mills in the South so long as a single bale of cotton is shipped to New England or across the water." Then he tells the Southern farmer of his losses, when he sells cotton at \$25 per bale, and later brings it back in fabrics or garments

for three times the price, enriching the rich or feeding the distant poor, at the expense of those at home.

All that is lacking at the South is the skilled superintendents and operatives, and these are already available in large degree. The streams of the southern Appalachians will furnish perennial water-power, if indeed, as now seems likely, their forests are rescued and preserved. If water be lacking, coal is plentiful, and in many parts is near at hand. Labor will be abundant, when the colored population have had another decade of industrial training. In one of the new mill towns of the South, visited by a Northern writer, coal was bought at \$1.50 per ton, while competitors in Massachusetts were paying three times that price and more. The saving in freights was \$2 per bale; and while these figures are not the average, they point to enormous savings and untold economic gains for the Southern states, by following the simplest laws of geography, and using their superb facilities for working up the raw materials of the field, forest, and mine.

Cotton did not begin to take its place in Southern industry until 1880. In 1881 the exposition at Atlanta set the ball rolling. On one of the mornings of that summer, cotton was picked from the plant in sight of the fair grounds, spun, woven, and made into a suit, which appeared later in the day on the person of the governor of Georgia. Single establishments in Massachusetts now pay more in wages than did all the cotton mills of the South combined in 1880. But in 1900 there were more establishments in the South than in New England, 400 to 332.

This does not mean that the South is now first, for the concerns are smaller, but she grew from 610,000 spindles in 1880 to 4,298,000 in 1900. In the latter year her capital was \$124,000,000, as against New England's \$272,000,000; but her percentage of increase in the previous ten years was 131, and that of the older home of the industry was 12. The southern cotton crop of the early eighties was about doubled in the last years of the nineties.

But cotton is not king, though it may long be among the great single interests in the South. There is no larger factor in the present unfolding of the South than the diversification of her crops. The wasteful days, when cotton and tobacco wore out the soils, and these were abandoned for fresh fields, are over, and rotation and variety have come in to save the soils, fill up the wastes, give rich and poor a place, and develop the riches of the land to their utmost. There is as much variety of soil and air as in the North, and almost everything that can be raised north of the Ohio can be raised south of it, with a wealth of characteristic fibers, grains, fruits, and timbers thrown in. "Locations can be found in which wheat, corn, cotton, and fruit can be raised in the same field."<sup>1</sup>

It is the day of grain elevators in Galveston, wheat conventions in Georgia, and roller mills in South Carolina.

Thus the newer products are putting some of the older interests far in the rear, as sugar, which in Louisiana holds its place, and may always remain a landmark of the past, even while the product of the

<sup>1</sup> Hoke Smith, *North American Review*, 1894, Vol. CLIX, p. 134.

beet with strides is overtaking it. But another ancient crop still grows, in rice fields of increasing size, cutting in half the importations of the grain, and rolling up to vast values in Louisiana and Texas. Here, too, the South has felt the enlivening touch of modern industry and practical science, for she has learned the uses of irrigation and has largely made her gains through the importation of a new variety of rice from Japan, under the care of the Department of Agriculture. It would be rash to say that the South will not grow her own and her neighbor's tea, and she is releasing herself from the grip of the herders and packers of the plains and prairies.

What more does the South need to warrant the largest prophecy for her future? If it is lumber, she has perhaps the largest reserves yet available in the United States. If it is iron, she has it in veins of unlimited extent. If it is coal, she can supply it through the long future from every Appalachian state. If it is fertilizer, she has the phosphates of Florida and South Carolina ; and she has building stones, clays, asphalt, petroleum, salt, and gold. Her Appalachian uplands, with water-power, timber, iron, and coal are sandwiched between her lowlands with cotton, rice, corn, and fruit. And she is fringed by the sea, whose warm, moist breath gives her blossom and fruit without stint, and anchors in quiet waters at Charleston, at Key West, at Mobile and New Orleans and Galveston the growing fleets of her commerce. Already it has been projected to build for a hundred miles or more, across the coral islets and their shallow straits, a railway from the mainland to Key West,



where, with the new prosperity of the Antilles and the new isthmian canal and the new South at the gateway of the Gulf of Mexico, one of the greatest American cities may in a few generations rise. The southern man cares little for the issues of the past, for the golden chances of to-day and the beckonings of a future too big for his imagining are before him.



FIG. 40. Mississippi Steamer at Levee, Mobile.

It is easy and safe to predict an era not far away when the Appalachians and their Piedmont fringes shall be as full of wheels as New England, sending their products as widely; when northern Alabama and Birmingham shall be another western Pennsylvania and Pittsburg; when the commerce of Galveston will compare with that of Boston, and New Orleans become a rival of Chicago. No region of

the United States is like the South in variety; she has the water-power and spindles of New England, the lumber of the far Northwest, the soils of the prairies, the coal of Pennsylvania, the iron of Minnesota. In every one of these she is a first, or a good second, and in the total outrivals all. Her incubus is gone, the carpetbagger is gone or has left his sons to honest citizenship, and the negro is her greatest problem; but this will be solved by industry and the training of the hand, with growing intelligence and the building of self-respecting character. Not many years will pass before sectionalism, already dissolving, will be lost in the industrial, agricultural, and commercial unity of what for convenience we shall always call one of the great "sections" of our country.

## CHAPTER VII

### THE CIVIL WAR

AFTER the Civil War had closed, a citizen of the South said to Horatio Seymour: "The North would never have beaten us if it had not been for our rivers. They ran from the north into the heart of our country, and we could not get away from you." This must not be taken to mean too much; but it raises many questions and may set us upon thought. The Mississippi does flow from north to south, and joins the prairies and plains to the lowlands of the Gulf. Hence, that man of the Northwest was right who prophesied that the Mississippi Valley must belong to one nation. But the invading armies went down rather than up, because in no other way could the North force the South to stay in the Union. So far as natural highways are concerned, Tennessee could overrun Illinois as easily as Illinois could hurry her battalions into Tennessee.

There is no boundary of much military significance between the North and the South, and indeed the great physiographic belts cross the line and lie partly in one section and partly in the other. New Jersey and Maryland are in no important ways different from Virginia and South Carolina, for all belong to the Atlantic coastal plain. The valleys and moun-

tains of the Appalachians are found in Pennsylvania, and they are found in Tennessee. And the lowlands of the Mississippi continue from the Lakes to the Gulf of Mexico, while farther west the uplands of Missouri and Kansas are separated by no barrier from those of Arkansas and Texas. East of the Rocky Mountains the natural land units were divided between the opposing groups of states.

We may indeed trace a line of rivers and count it for what it is worth as a boundary. The Potomac made such a limit with Maryland and the District of Columbia on the one side and Virginia on the other, but the Potomac did not keep Lee from Gettysburg or Grant from Richmond. Maryland was in sentiment almost as much a Confederate as it was a Union state, and West Virginia was sliced off and joined the North. By any nice theory of river barriers, the Ohio should have marked the line; but Kentucky on her south bank clung to the Union as a commonwealth, while thousands of her men entered the southern army. On the other hand, many in southern Illinois and Indiana were in close sympathy with the Confederacy. Similar things might be written about the Missouri River and the halves of the great state which are made by it. These streams had no large importance for the war, therefore, because they ran through states checkered with opposing ideas, and because the Northerner in accomplishing his aim had to go where the Southerner was, and fight his battles there.

But there were rivers of the utmost importance in the strife on both sides of the Appalachians. In

Virginia the Potomac, the Rappahannock, the York, the James, and the Appomattox all flow southeastward through the lowlands to their mouths in sea or river. Washington is on the Potomac, Richmond is on the James, and every movement of the armies of Virginia between the hostile capitals had to take account of these streams of the coastal plain. And to the west was the Shenandoah River and its valley, a road which neither the Confederate nor the Union commander was ever at liberty to forget.

No less a critical factor in the long struggle was the Mississippi River from Cairo to the Gulf. In the War of 1812 Andrew Jackson had made his name and paved his way to the presidency by crushing a British army with his hardy Westerners at New Orleans. But from 1861 to the summer of 1863 the great river was to yield its points of advantage to this side and to that, after fierce land attacks, bitter naval encounters, and prolonged sieges. If we leave out the Atlantic coastal plain, the rest of the Confederacy was about cut in halves by the Mississippi. Its possession was, therefore, of the utmost importance to both sides. To the Confederates it was necessary, because to hold it was to have free communication for their armies and for supplies between the east and the three great states that lay west of the river. It was correspondingly the object of the Federals to cut this line, and thus isolate from each other the two groups of the Southern states.

The situation was much like that of the thirteen colonies in relation to the Hudson in the Revolution. In both cases we have a chain of states crossed by a



FIG. 41. Tennessee River and Lookout Mountain. Photograph by W. H. Stokes, Chattanooga.

navigable river, and the important points on one, New York and Albany, may well be compared to New Orleans and Vicksburg or Memphis. And if Grant had failed in his attempt in 1863 as Howe and Burgoyne failed in theirs in 1777, the South might have maintained its independence, at least for a time, as the colonies had done.

A little to the east, in Kentucky and Tennessee, are two other rivers which figure constantly in the first years of the Civil War, and often in close relation to the Mississippi. One of these is the Tennessee, born in the mountains of North Carolina and Tennessee, pursuing its way down the Appalachian Valley, turning aside at Chattanooga to cut through the plateau and cross northern Alabama, where it changes its course and flows almost directly north across Tennessee and Kentucky to the Ohio. Another stream, the Cumberland, rising in the plateau of eastern Kentucky, makes a bend much like that of its southern neighbor, southward by Nashville, and then, turning north, runs closely parallel to the Tennessee, and enters the Ohio but a few miles above it.

The Tennessee was to see stirring times at Chattanooga and Knoxville. Both rivers could be navigated by gunboats a long way above the Ohio, and both were to be guarded and stubbornly fought for in the early days of the conflict.

If there had been no Appalachians, the northern people would have had a very different problem to study and solve. But for these, cotton and tobacco would have been spread where now are bold mountains, forested slopes, and a temperate climate. Cot-

ton and tobacco would have brought slavery and the plantation with them, and the South would have been "solid" in a sense that has never belonged to that word. Instead of scores of thousands of Federal soldiers from the uplands and forests, there would have been a vast increase of the Confederate armies, and what might have been the issue of such a contest we can never know. Virginia was divided against itself, and the mountains went to the Union, and the plains joined hands with the South. Even in Tennessee were many Union citizens, and it was at one time a prime object of the administration at Washington to bring an army into eastern Tennessee, to co-operate with the great body of sympathizers with the North that was to be found in the mountain valleys and on the Cumberland plateau.

If there could have been any doubt before, the great conflict seems to have proved that our land, from east to west, is cut out for one people. The Appalachians were a great barrier in colonial days, but we cannot think of them as a national boundary, now that the forests are so largely cut away and the highways of traffic run everywhere. If this were not enough, there are open gateways betokening unity along the St. Lawrence and the Mohawk, and the wide Gulf plains wrap completely around the southern end of the mountains, joining the plains of the Atlantic with the prairies of the Mississippi. The Rocky Mountains alone, within our domain, might conceivably divide nations, and now, almost forty years after 1865, we can look with a bird's eye upon the physical features of the United States and say



that final union was inevitable. The only other possible thing would be a group of changing and quarreling powers, for two compact, stable republics could not arbitrarily cross all lines of geographic control and live side by side in peace.



FIG. 42. Vicksburg from the West. Photograph by A. L. Blanks, Vicksburg.

Professor Shaler, in his history of his native commonwealth, Kentucky, has described what he well calls the "geological distribution of politics" in that state. The Blue Grass region, rich in its limestone soils, was hospitable to large holdings of land, the slave system was dominant, and here were the strong southern majorities. The poorer sandstone soils, on the other hand, especially in the large and wilder tracts of eastern Kentucky, supported a poorer popu-

lation which was commonly hostile to slavery, and furnished many hard fighters for the Union armies.

Thus the rivers, the soils, and the reliefs of the land are all to be counted in if we would appreciate the causes that led to the war, or would understand its campaigns and its battles. Before we study some of the more special problems we must recall one very general condition that had a profound bearing on the fortunes of the South, namely, their almost exclusive agriculture. They did not have the mills and the shops to make what they needed for peace or for war; and when northern gunboats at last made the blockade of southern ports effective, the pressure on the South was severe, for she could neither send out the cotton which would give her money to buy, nor could she count on bringing in, after she had bought them, the munitions of war or the necessities of life.

Not trying to follow, in this short sketch, the strict lines of division into military departments, we can see in a general way how the centers or lines of action located themselves. For the South to hold independence, or for the North to enforce union, there must be a struggle between the Appalachians and the sea; and because the two capitals lay, one in Virginia and the other on its edge, barely more than one hundred miles apart, the first and last great operations of the war were between the Potomac and the Appomattox. And because the South had an extended shore-line and many harbors, and foreign commerce was vital to her success, swiftly improvised navies on both sides made the ocean border the theater of some of the hottest and bloodiest fighting

of the war. West of the Appalachians lay the Mississippi Valley and a river whose final holding was vital to success on either side. Here lines many hundred miles long had to be maintained; here rivers were fortified, railways were few but important; here the great generals of the war were taught, and here some of the most brilliant battles of the war were fought. It was not until this great campaign ground was in full possession of northern arms that there could be sufficient concentration in Virginia to bring hostilities to a close.

The first line of outposts established by the southern forces lay in Tennessee and Kentucky, well down toward the Ohio River. If this could be held, there could be no effective or lasting invasion of the lower Mississippi country — unless it came from the sea. And such a line would serve as a base from which to win the Ohio and harass or overrun the states lying to the north. The main artery to be held was the Mississippi River itself.

Cairo, at the junction of the Ohio with the Mississippi, was held by the newly commissioned General Grant. About a dozen miles down the river, upon a high bluff on the Kentucky side, was Columbus, which the Confederates had strongly fortified, planting there 120 guns. This was the Confederate left, and is a good sample of those fortified points mainly on the east side of the Mississippi, well suited by nature for military defense, because the river offered a natural moat on the west, and the batteries could hurl a plunging fire upon vessels going up or down.

Sixty miles or a little more to the east, the Ten-

nessee and Cumberland rivers in parallel courses flow north across the southern boundary of Kentucky. Just south of the line, in Tennessee, Fort Henry had been erected on the east bank of the Tennessee, and Fort Donelson on the west bank of the Cumberland. These two points of defense were scarcely a dozen miles apart, and so long as they were held, Tennessee could not be invaded from the north along the valleys. This was especially important, because Nashville lay on the banks of the Cumberland, and it was appropriate, therefore, that Donelson should be the stronger of the two forts.

About eighty miles northeastward from Fort Donelson was Bowling Green, at the point where the railway from Louisville forked toward Nashville and Memphis. Here was the Confederate right, and the line, like a crescent, swung down into Tennessee, across the twin rivers, and back into Kentucky, to Columbus, on the Mississippi. It was the object of the South to hold this line, and any proposals to push it toward the Ohio or invade the North were dismissed. But the North had no alternative but to try to break the line. A step in this direction had been taken when Grant sent a force up the Ohio and occupied Paducah, at the mouth of the Tennessee.

It was possible to make a direct effort to open the Mississippi, and this at first was planned, but this involved great difficulties. Columbus was likened to Gibraltar: ships alone could not destroy this secure perch on lofty bluffs. A land force could not take it, so long as connection along the river was open. To have attempted the post would have involved a

siege, and might have anticipated much that happened about Vicksburg more than a year later.

General Halleck decided upon a different plan, which was carried out by Grant and Admiral Foote. The center of the line was to be broken by a land and water attack upon Fort Henry and Fort Donelson. If these could be carried, the two rivers would be open, Nashville would be exposed, and the whole southern line would be pushed southward. And so it turned out: Fort Henry was taken, and as soon as Fort Donelson was invested, Bowling Green was abandoned; and as soon as it fell, Nashville was given up also; and on the west, Polk withdrew his stores and forces to Island No. 10 and New Madrid, thirty miles or more down the river. The stream there makes a great double bend, and the town, although ten miles northwest of the island, is still down stream from it. But the possession of the Tennessee and Cumberland rendered this position and outpost too exposed to be long held, and the next withdrawal was to Fort Pillow, fifty miles down the river in Tennessee. It was much like Columbus, being on a high bluff east of the river; but the flanking movement on the east had carried the Federal forces still farther south, and the great battle of Shiloh was fought, inflicting vast losses upon both sides, but leaving the Federals in possession of the Memphis and Charleston Railroad, and jeopardizing such positions as Fort Pillow and Memphis on the Mississippi. The issue of the naval combats at both these points was favorable to the North, and the positions were yielded without siege or land operations of any kind.

Our object must not be lost from view, which is not the story of marches, attacks, or capitulations, but to see how the large lines of movement were made ready by nature, and seized upon by men versed in military strategy. It was seen by Halleck that fugitive operations west of the Mississippi could have no great relations, although they had been important to the North, since, in the first months of strife, Missouri had been restrained from going out of the Union. But now the river and the states to the east must be held by the side that would win. Everything west of the Appalachians belonged to the combatant who could hold the Mississippi, the Tennessee, and the Cumberland. If the North could do this, it would cut off Texas, Louisiana, and Arkansas from the Eastern states of the Confederacy, and center the conflict on the Potomac and the James. Halleck saw this without question, though it required his greater subordinate officer and two years of tenacious struggle to bring it to pass.

The campaigns around Vicksburg illustrate both the local and the general problems of the Mississippi in those days of war. Most of the river above that point had been opened by Federal gunboats, while Farragut from below had taken New Orleans and Baton Rouge, leaving only Vicksburg and closely associated fortresses in the hands of the Confederates. Farragut had run under the Vicksburg guns, and said it could be done again; but this would not do for regular transmission of men and supplies. So long as this single point could be maintained, therefore, the South could keep her enemy from using the river, and

the enemy could not keep her from such communication as she might wish between the Eastern and Western Gulf states. So strong was the position that the repeated efforts of such commanders as Sherman and Grant were foiled, and one plan after another was given up.

Vicksburg is one of those river towns which have been determined by a bluff, at the base of which flows the stream. Upon any good map of the region there is evidence enough that the river does not always keep the same track; but here for the present is the bend, and on the slopes to the east is the town, stretching up to the low plateau above. It is a rule of meandering streams also to cut a deeper channel on the outer curve of the bend, and thus we can see two reasons for the growth of a town, for there was a commanding site high and dry above the swamps and bayous on the west, and there was approach for the largest vessels to the wharves at the base of the bluffs.

Both above and below Vicksburg there is a considerable tract of the low bottom land lying between the Mississippi and the base of the bluff. North of Vicksburg, the Yazoo River follows the foot of the escarpment, and then, through a maze of lakes and swamps, bears to the west and enters the Mississippi. Vicksburg is on the steep slope that separates the bottoms from the upland. West of the city a great meander doubles the river on itself, as it flows first to the northeast, and then abruptly southwest, under the city. Above is the Yazoo, sending its several mouths into the Mississippi as the greater



FIG. 43. Vicksburg from the North, showing the Great Bend of the Mississippi. Photograph by A. L. Blanks.



river sends her distributaries into the Gulf. One of these is Chickasaw Bayou, under the Walnut Hills. From the river opposite Vicksburg runs the railway to Shreveport, and north and south of this road is a tortuous network of bayous and swamps.

A fleet could not capture the town, perched upon its heights. And when Grant at last was free to make the trial, he proposed to come at his goal by a combined attack, sending Sherman down the river to the mouth of the Yazoo, and coming himself from the northeast. The cowardly surrender of Holly Springs by an unworthy subordinate, and the loss of vast supplies stored there, compelled Grant to abandon his plan until a new base could be established. But meantime Sherman had gone down the river, only to find himself among the marshes of the lower Yazoo, exposed to the sharpshooters and batteries of the towering wall on the east, and without the support that was planned. He failed completely and withdrew, to share the fortunes of Grant when later it was decided to make the river the great line of approach from the north.

Grant's problem was to get a foothold on the plateau back of Vicksburg and at the same time keep an open line of communication from the north. His attempt to come directly to his goal had failed, and he will now try it from the lowlands and the river, moving down in conjunction with Porter's fleet. He does not attempt the bluffs north of Vicksburg and east of the Yazoo, for the obstacles were too great and Sherman's failure there had made them known. He does try to complete what had the year before



**FIG. 44.** Shirley House and Federal Encampment, Vicksburg. From a View taken at the Close of the War.

been begun, — to turn the Mississippi across the narrow tongue of land within the bend, at a point four miles below the city. If this could have been done, there would have been no need to capture Vicksburg; for, isolated from the river, it would have been no more important than any similar town. But Grant failed in this, and again nature gave her favor to the Confederates. Indeed, such was their confidence in the difficulties of the ground, that the lowlands were practically unoccupied, the batteries commanding the river being thought sufficient. Unsuccessful efforts also were made to find or cut navigable channels among the bayous on the west, between Milliken's bend on the north and New Carthage on the south.

What Grant did was to take his army swiftly across the watery lowlands, — while Porter ran his boats under Vicksburg loaded with supplies, — cross the Mississippi thirty miles below the city, cut loose from his supplies, seize Jackson and the region east and south of Vicksburg, fight several battles upon the provisions carried in knapsacks, keep reënforcements from coming to Pemberton, drive him into Vicksburg, and open communication with the Mississippi north of the city. The difficulties interposed by physiographic conditions were so great that a much larger army must have been required by a commander of less judgment, promptness, and daring.

The underground formation in and about the town to which siege was now laid was such as to give distinct shape to the events of the hour. The great mass in which the Mississippi has carved the high bluffs consists largely of tough clay, so coherent that

vertical walls of it will stand for many years. Thus we can see how easy it was, when the bursting of shells went on week after week, until scarcely a dwelling was unscathed, to burrow in the earth, and live, as thousands did, in subterranean rooms. The same conditions made it easy to open tunnels, in which mines could be sprung. The plateau also is furrowed by short ravines which have been made by the streams that drain the heights toward the river. They could only be short; for a dozen miles east of the city the Big Black River runs parallel with the Yazoo and Mississippi toward its union with the latter stream. These ravines alternate with narrow table-topped spurs, which could be easily fortified so as to command every point in the ravines with cross-fire. Hence it was that the siege line could not be drawn too closely around the beleaguered city, but had a length of eight miles from bluff to bluff on the north and south.

It should not be thought that Vicksburg ended the war in the southwest, while the Federal army had still a daring and persistent foe in the fertile region west of the Mississippi. The bayou country was still to embarrass the invader with conditions of war that could not be found in the north. Early in 1864, following the capitulation of Vicksburg, an expedition was planned for the west, which resulted in entire failure. A force was to go up the Red River, take Shreveport near the Texas border, disperse the Confederate forces in those places, and make accessible the cotton and other supplies of Texas. There was to be a fleet on the river, but land communications must also be

kept up, for the river is subject to changes that would hinder the passage of boats. Indeed, a map of the river belt shows a kind of geography that is rarely seen — many tributaries swollen into lakes, making the whole river above Alexandria look like a ragged cluster of grapes. A sluggish stream grafted upon the Mississippi, setting back with the silting of the bottom of the trunk river, builds up its own bed in turn, and thus ponds the water in its own branches, forming the lakes already mentioned.

Thus the country was difficult, the expedition was blunderingly handled, the Confederates moved rapidly and fought fiercely, thousands of men and many guns were lost, and the Federals were fortunate in bringing off a remnant of their invading force. The national campaign had, in the words of Draper, "but one redeeming feature — the engineering operations of Colonel Bailey." Porter's fleet was caught at Alexandria by the falling of the waters, making its abandonment and destruction probable. The Yankee engineer, in the face of much ridicule, built a dam at the falls, deepening the water and allowing the vessels to pass. The retreat was thus at last successful, but the expedition was a defeat, and a disgrace as well, to the Federal arms.

If there is a point in the South which for the uses of strategy compares with the lower Mississippi, that point is the southern gateway of the Appalachian Valley, the country around Chattanooga. This region is sharply defined in all its geographic features. On the east are the wild forest slopes of the Unakas; on the west is the frowning Cumberland escarpment



FIG. 45. Chattanooga and Missionary Ridge; looking East from Cameron Hill. The Small Hill, X, on this Side of the Ridge is Orchard Knob, Grant's Headquarters during the Battle. Photograph by W. H. Stokes.

and the Cumberland plateau. Down this great valley to the southwest runs the Tennessee River, already majestic with the tribute gathered from the mountains and valleys of Virginia and North Carolina. But instead of passing out at the wide-open southern door, it suddenly swings off to the right, and follows a deep gorge through the plateau into Alabama.

Just where the river leaves the spacious Appalachian Valley and enters the plateau is Chattanooga, on the east bank. Northward the railway runs, eighty miles, to Knoxville, on the river also, and then on into Virginia to Richmond and Norfolk, or down the Shenandoah to Harpers Ferry. Westward, through the gorge, is a railway which branches in the northeastern corner of Alabama, and leads to Memphis and Nashville. Southeastward, another line connected with Atlanta and Savannah. Chattanooga, therefore, by nature, and by man's use of nature, is a key to all military movements in the southern Appalachians, especially as it controlled at that time the only direct line of communication between the southwest and the Confederate capital.

A little below Chattanooga a small stream, called Lookout Creek, enters the Tennessee from the southwest. It flows in a narrow valley which it has cut in the Cumberland tableland. East of it runs a long, flat-topped hill, about fifteen hundred feet above the valley. It is like a wedge, narrowing at the north and ending at the bank of the Tennessee where the river turns west at this point, forming Moccasin Bend. This hill is a spur of the plateau, and is the historic Lookout Mountain. Standing upon its northern end, one may look

northward upon Chattanooga and the river, eastward over the wide lowland, and westward across the gorge of Lookout Creek upon the parent plateau, from which the observer's perch has been separated.

Between Chattanooga and the river is Cameron Hill, nearly two hundred feet in height. We may stand on this, as upon the stage of an amphitheater, and see all the features that controlled the lines of battle. Lookout Mountain, with its steep slope, crowned by a sandstone cliff, is south, on the right. The river is at the left and in the rear. The city is directly in front, and three miles to the east runs a hill extending from north to south for several miles, and three hundred feet high. This is Missionary Ridge ; it is a small example of the innumerable worn mountain ridges that run up and down the Appalachian Valley from Alabama to Pennsylvania. It is the upturned edge of a mass of the Knox dolomite, the common rock on the floor of the great valley in this region. It has not only been turned partially on edge, but has been pushed, in ancient days, from the eastward somewhat over the rocks that form the base of the ridge. The geologist would say that the structure shows a fold and a thrust fault.

Now we have the conditions of battle, but we must go a few miles south from Chattanooga to follow the line of events. In September, 1863, a little more than two months after the capture of Vicksburg, the Federal army entered Chattanooga, under Rosecrans. The Confederates under Bragg were believed to be in retreat southward, but were in reality preparing for aggression. Rosecrans moved out and was met at



Chickamauga, twelve miles southeast of Chattanooga. Here is another longitudinal stream, Chickamauga Creek, parallel to Lookout Creek, the Lookout Mountain Ridge, and the Chattanooga Creek; its Indian meaning is the River of Death. The bloody battle on the banks of this stream was a defeat for Rosecrans, and would have been a rout but for Thomas, the "rock of Chickamauga." The *rocks* of Chickamauga are not so well known, those gently slanting beds of limestone whose outcropping edges furnished a natural fortification to many riflemen in the two days of battle.

Rosecrans took refuge in Chattanooga, and his foes well thought that he was in a trap. But he was relieved from duty, and Thomas was in command, until Grant, now free, could be brought, from the west.

Our story of the great battle can be told in a moment, for our only purpose is to see how the movements of war followed the forms of the land. The Confederates held Lookout Mountain and Missionary Ridge. Grant observed the great battle from Orchard Knob. He deployed his army in three divisions,—sending Hooker to dislodge Bragg's left from Lookout Mountain, Sherman to push back the enemy's right, and Thomas to storm the Confederate center on Missionary Ridge. That this was perhaps the most spectacular battle of the war was due primarily to the geographic conditions, but also to the unerring skill and certainty with which the plan of battle was carried out by the three great subordinates of the commanding general.



**FIG. 46. Moccasin Bend, Tennessee River, from Point Lookout. Photograph by W. H. Stokes.**

It would require a separate chapter even to sketch the geographic conditions which controlled the movements of the great armies in Virginia from 1861 to 1865. We have more than once in this volume had occasion to look upon this part of the Atlantic coastal plain, backed by the mountains and crossed by tidal rivers flowing to the southeast. Roads were few and in part because the rivers were many. The ground was often flat, swampy, and covered with forest, while the maps were too commonly poor and inadequate. The direct line of attack or retreat between Richmond and Washington lay across the rivers and these tangled lowlands. A dilatory, not to say timid, commander kept the Federal forces from striking a blow, and allowed Lee to organize the Southern army, and maintain an ascendancy that was never shaken until Grant came from Chattanooga to Virginia.

McClellan had made himself a slave of geographic conditions when he had organized his costly and useless Peninsular campaign, by which he intended to come up between the York and James rivers and enter Richmond. But commanders who win are not only organizers and strategists and students of the map — they are fighters, a consideration never to be overlooked in the study of campaigns.

The Shenandoah Valley, lying behind the Blue Ridge, offers, in connection with the Virginia lowlands, perhaps the best illustration of our theme in all the South. The relations of this "Valley of Virginia" were briefly given in Chapter III. We there traced it northward beyond Harrisburg and southward to Chattanooga. All its northern portion in Virginia




FIG. 47. Shenandoah Valley, Luray.

drains through the Shenandoah into the Potomac at Harpers Ferry. West of the immediate valley of the Shenandoah are other parallel valleys and ridges until we come, farther west, to the Alleghany escarpment. Snugly protected by mountains, well watered by many streams, rich in soils derived from ancient beds of limestone, filled with fertile farms and comfortable homes, it afforded a scene of rural beauty and human prosperity, until in the four years of war it was found to be a great highway for armies. Running transverse to the rivers of the plain, and cut off from them by the Blue Ridge, either army could use it to flank the other, although it was the Confederates who used it most.

At the very beginning of disunion the shops and arsenal at Harpers Ferry were seized, and war did not desert the valley for the next four years. In 1862 Stonewall Jackson was sent beyond the Blue Ridge to make a diversion that might destroy the effectiveness of McClellan's campaign in the Peninsula, especially by threatening Washington. Jackson enacted along the Shenandoah one of the most brilliant chapters in the history of the Confederate arms.

It was expected by McClellan that he would take to the Peninsula one hundred and fifty thousand men, but in this he was disappointed. Jackson being in the valley, the President held back thirty-five thousand men under McDowell to defend Washington. Banks was sent from Manassas to Winchester, and McDowell was ordered to Manassas. Jackson thus had McDowell on his right, Banks in front of him in the valley, and Fremont in the mountains on his left. His object was to



**FIG. 48. Shenandoah River.**

crush them one by one before they could unite. He drove Banks on a breathless retreat down the valley, until the Federal soldiers had crossed the Potomac to avoid destruction. He then sought and scattered the force under Fremont, and was ready to give fierce battle to Shields who had come across the Blue Ridge from McDowell. Having already diverted McDowell's great corps from McClellan, he now himself hurried to join Lee. "Thus in thirty-five days Jackson's army had marched two hundred and forty-five miles, had fought three important battles, besides two minor ones, winning them all, and had practically destroyed three Union armies."<sup>1</sup> The next important movement in the valley led up to the greatest and most critical battle of the entire war. It was in 1863 when Lee determined to execute the vast flank movement that should carry him down the Shenandoah, across the Potomac, through Maryland, into Pennsylvania. Nature had planned a spacious highway and walled it in. Through this avenue Lee would go, and transfer the seat of war from southern to northern soil. Once across the Pennsylvania line Lee turned to the right, entered the passes of the South Mountain, thus leaving the valley to the west, and met the Union army at Gettysburg. After the battle Lee withdrew across the Potomac, as he had come. Failing to reap all its advantages, the North had won a great victory, and at a most dramatic moment, — on the day when the future commander of the Potomac was receiving the capitulation of Vicksburg.

In 1864 Grant was before Petersburg and Lee

<sup>1</sup> "History of the United States," Adams and Trent, p. 391.

sent Early to make in the valley the same kind of diversion that Jackson had made. Early was a fighter, but he was not Jackson; and it was not McClellan now, but Grant, who stayed stubbornly where he was and sent Sheridan to take care of the Shenandoah. Early had even appeared before Washington, but was soon driven out of the valley by his foe, and the brilliant Irish soldier under Grant's orders proceeded to burn everything that could subsist an army. The Shenandoah Valley was a smoking ruin, and it was thereafter to know the pursuits of peace.



## CHAPTER VIII

### WHERE LITTLE RAIN FALLS

NEW ENGLAND, or the Great Lakes, or the South, offers us a single continuous region, but when we study the pattern of the West, it is a patchwork, made up of mountains and plateaus, and the latter are often so smooth and so girt about with mountains that we call them plains. And these plains are so dry that they have long been put in a bundle and called the arid lands. Their dry climate is the feature which more than all others affects the lives and doings of men, and therefore we place under a common title lands as remote from each other as the plains of western Kansas and the great valley of California.

The westerly winds strike the edge of the continent, heavily freighted with vapor from the warm Pacific Ocean. When these seas of moist air roll up the cooling slopes of the Pacific mountains, condensation is rapid, and abundant rains and snows support the forests and feed the glaciers of these lofty lands. East of the mountain belt, which includes western Washington, Oregon, and much of California, the arid lands begin, and they include nearly all the territory eastward to about the hundredth meridian. This line runs through the Dakotas, central Ne-

braska, and western Kansas. It is not the exact climatic boundary, but is nearest it, and it is easy to remember that eastward more than twenty inches of rain fall in a year, crops are raised without artificial watering, and we call the lands prairies. West of the line there is no sudden change either of climate or topography, but on the average the rainfall is less than twenty inches, and irrigation is needed, except in unusual seasons, or for crops that require but little water.

From western Kansas to the Sierras is a solid arid country, save patches of mountain land which are cold enough to condense and comb out of the atmosphere the water that yet remains after it has swept over the Pacific ranges. This area of dry land in the United States is enormous, and in much of Utah and Nevada the rainfall is less than ten inches, and in parts of Nevada and southwestern Arizona it is less than five. That an empire of a dozen states and territories should sometime lie in this arid country would not have been dreamed by the early explorers, who thought themselves lucky if they eluded the savage, and got water enough for man and beast. They wrote the region down upon the maps, at least so much of it as lay east of the Rocky Mountains, as the Great American Desert, and made it seem to the childish geographer behind his atlas at school as inhospitable as the Desert of Gobi or the Sahara. Indeed, in such mistaught minds, a desert was a place where nothing could live or grow, for the world had not begun to learn its wealth of life, or to discover those changes of heredity and environment by which

lowly populations are fitted to the dryest and wettest, the hottest and coldest, the steadiest and the most shifting conditions.

There was no dearth of life on the Great Plains before the prairie schooner crossed them, or the swift train sped without hindrance from Omaha to Denver ; the savage knew the highways of the plains, the buffalo and prairie dog made them populous, and the desert grasses thrived and kept the sands from nakedness. The green slopes of New England would be missed and might be sighed for, but the skies were always bright, the gray landscape had its own spell, and it was the land of the imagination, with vastness like the sea.

When we cross the hundredth meridian, going west, we begin to be three thousand feet or more above the sea, and when we have reached the eastern base of the Rocky Mountains, in Wyoming or Colorado, our altitude is five or six thousand feet. We have crossed a plateau which has a gentle slant to the east. The rivers flow out of the mountains and down this upland floor toward the Mississippi. Such are the Missouri, the Platte, and the Arkansas. In many places in Kansas the Arkansas River and its branches flow almost on the surface of the country, or have cut shallow valleys, barely one or two hundred feet below the plains. There is good reason for this in the long, gentle slope over which the rivers must run, and in the soft and destructible strata in which they often work. The streams cannot have much velocity, hence their working power is small. And the land waste is so abundant that it clogs the streams, and



FIG. 49. Pike's Peak from Pike's Peak Avenue, Colorado Springs. The Growth of the Cottonwoods is made possible by Irrigation.

they become, as the geographer says, "overloaded," and tend to struggle over a waste floor of their own making, frequently dividing into strands which reunite, making a "braided" river, such as the Platte often is. This tells why the French discoverers saw a torrent of muddy water when they passed the mouth of the Missouri — waters described by a modern witness as "too thick for a beverage, too thin for food."

Yet we must not let ourselves think that the country is as smooth as it might appear to a tourist on the Union Pacific or Burlington Railway. The rocks are not all soft, but they are nearly always horizontal, and the weathering of the softer strata leaves the edges of the harder often outstanding in escarpments, or walls, that relieve the monotony. And in many parts of western Nebraska, and elsewhere, the fitful streams of this country and the perpetual weathering have cut the strata into a maze of scarps and slopes, which remain utterly naked and barren, through failure of herb and tree, and make what the early French voyageurs called *mauvaises terres*, bad lands — bad to them because they were hard to travel over, as bad they must always remain, save for weird scenery and their great harvests of fossil remains, which have kept many scholars to their tasks and filled many museums.

In some parts, too, the winds have shifted the waste and done what they could to give variety to the land surface. This has especially happened along the rivers, which have made the earth and sand available for wind action. The contoured maps of the plains will often show, by the crowd-

ing of small circles and ellipses, great patches of such dunes on the leeward side of the Platte, the Arkansas, and lesser streams.

The land is not, then, absolutely smooth, for rivers and winds and weathering have diversified it much, but reliefs of a few hundred feet count for little when the eye sweeps vast areas, reaching from Dakota to Texas.

There is a central belt of the Great Plains which is smoother than the rest. It runs through Nebraska and Kansas and into Texas, and has been distinguished as the High Plains. We can better understand them if we go back to the origin of the Great Plains as a whole. Under these lies a vast floor of older beds of marine origin. After this sea floor was uplifted it was overswept for long by river torrents from the young and high mountains on the west. These torrents wandered this way and that, and laid down the materials that now form the surface parts of the plains. Thus there is a veneer of younger waste, often five hundred feet thick, carpeting a floor of harder and more ancient rocks.

In this central area there is rain enough to allow the forming of a sod, which is firm enough to check erosion by rain and by small streams. Hence, the old debris plain is almost perfect in its preservation. West of it, however, as in eastern Colorado, there is less rain, no real turf can form, and yet the streams from the mountains are more forceful than farther east, because nearer the rain belt of the Rockies. Hence, though it seems a contradiction, the semi-arid, middle belt is smoother, and has suffered less

erosion than the arid belt west of it or the well-watered prairies east of it. The character of this singular land, with its horizon like that of the ocean, can be read in a recent report of the United States Geological Survey.<sup>1</sup>

As distinguished from the still drier plains on the west, the High Plains became known as the "rain belt," and there followed on this several years of the most disastrous experiment in agriculture ever tried in the United States. Every one knew of the fertility of the prairies, and the prairies lapped well over into central Kansas and Nebraska. So the inrushing settlers, from 1885 to 1895, failed to mark that vague but stern boundary which separated the regions of ample and deficient rainfall.

As if fate were in league with their ignorance, there were in this period several seasons of increased rainfall; and it was bravely asserted that the climate was changing, and some thought the plow was doing it, and that any region once plowed and set with patches of trees would woo the rains.

In earlier days, when the westward extension of slavery was pending, Kansas had seen storms that rivaled her tornadoes. But she never perhaps saw so much suffering or enacted so large a social and geographical experiment as when excited emigrants from the East, or men who found no place in Illinois or Iowa, rushed across the one hundredth meridian and began to take up quarter sections, lay out cities by the square mile, build county seats and court-

<sup>1</sup> "The High Plains and their Utilization," by Willard D. Johnson, Part IV, Twenty-first Annual Report U. S. Geological Survey.

houses and palatial schoolhouses, and boom the country. One might expect such conditions at Virginia City a generation ago, or at Cripple Creek in later years, but hardly on the dull, endless acres of western Kansas.

The men who worked the boom did not bring their money in their pockets or draw their checks on eastern bank accounts. The checks were drawn in the East, but by men and women who, with equal haste, accepted mortgages upon lands they never saw, lands which, with square miles enough, would raise cattle, but would not raise wheat. When the bubble collapsed, many men had learned many things. One dry season after another taught them that the climate had not changed. The boom towns did not fill up; the farmers had no money with which to pay interest, to say nothing of principal. Banks and loan companies failed, the eastern lender and western borrower had hard feelings toward each other, and the one became wisely conservative about western investments, and the other learned economy in a hard school, either by sticking to the ground, or after his prairie schooner had carried him back to Illinois or over into Oklahoma.

A people pressed for ready money is a people ready to hold and preach extraordinary doctrines, and thus we are able to see how the populist wave of antagonism to eastern financial ideas swept the plains, and how a large political and social movement grew out of the failure of a frontier population to adjust itself properly to geographic conditions.

We can see how this adjustment has now come, and



that these commonwealths may now look safely forward to an era of unbroken progress. Kansas increased her population between 1870 and 1888 by much more than a million. Her numbers were quadrupled in that period. She now knows that there is a limit to the people she can support, especially in her western counties. She has found that only here and there can these lands be watered. They are too far from the sources of supply in the Rocky Mountains. Too much water has been evaporated, or has soaked away, or has been drawn into Colorado ditches, or it flows, as in Arkansas, too low to be run out on the uplands. The artesian supply will be small and confined to special places. Smaller population, more grazing, and forage crops that will thrive in a dry climate—such are the secrets of adjustment which have now been learned. The Kaffir corn product alone is now worth millions of dollars every year, and here, as in Nebraska on the north, the cow is known as a “mortgage lifter.”

The Llano Estacado of Texas is the southern continuation of the High Plains of Kansas; but its true nature as a plateau is more visible because, on the east and south, it fronts the seaboard lowlands by a steep wall formed as the streams have gnawed back into the upland, and on the west the Pecos Valley separates it from the mountains. The region is hot and almost too dry even for pasturage. And yet as much rain falls here as upon the wheat lands of Dakota, but the difference is in the spasmodic character of the rains, the greater evaporation, and low relative humidity. The amount of rainfall does not

assure paying tillage of the soil, for many things must be counted in. A region may seem to have water enough, but it may fall at the wrong season of the year, when it can do crops no good. Thus storage is added to the great bundle of irrigation problems.

Irrigation, indeed, is of universal interest west of the one hundredth meridian, and has become in many



FIG. 50. Desert Vegetation. Foothills of the House Range, Western Utah.

ways of national importance. And yet few saw this until within the last two or three years. National recognition came with the opening of a new century, and long before its close fifty millions of people may be dependent on this phase of agriculture, and the society of the West will be profoundly molded by it. Seven and one-half millions of acres are now made productive by artificial watering within the United

States, and the work is only in its beginnings. Before 1900 a proposition to give federal direction to irrigation was met by a united protest from the press of the East that this was a scheme to take money from the eastern farmer to give it to his brother in the West. It is now seen that more than one-third of the United States must depend on irrigation. It is not merely the value that lies in the soils that is in question, but the profitable development of every natural resource of the West, for food cannot permanently be brought across half a continent to provide for a vast and stable society.

We know now, also, that only a fraction (about one-tenth) of all the dry land can be irrigated, because there is water enough for this and no more. It becomes, therefore, a question of wisdom in the use of water, of the right choice of lands, of the proper crops, of skillful handling, and of a conserving use for grazing of lands that cannot be brought "under the ditch." Irrigation means, also, intensive agriculture, for economy requires the use of the shortest canals, the fewest weirs, the least machinery, and the largest cropping of small fields. And this means small holdings, a compact rural society approaching the conditions of the town, with convenient churches and schools, the best roads, telephones, free delivery of mails, and constant social life, divesting the farm of its ancient narrowness and loneliness. Such is the attractive picture presented in a recent writing,<sup>1</sup>—whether too sanguine or not we will not affirm,—but suggesting that at length the germs of discontent and

<sup>1</sup> Guy E. Mitchell, in *Forestry and Irrigation*, January, 1903.

anarchy in the cities may be made harmless by bringing out of the slums the men and the women that would with opportunity respond to the call of a better life.

Irrigation is national in other ways, for millions of people, frugal and wealth-producing, would thus be added to our population, ready to spend vast sums for articles manufactured in the East; while the growth of cities in the East, and the diffusion of money there, would enrich the farmer of the older states as well. Within a few years, also, bulletin after bulletin has appeared from the presses of the United States Department of Agriculture, dealing with irrigation experiments and results in humid regions. Every farmer knows that he loses half or far more than half of some crops because of the failure of rains at the critical time. More and more out of the principles established in western experience will the eastern farmer profit. Especially will this be true of crops which, like fruit, are especially dependent on water, and are grown on compact areas. Gradually the skinning processes, so well known in American agriculture, ~~will disappear~~, and their place will be taken by intensive tillage, small farms, special crops adapted to locality, closely settled lands which are indeed communities; and the unhappy line which makes the city a slum and the country a wilderness may be at least relieved, though it be a large hope that it should disappear.

Those who frown on federal supervision have not considered the inherent difficulties of irrigation policy and law. The early settler takes up a claim, cuts a ditch, and uses the water. He has a prior right, but

others come and water rights become involved. Long and big ditches and storage reservoirs are needed, and the corporation replaces the individual and the difficulties thicken. Finally a great river like the Missouri or Arkansas crosses the boundaries of states, and even state governments become helpless to protect their citizens. It would not be fair for Colorado to stop all the water of the Arkansas, leaving but a dry river bed in Kansas. Only federal authority can adjudicate such claims as this, or provide for the fair and continuous economic progress of this great western domain. In March, 1902, the United States Senate performed its part in enacting the new irrigation law, without a dissenting vote and without so much as a roll-call, and it seems at last to be recognized that the arid lands and the forests of America are as proper subjects of legislative attention as our manufacturing or our shipping.

In President Roosevelt's first message to Congress he said, "The forest and water problems are perhaps the most vital internal questions of the United States." He rightly puts these questions on their highest ground. They do not belong to the mere technique of agriculture; they pertain to the making of homes, to the right use of our greatest resources; they are social and economic problems that effect our whole national life.

In a recent report President Wheeler of the University of California included a department of irrigation among the immediate needs of the school, and such a department was almost at once established. More or less instruction in this field is given in all

the agricultural colleges and higher schools of the arid region. Somewhat over seven million acres, as we have seen, are now watered in the arid states and territories, which are eleven in number. California and Colorado are at the top of the list with more than one million acres each. But in the western United States there is believed to be water enough to irrigate sixty million acres. This means that but one-eighth of the work has yet been done, and a map showing the watered areas of the West is barely specked with the black patches used to represent them. Professor Elwood Mead compares the Missouri with the Nile. The African river supports five million people with its fertilizing waters, while our own great river and its branches can be made to water three times as much land as is now cultivated along the Nile. There are now fifty thousand miles of irrigating ditches in this country. The cost of them has been enormous, and yet upon authority we are told that "the total cost of all the irrigation works in use in the country is only three-fourths of the value of the crops produced each year on irrigated lands."

In Colorado the latest figures give more than 1,600,000 acres under the ditch. The state has thus outstripped California in its extent of watered land, though not in the value of the products, for some valuable fruits of the Pacific state will not grow in the colder climate of the Rocky Mountains. The agriculture of Colorado has often produced more annual value than its mining; but both go together, for the miner gets subsistence and the farmer gains a market, so that, with cities, farms,

railways, and mines, Colorado has fast risen to the complete possessions of a civilized and advanced community, and few richer or finer regions can be found than that which stretches along the eastern foot of the Front Range past Boulder and Greeley. If the one is known for its university, the other has



FIG. 51. Dust Whirl in the Desert, Western Utah.

its potatoes and alfalfa, and is not without its normal school, and both together typify the vigorous, untiring life which has grown out of a desert by right use of soil, sunlight, and mountain streams. The value of crops grown by irrigation in 1899 in Colorado was more than \$15,000,000. The settlers at Greeley in 1870 were second only to the Mormons of Utah in the early beginnings in the reclamation of dry soils; but now the watered lands of the state border

the Rocky Mountain front, stretch down the South Platte River into Nebraska, and form great patches on the Rio Grande, and also on the Gunnison, and the Grand, beyond the Continental Divide.

West of the Wasatch Mountains and east of the Sierras is a land which we know as the Great Basin. We call it so because it has no drainage to the sea. The mountain slopes that border it are well



FIG. 52. Great Salt Lake.

watered, and some rain falls everywhere upon its surface; but not enough to fill up its central lowlands and pour across the bounding divides upon the slopes that lead to the Pacific. The western half of Utah and the whole state of Nevada occupy the greater part of this basin. Many swift streams rush through the gorges of the Wasatch; but their goal is not the sea, for the remnant of water that is not dissipated in soil and air mingles with the shallow brines of Great Salt Lake. With more than temperate heat, and with little rainfall, the air is like a dry sponge, and absorbs



so much of the scanty moisture that the lakes cannot fill up and run to the sea. Hence the minerals dissolved from the surrounding lands and brought into Great Salt Lake cannot escape, and they completely saturate its waters.

Within the basin itself are many mountains, though they do not rival in breadth or height the bordering ranges. They run parallel to each other and from north to south, and are separated from each other by smooth areas that make up the general floor of the basin. This floor is especially flat and wide around Great Salt Lake, and southward.

If we look out over the fields and gardens that blossom at the base of the Wasatch, and would know the meaning of the soils, we must lift our eyes to the lower slopes of the mountains. It will take no skill to see horizontal platforms cut as strong lines on the mountain sides, and some of them are formed as high as one thousand feet above the lake and the railways. They are not such forms as streams and rain wash make on a mountain. Instead of ravines and buttressed ridges, we find what might be railway grades.

They could only be made by the waves of a body of water, and they mark the days when the Great Salt Lake was 1050 feet deep (it is now less than fifty); when it was not salt at all, but found a northward outlet into the Snake River, the Columbia, and the sea, and when the climate was therefore far more cool and moist than it is to-day. The reader has already been asked to imagine the wide flats that would greet his eye if Lake Erie or Lake Michigan could be drained. Here is a similar case: the ancient lake in Utah was

as large as Lake Huron and deeper ; into its waters floated the waste of the uplands, and sinking it formed the mud plains which have been uncovered by the drying away of the lake. If we ask when all this happened, we can only answer that this era of cool and wet climate seems to have been contemporaneous with the glaciers and great glacial lakes of the East.

We need not look for any finer instance of geographic control of the forms of land and water and of the ultimate doings of men. The earth's crust had to be wrinkled and broken to raise the mountains that bound the basin and run along its floor. Their wasting was made swift by the abundant waters that not only formed an inland sea, but brought the ruins of the land to rest in it ; and a change of climate, as yet unexplained, dried away the waters, until but a salty patch is left, leaving the wide plains dry and barren, and compelling man to guide out of their natural channels and use with economy the streams that remain. This the Mormon colonist began, more than fifty years ago, to do. It was the only way in which a community could then live in so distant a wilderness, and it continues to be the only way in which a commonwealth can prosper even in the days of great railways and swift communication.

As on the Great Plains so in the Great Basin it is an economic fact of greatest meaning that the water supply avails for but a fraction of the land. We shall never see a thousand miles of wheat and corn, as one might see on the Mississippi prairies. But here is little land of absolute dearth ; grasses grow, and their nutritious qualities outlast the process of drying, and

keep alive the roving herds even when snows cover the mountains of the horizon. Millions of sheep belong to the wealth of Utah, and cattle not a few.

The Colorado colony at Greeley and the settlers of Utah were the pioneers in irrigation, and have demonstrated that states can be built and can thrive upon this mode of tilling the soil. Hereafter it is only a question of using the experience of the past, with the necessary capital, to achieve like gains in New Mexico, Arizona, and other parts of the West.

Centuries ago aboriginal peoples made ditches and watered their crops in what is now Arizona, and the later Indian inhabitants were doing the same when the white man came. Nature has one unvarying command when man insists on dwelling in that dry and heated country. He must use the water with economy, and use as much of it as he can.

Northern Arizona will never be made into farms, for it belongs to that high plateau, cool and rocky, through which the Colorado has worn its great canyon. It has a fair rainfall, however, and will have its quota of prosperity through its pasturage. The southern and western districts are much lower, and they are hotter and drier as well; for at Phoenix, and westward, the rainfall is not above five inches in a year, and the average temperature is that of New Orleans.

The Gila River rises on the eastern border of the territory, and crosses it to the west and south, entering the Colorado at Yuma, and it is in the low and tropical basin of this river that man is finding a home. The irrigated lands of the Gila River are already worth millions of dollars, and without such use of water

there could never be anything here but tropical deserts and desolate uplands, crossed by the railways and visited by the tourist and explorer. Here it is proposed to make one of the beginnings in federal aid and supervision by building on the Gila River what is known as the San Carlos dam. By erecting a dam somewhat more than two hundred feet from the bed rock, enough water can be held in reserve to water two hundred and fifty thousand acres of land. If this can be done, the million dollars which the reservoir will cost will be a trivial outlay for so large a return, and would be far more than earned in any single year after the land is fairly under cultivation.

Similar to the Arizona lowlands is the Colorado desert of southeastern California, and this whole Colorado region may gather an importance all its own through the cultivation of tropical fruits. The Department of Agriculture at Washington is now coöperating with the University of Arizona in supporting at Tempe, near Phoenix, an experimental garden for date palms. These trees need plenty of water for the roots, a hot, dry atmosphere for the foliage, and winters not too severe. The tree will flourish in Florida, but the southern summer is neither hot nor dry enough to mature the fruit. It is at home in the Sahara, and at a single point in southeastern Spain. In 1900 the Department brought from Algeria shoots of the best varieties, and experiments are now in progress in Arizona and California. The fruit will not ripen unless the mean temperature exceeds 80° for a month in the summer, with a mean of 70° from May to October. The soils, however, must be moist,

and will not injure the plant if they are alkaline, as is often the case in arid regions. Earlier experiments have been tried here, and a single tree, eight years from the seed, bore four hundred pounds of fruit in a season. The Colorado Desert in California is thought to be the best date region in the New World. It would be deeply interesting if this land of perpetual heat and cloudless skies could be so watered as to grow rich with this Old World fruit.

Little attempt has been made to use the water of the Colorado River. For much of its course the deep canyons prevent all diversion to the adjoining lands, but there is no good reason why considerable patches of the hot desert farther south should not be reclaimed. Some of this land in southern California lies three hundred feet below the sea level, being isolated from the Gulf of California by the delta of the river. Exceptional floods now and then break across the river banks and form a lake in this depressed area, a lake which is at length destroyed by soakage and evaporation. If nature can do this, man might make canals serve a like purpose. His greatest obstacle would be the silting of the ditches by the waste with which the river is heavily loaded.

Along with a new reservoir on the Gila River, it is proposed to control the waters of St. Mary River in Montana, keep them from running their natural course into Canada, and turn them into the head waters of the Missouri, and make them the means of reclaiming, on their way, several hundred thousand acres of land. Whether such diversion of waters might become a still wider question is a problem for

those familiar with international law. It would not be difficult at least to raise the question of equity on our southern border, if ere long the progress of agriculture in Colorado and New Mexico should dry up the Rio Grande and destroy the value of lands that lie across the Mexican boundary and have been for generations refreshed by the waters of the river.

America is surely not a good field for showing what, in the long run, geographic environment can do with a people. History is here too short, and the tree is but a sapling, not bearing its mature fruits. And our people have scarcely recovered from the shock of migration, and we do not know to what account our changes should be charged. And we are a mixture of races, forming something as yet new and unknown, and who can tell how much is due to country and how much to amalgamation? No result may fairly be called final, and no type has been perfected. We can only study beginnings.

We know well what the desert type of society has always been,—nomadic and tribal, without cities, without settled interests, and almost without tillage of the soil. Flocks and herds were appropriate to the wastes of the Orient, familiar to us in many annals of the Old Testament, and in the tales of many a traveler. The heat of the plains, the keenness of the sun, the coolness of shadow, the preciousness of springs,—these are the earmarks of desert literature. Houses must be tents, or something easily renewed, in a migrating society, and the garb must protect from heat by day and the chill air by night. Or, if life is more settled, the primitive man or the

pioneer must build his hut as he can ; if he is in the "short grass" country, that is, on the high plains, he uses sod, and in the arid belt, or "bunch grass" country, he must have recourse to "adobe," or sun-dried mud.

An environment so pronounced could not be without its distinct power over thought and spirit. Nowhere



FIG. 53. Desert Valley at the Base of the House Range, Utah. The skeleton is that of a horse. The lower part of the valley is undrained, holds a shallow lake after a storm, and is covered with a fine earth, "adobe," containing gypsum and salt.

is this more finely seen than in the literature of the Bible, perhaps superlatively in the Psalms. In the desert the very insects seem to catch the spirit of the place and make themselves over into a protective oneness with its gray and neutral tones. And the dweller in verdant lands, entering the desert wastes with a recoil from their dryness and silence and solitariness, finds himself after a time bound by their

spell. He has never breathed air so pure and so purged from all odors, he has never looked into such measureless depths of stars, he never knew or dreamed that the desert could be so full of life, that its trails and water pockets, its grasses and its sage-brush, its coyotes and jack-rabbits, its rocks and its bordering mountains, all conspire to make a world in the wilderness. "The absence of dark green is soon not noticed, for the grays, reds, browns, and yellows are so quiet, so soothing, so varying in their intensity, and so thoroughly mingled that their quality cannot but be constantly in mind. To see the grand colors of a deep brown cliff brought out in a clear moonlight is to see one of the most wonderful effects. In the desert tints, as in the green of the humid country, the value of shadows in bringing out the quality and the contrast is not to be overlooked. In fact, after we become accustomed to the desert range of colors, the green of an oasis comes with a shock, like a misplaced touch in a beautiful picture."<sup>1</sup>

Arid America will not be, in just this way, the land of the imagination, when the American of to-day has tried his hand upon it. If there were water enough, he would moisten it all, and make it as populous as Massachusetts; but nature will have her way with much of it, and man will cross it with his railways and range over it with his herds, but he may only settle it here and there. But where man does conquer a dry wilderness, the change is absolute and profound. Instead of a nomad, we shall find dense and deep-rooted

<sup>1</sup> "Life Amid Desert Conditions," R. E. Dodge, Bulletin American Geographical Society, Vol. XXXIV, p. 416, 1902.



communities, like jewels in wide settings of gray desert. In a large settlement the single farmer cannot make his own ditch from the river, but there must be communal or government action. This, with small farms, intensive tillage, and close contacts everywhere, compels an approach to socialistic conditions that may never be reached on the watered prairies or among the Appalachians, where in some larger measure each man can be a law to himself.

Indeed, most of the embarrassment and embittering litigation of the arid country has arisen from an unconscious attempt to apply the old English law, made for a moist country, that allows a man to control the water that flows past or across his land. It has been well said that in an arid country water is like sunshine and air, and to monopolize it is infamous.

The young state of Wyoming has led the way in brushing aside the injustice of ancient customs, and the burden of unfit statute, and placing under just public regulation all the waters within her boundaries. She is fast being followed by older states, and we may look with amazement upon a flourishing commonwealth, less than thirteen years a member of the Union, rising in population, strong in agriculture and in mining interests, with a well-developed educational system and an enlightened government, where a generation ago there appeared a high and barren plateau beset with rugged mountains.

## CHAPTER IX

### MOUNTAIN, MINE, AND FOREST

THE East has its mountain ranges and they are covered with forests; but the mountains are low and in no important degree do they hold deposits of gold, silver, copper, or lead, and they are set in the midst of a moist rather than an arid land. The mountain ranges of the West are far from the older home of civilization on this continent, and the conditions of human life are as different as well could be from those of the East.

Colorado is in many ways the typical western state. Its mountains are broad and high; it supplies some of the sources of every great river in the West except the Columbia; it has unequaled mineral resources; irrigates more land than any other state; and has, in addition to its mountains, an area of the Great Plains on the one hand and a part of the Colorado plateaus on the other. Pike entered this land in 1807, Long in 1819, and Frémont in 1843. Gold was found in the Platte Valley in 1858, a territory was organized in 1861, and it became a state in the Union in the centennial year of American independence. It has a composite people, with all the qualities of the West, and has come in fifty years to an advanced civilization.

In 1893 a historical and descriptive pamphlet was prepared to accompany the state's exhibit at the Columbian Exposition. Upon its cover were placed the seal of the commonwealth, a mine gang at work, a view of irrigated fields in the Poudre Valley, a potato,



FIG. 54. A Mountain Highway, Ute Pass, near Manitou.

and the state Capitol building done in native granite. If a university had been included and a mountain railway, the representation would have been complete. The world has few such products to show for a half century of development.

Colorado is a quadrangle more than twice as large as the Empire State. North and south across the

central parts of the state lie the Rocky Mountains, a name that ought not to be used of mountains farther west. We may, however, carry the name northward into Wyoming and Montana, and southward into New Mexico. This means that the eastern ranges of the Cordilleran system are properly the Rocky Mountains.

East of the mountains, more than one-third of Colorado belongs to the Great Plains, looking toward Kansas and the Mississippi River. West of the Rockies is a region high, often rocky and barren, which continues into Utah and Arizona, and is a part of the plateau drained by the Colorado River. Its surface is much more broken than that of the Great Plains; for it is beset with lofty and pinnacled mountains, like the San Juan in the southwest, and the rugged and tangled Elk Mountains farther north; and it is carved by deep gorges like the Black Canyon of the Gunnison, and the canyon of the Grand River.

Nor is the Rocky Mountain Range simple and single; for it is made up of several north and south belts of mountains, separated from each other by broad and almost treeless valleys, which by a perversity of language are known as parks. Thus as one comes from the eastern plains he sees the Front Range looming on the horizon back of Denver, or south of the Arkansas it is the Wet Mountain Range or the Sangre de Cristo. Back of these mountains is a chain of parks, — North, Middle, South, Huerfano, and San Luis. These are smooth floors sloping gently up to the base of the mountains all around, and from six to seven thousand feet

above the sea. Their strata are young and loosely put together, having been washed in by mountain streams from every side. North of the Arkansas River the parks are too cold for grain and fruit, but yield pasturage. To the south, as in San Luis Valley, along the upper Rio Grande, thousands of acres are under the ditch. West of North and Middle parks is the Park Range, a part of the Continental Divide. West of South Park is the Mosquito Range and the Sawatch, the latter separating the Atlantic and Pacific waters; and between the Mosquito and the Sawatch is the open, longitudinal valley of the upper Arkansas River, which turns at Salida and passes, by the Royal Gorge, through the mountains to the plains. West of San Luis Park are the heights of the San Juan.

Perhaps best by a study of the drainage does one learn and remember the physiognomy of a new country. On the east the South Platte and Arkansas extend many slender fingers up the slopes and gather the abundant moisture of the mountains. The Platte reaches into South Park, and the Arkansas into the heart of the mountains around Leadville. The North Park drains by the North Platte out into Wyoming; while to the south into New Mexico flows the Rio Grande. On the west the Grand flows from Middle Park, the Gunnison from Marshall Pass, the Animas from the southwest, and the White and Yampa from the northwest. Colorado has not glaciers to feed its streams, but it does scatter its waters in every direction, like the Po, the Rhone, the Danube, and the Rhine, coming from Alpine sources.

We shall have a suitable idea of Colorado if we think of it as an upland whose general surface is from 4000 to 7000 feet above the sea, with long and strong ranges of mountains resting on it, and rearing many peaks to heights of a little more than 14,000 feet. If the land mass of Florida were so graded as to be everywhere of equal height above the level of the ocean, this average altitude would be 100 feet. The average altitude of New York is about 900 feet, that of Oregon is 3300 feet, and of Colorado, the highest of all the states, 6800 feet. Thus a rarefied atmosphere is to be added to our catalogue of conditions that here make up the environment of man.

Nearly as many kinds of natural causes for the growth of towns can be found in Colorado as would reward inquiry in any other state. These causes sometimes lie close at hand, and often in the more general conditions. Denver belongs to the latter class. It might, so far as the stream is concerned, have been at any other point on the South Platte River. But it is on the plains, where it was accessible to all lines of railway. On the east is the long approach from the Mississippi River. From Wyoming on the north and New Mexico on the south the lines of traffic follow the eastern base of the mountains. And twelve miles to the west the Clear Creek passes from the mountains to the plains. In the deep narrow valleys of this stream and its branches are the older mining camps, which developed forty years ago and ran the output of gold and silver far into the millions. For the sale of ores and the entrance of supplies Denver was the

center, and such it has remained, as remoter and richer masses of ore have been brought to light in later years throughout the state. It is the business and financial headquarters of the Rocky Mountains and the metropolis of the region between Kansas City or Omaha and San Francisco. It has a relative importance which no town of its size could have in the East.



FIG. 55. Product of a Leadville Smelter. The "Pigs" contain Silver, Gold, Lead, and Copper.

A village added to Toledo would bring it up to Denver with its 134,000 people. Rochester has 28,000 more people than Denver, while Newark equals Colorado's four largest towns combined and has 50,000 to spare. But Denver is the focus of larger interests than belong to any of these eastern cities, and we are not to forget that Denver dates from 1858, that she had but 35,000 people in 1880, and that she trebled her population in the next ten years.

The resident of Colorado Springs makes light and cheerful reference to the population of "lungers," of which perchance he is one, and tells you that the place is "a very good Siberia." But as a land of exile he does not seriously regard it, nor should he. The town was founded through the force of an unusual motive, for in the summer of 1871 its site was deliberately chosen for a health resort. The dry air, the towering Pike's Peak and lovely Cheyenne Mountain, the springs of Manitou, and the weird monuments of the Garden of the Gods, with natural routes of travel along the plains and through the passes of the Front Range, — these make the geographic foundation; while thirty-five years ago it could not have been foreseen that the richest mining district now open in the state, at Cripple Creek, would be largely tributary to Colorado Springs.

Pueblo was a village of less than a thousand in 1870, and is now the second town in Colorado. Several conditions combine to rear a city. It is on the highway leading south from Denver; it is on the Arkansas River at the gateway of the Rocky Mountains; it is within easy hauling distance of ores, coal, and flux, and draws tribute from the agricultural belt along the Arkansas River above and below.

Thus the three largest towns of Colorado occupy similar sites at the eastern foot of the mountains; none of them are surrounded by mineral deposits, but the three owe much of their wealth to the stores so long hidden in the mountains on the west.

Of the mining towns are Aspen in the west; Creede in the south; Ouray, Silverton, and Rico in the San



Juan; Cripple Creek in the east; — we pass them and take Leadville, in the center of Colorado, two miles above sea level, in the heart of the mountains. It does not require long in America for gold, or silver, or gas, or oil, to make a town. The mining that made Leadville was not the first in the neighborhood. California Gulch cuts the Mosquito Range east of the upper Arkansas. Here Tabor, later a senator of the United States, and his partner washed the placer gravels and cleaned up \$75,000 in sixty days. They and others were always annoyed by masses of heavy iron-stained rock that clogged the sluices; but these alien pieces of mineral proved to belong to the silver-bearing carbonates that would yield untold millions. From a mine salted by one "Chicken Bill," and refused by Denver buyers who found out the trick, Tabor afterward took \$1,500,000, and then sold it for an equal sum. A mine sold in the morning for \$50,000 was bought back by the same parties in the evening for \$225,000. Where in 1877 there was a post-office with 200 people, there was in 1879 the second city of Colorado, with a population of 15,000. A year later there were almost thirty miles of streets, gas, water, thirteen schools, and five churches.

Unlike some boom towns its life continues, though more quietly. The count of 1900 showed 12,000 people and more; and you may enter Leadville by rail from the east, south, and west, and regulating your steps with moderation needful to a "tender-foot" at an altitude of two miles, may wander among the dump heaps of Carbonate Hill, descend the shafts, visit the smelters, or look off upon the

rocky crests and snowy gorges of the Continental Divide.

The mining interests of Colorado have been about equally distributed on the two sides of the Continental Divide. West of the mountains is Aspen, which for several years was one of the first mining camps in the West. Here is the Mollie Gibson Mine from which \$60,000 in value were once taken in eight hours. One car of ore weighing twenty-four tons was worth \$76,500. One hardly need say that such cars were protected, en route to the smelters, by armed guards.

We have seen how the need of irrigation forces a recasting of the laws concerning water. Thus mining has its code, one point of which is that the lode or vein, which often is not far from vertical, can be followed to the depths by the owner of its outcrop, even though it runs beneath his neighbor's claim. But at Aspen and Leadville "blanket lodes" were found, which in geological phrase means that the ore-bearing mass is not a vein, but a bed. Now a bed is often horizontal, and it would be clearly unjust to allow it to be followed indefinitely. Both veins and blanket lodes run so indefinitely, that in a rich region the courts are full of claims, representing a fierce underground war for the treasures of the mountains.

Another great cluster of mining communities has grown up in the rugged San Juan corner of Colorado, so that the excitements and fascinations of the claim, the tunnel and the shaft, often overshadow the more sober but equally rich agricultural interests of the Centennial State. Yet here, as everywhere in the

western country, the crude life and unsystematic methods of prospecting, mining, and ore reduction have largely given way to systematic, scientific operations, with abundant capital and sober business management.

Many things must be remembered if we would understand the human type which is unfolding in these mountains. The cowboy does not typify the life of the plains and Rocky Mountain plateaus, though we could not know its beginnings or fully understand its quality without studying him. Nor does the miner, to whom we are introduced in Bret Harte's tales, reflect all, or the most, that is to be found in the Rockies and the Sierras; yet he does most truly enter into it, and we could not know the West if we left him out.

He is the hardy spirit who in 1849 or the decades that followed found eastern life too cramped to suit him, or had seen ill fortune on the Atlantic seaboard, or had found prairie farming too slow, or perchance had not been a welcome member of settled society. Whatever his conditions, he found himself in a land of realities and of dreams, and there were no greater dreams than some of the realities; he was apart from the restraints of society, and was often the more careless and violent, but more honest rather than less, for there is something in the western air, belonging perhaps to any frontier, which keeps being and seeming close together, and marks hypocrisy as the most loathsome of vices. Unduly careless it may be of conventionality, a new country frees itself from many self-imposed thralls of older com-

munities. As the frontiersman is free from the restraints, so he is bereft of the protection, of civilized society, and he becomes his own sheriff, court, and executioner; and the past generation in California or Arizona has in this regard brought back the conditions of a hundred and twenty-five years ago on the Holston and the Cumberland.



FIG. 56. Panning Gold at Cripple Creek in Earlier Days.

The very names given to the mines are full of the flavor of the frontier, and draw, in a bold line or two, pictures of men that must decide instantly, stake all on a venture, and follow failure with another trial, untrammelled by ordinary standards of conduct, and undismayed even by fate. Some personal history of success or failure is often hinted, — Lost Contact,

Last Dollar, Puzzler, Pay Rock, Last Chance. The fair sex are generously remembered, — Yankee Girl, Henrietta, Minnie, Della, Edith, Little Annie, and Maid of Erin. And some shall remain unclassified, — Smuggler, Modoc, Argonaut, Big Indian, Muldoon, Whale, Holy Moses, and Morning Glim. Even the saloons are not to be outdone in invention, — First Chance (at the fringe of the camp), Chamber of Commerce, Board of Trade, Early Morning, and Magnet.

- 7 • Shall we say that the young, the hardy, and the daring went West? And when they reached the mountains they dropped the shell of custom, took up their great tasks, grew strong with achievement, made fortunes for themselves or others, and hewed out states. He looks on the surface, who sees only profanity and light regard of human life, and does not see the bursting of a seed in new soil, and its upward growth in air free from the vapors of the lowland and the fogs of the sea border, where the sun ever shines, the pulse beats sturdily, and all the physical conditions tend to maintain, into more settled days, the energy and pace of the frontier period.

It is hardly safe to discount a pair of overalls anywhere, much less among the Rocky Mountains. There are universities now among the heights, and if there were not, under the coarse garb is apt to be a son of Harvard, Yale, Columbia, or Michigan. With enterprise go cordiality and helpfulness, and neither projects nor men are scrutinized with long and suspicious gaze before confidence is extended. And there is more moderation than the East gives the West

credit for having.♣ In the depressing months of 1893, among the mines, one heard no recriminations, and more often a pleasantry, as upon the "inconvenience of having a poor father-in-law." And there was no disloyalty to the western home. "You'll dream about this country," said an old-timer from Aspen, coming through South Park. And a mulatto woman in a town on the Rio Grande and Western voiced beyond doubt the feeling of every citizen of Colorado,—"Well, I'm *heah*, and I guess unless there's a mighty upheaval, I'll *stay* heah!"

If we follow the Rocky Mountains southward, they will carry us into New Mexico, and when we have reached Sante Fe or Las Vegas, the ranges have melted away into the plateau, lofty and dry, of which the territory is mainly composed. Southward, in western Texas, distinctive ranges reappear, and connect, across the Rio Grande, with the mountains of Mexico. Eastern New Mexico continues the high plains of Texas, and must mainly serve as a land of pasturage, except where irrigation is possible. This limits tillage to the borders of the Canadian and Pecos rivers. Western New Mexico is much of it too arid even for herds, except along the San Juan River in the northwest, which gains thus a store of water from the mountains of Colorado. The chief stream is the Rio Grande, which divides the territory from north to south. But here comes in a vexatious interstate problem, for there are canals enough on the upper river in Colorado to take all the water in the dry months, and no water now reaches the southern end of the territory during the irrigation season. The

only solution apparently lies in the construction of reservoirs.

Northward the Rocky Mountains lead us into Wyoming. It is a state similar in size, shape, and climate to Colorado. Like its neighbor, it is made up of mountain and plateau, but the differences are important. Colorado has a continuous backbone of high mountains. In Wyoming the ranges break down, leaving an easy passage from east to west through its central parts. This easy way has been found and followed by the Union Pacific Railway in its course from Nebraska to Utah. The Park Range from Colorado fades out in southern Wyoming; but the mountains reappear in rugged grandeur in central and northwestern Wyoming, in the Wind River Range, with its gorges and glaciers, and with few peaks ever scaled by man. Out of the northwestern corner of the state is carved the Yellowstone National Park.

Wyoming is in its drainage almost as inclusive as Colorado. From the North Park in the latter state it receives the North Platte head waters, which take a wide curve in the heart of the region. Northward it sends the North Cheyenne, the Powder, and the Big Horn to the Missouri. Over against the sources of the Big Horn River the Wind River Mountains send rolling to the south a great portion of the waters that have worn the canyons of the Colorado, while in the west the Snake River gathers its contribution for the Columbia. Without violating strong state pride one may yet aver, that having told the story of one Rocky Mountain state, it has been, in essentials, told for all. Each has its mountains and dry uplands, each has its

waters of which it saves as much as it can, each sends its herds over wide ranges for the sparse but nutritious grasses of the desert, and each has its share of mineral wealth. More than six hundred thousand acres are under the ditch in Wyoming, and nearly all of this land is devoted to forage crops, for agriculture here belongs almost entirely to the herd.

The ranges of the northern Rockies are in Montana and Idaho, and their direction is northwest and southeast. They are rugged, but not so lofty as the mountains of Colorado, and being farther north they harbor most of the small glaciers yet remaining in the Rocky Mountain region. Here are the northern sources of the Missouri and the southern sources of the Columbia River. Montana is a vast state, with a broad western hem of mountains, and a wide stretch of plateau watered and drained by the Missouri and its branches. Being in the far northwest, it has been occupied until recent years by those who were willing to live in isolation and care for cattle and sheep, or by those who, with more adventure or more capital, sought mineral treasure among the mountains about Butte and Bozeman. But with a climate not too severe and wide areas of arable soil, agriculture has risen to enormous proportions, and the ranch shares the state with closely settled groups of farmers. Almost a million acres are now subject to irrigation, as much as in Colorado or California a few years ago. The climate is more moist than in the states to the south, and being cooler there is less evaporation, so that much more is possible without irrigation than in most plateau and mountain states. Two transconti-



mental lines of railway serve for exchange with the East and the Pacific coast.

Like Montana, Idaho consists of mountain and plateau, but the latter is of another origin. The plateau of Montana is but a westward extension of the Great Plains, and in its northeast has an area of dissected strata forming bad lands, which are wholly as bad as any in Nebraska or Dakota. The plateau in Idaho lies broadly along the Snake River, which, rising in the Wind River Mountains of Wyoming, crosses southern Idaho by a wide curve from east to west. Here are the beginnings of the lava plains of the Northwest, and they occupy many thousand square miles, stretching broadly across southern Idaho and far over the eastern parts of Oregon and Washington, along the Snake and Columbia rivers. These lavas have been poured out of many vents or fissures now concealed and unknown, and are in some places three or four thousand feet in thickness. Often they have exceedingly smooth surfaces, and elsewhere they are diversified by volcanic cones and necks, by dislocations and by deep-cut channels of streams, such as the canyons of the Snake River. The prevailing species of vegetation is sage-brush, which gives its hue to the landscape; but hundreds of other plants occur, and the grasses furnish pasturage, and the soils when brought under the ditch are productive. And in the more northerly parts of Idaho, and near the base of the mountains, are lands better watered and raising the hardier grains and fruits freely. Few states show more variety of surface than Utah. In most of its eastern half are the



FIG. 57. Marshall Pass, Colorado. Sheds at the Summit Level.

Colorado or High Plateaus, regions of horizontal strata whose capping beds are six to eight thousand feet above the sea, broken into blocks by profound fissures, and dissected by streams, forming canyons only inferior in greatness to the Grand Canyon of Arizona. On the borders of the Colorado are the Henry Mountains, formed by subterranean intrusions of lava which domed up the overlying strata. The present mountain form has been reached through the removal by surface erosion of the upper parts of the domes, down into the lava itself.

In the north are high mountains of another sort. Contrary to Cordilleran custom, the range of the Uinta Mountains runs east and west—a broad up-arching of the strata, making a range eleven thousand feet in height. It stands like a rampart against the border of Wyoming, and through it the Green River has cut a sinuous gorge.

On the west the plateaus are bordered by the Wasatch Mountains, which present a less imposing front to the higher land on the east, but rise lofty and magnificent from the Great Basin. The basin we have entered already, to observe its ancient shore lines, its lake-bottom soils, its narrow ranges of mountains, and its clusters of human habitations clinging to the streams of the Wasatch. Four groups of mountain heights, all showing important differences of origin and structure, and two sets of plateaus, one lofty and broken, the other low and smooth, fresh waters, salt waters, deserts, forests and farms, gardens and mines—such are the contrasts of this central commonwealth of the Cordilleras.

No state has more curious interest than Nevada, whose conditions as a whole are more discouraging, not to say hostile, to human life than in any other field of the western United States. With western Utah it is a part, and by far the greater part, of the Great Basin. It is shut in by the Wasatch on the east and the towering Sierras on the west. It sends no stream to the sea, and the rivers which its meager waters keep in flow lose themselves in lakes which often become alkaline flats in the dry season. Like Utah, Nevada bears the records of a vast prehistoric lake, not so large nor so compact as its eastern neighbor, the Lake Lahontan of the geologists. The land is about five thousand feet above the ocean at the north, and declines below the level of the sea in the extreme south of the basin. The Basin Ranges interrupt the plains and save them from the monotony and dryness of absolute desert.

Nevada could scarcely have been admitted to the Union but for political necessity, and now has a population of 43,335, less than that of Akron, O.; Dallas, Tex.; Holyoke, Mass.; Norfolk, Va.; or Saginaw, Mich. Rhode Island has 428,000 people, or 407 for each square mile. The big western state, more than twice as large as New York, has four-tenths of a person for each square mile. Arid Wyoming has nearly a hundred thousand, and Oklahoma, not yet admitted to statehood, has almost four hundred thousand people.

The future population of Nevada is absolutely limited by her scant supplies of water; and yet, with all possible storage, some hundreds of thousands of men

and women can find homes within her borders. And when this day comes there will be stable prosperity, in no way like the fitful boom that built Virginia City and worked the Comstock Lode until the scalding waters of the lower levels could be endured no longer, and Nevada ceased to herald its bonanzas.

The state has three incorporated towns, and not one with a census roll of five thousand. Virginia City declined in the last decade from 8511 to 2695. But this is of small import when we look at the irrigation map and see black patches representing more than a half million of acres of watered lands, whose annual product is worth nearly six million dollars. For whatever of human comfort and prosperity is possible, the way is open, even in Nevada, and, as in southern California, intensive work with careful adaptation of valuable crops to small watered areas may achieve results beyond expectation.

The sparseness of populations of the West appears in another way. Twelve cities in the eleven divisions of the Cordilleran belt had, in 1900, twenty-five thousand people or more. Eight of these are in the three states of the Pacific coast, leaving but four to the eight vast states and territories that remain. Those four are Denver, Pueblo, Butte, and Salt Lake City. No Cordilleran state or territory has as many as ten people to a square mile, though California almost reaches it, and for more than half these states the average population of a square mile is less than two persons. Even under the limitations of the water supply the field for expansion is enormous.

In 1803 Louisiana was purchased, bringing an empire to the United States, but it was the Great Unknown. The fur trade had its headquarters at St. Louis, and the trappers brought their pelts and their stores from the plains beyond ; but no map had been made, little was known of the wild and mysterious tribes of the upper Missouri, and no white man had seen the northern Rocky Mountains or gone from the Mississippi River to the Pacific Ocean. Jefferson selected Captains Lewis and Clark to find out what lay beyond the horizon, and with a small party of laborers and soldiers they left St. Louis in 1803. They went up the Missouri River and were lost in the wilderness, whence they emerged in 1806, having completed the most daring, important, and famous exploration ever undertaken within the United States. Their route could be traced by the chain of names which they gave to river and mountain between the mouth of the Missouri and the mouth of the Columbia rivers. On the Missouri in Nebraska they made peace with the Indians of the plains, and of this the city of Council Bluffs, across the river in Iowa, is a memorial. They saw the dark coniferous forests of the Black Hills, passed the mouth of the Yellowstone, carried their boats around the Great Falls of the Missouri, climbed the Rocky Mountains, named the sources of the Missouri, went down into the basin of the Columbia, appeased their hunger upon its salmon, saw the glistening Rainier, and camped upon the desolate shores of the Pacific Ocean. They conciliated where they could, fought where they must, waded the snows, kept their note-books, traced

their maps, finished what they were sent to do, and came back to civilization.

In 1807 Lieutenant Z. M. Pike, having previously sought the sources of the Mississippi, turned his



FIG. 58. The Old Way. Pike's Peak Trail at Minnehaha Falls.

steps westward toward the waters of the upper Arkansas, and fastened his name upon the best-known though not the highest peak of the Rocky Mountains. Major S. H. Long went from Pittsburg to the Rocky Mountains in 1819-20, and likewise left his name upon one of the lofty peaks of the Colorado. Three years later, in going to the upper

Mississippi country, he passed Lake Michigan and found at Chicago "a few miserable huts inhabited by a miserable race of men."

The explorations of Captain B. L. E. Bonneville have more than geographic interest, because his jour-



FIG. 59. The New Way. Cog Railway at Minnehaha Falls.

nals afterward came under the editorial hand of Washington Irving, who gave them literary form and sent them out in the series of his works. Bonneville was a soldier, who asked leave from the United States Army to carry out, with such funds and men as he could himself secure, a search into the distant West. His work was done in the years 1832-36 and was primarily in the interest of the fur trade, a business



which lies at the foundation of much primitive history in the United States. Later authorities have ascribed to Bonneville the first correct account of the drainage of the region west of the Rocky Mountains, the region now known as the Great Basin. He it was that showed the interior character of this drainage, fixed the sources of the Willamette, San Joaquin, and Sacramento, and brushed away some of the geographic myths of Spanish writers. His search extended to the sources of the Yellowstone, of which he made a map.

The explorations of Captain J. C. Frémont followed by a dozen years and more. His work suggests the persistency of an error which was natural enough at the time, the belief, based on his reports, that the Great Basin is walled in by lofty mountains, making a continuous rim. This is suggested by the Wasatch and the Sierras on the east and west, but is not true to the north or south. Indeed, the long descent of the floor of the basin southward makes it perfectly possible, so far as land form is concerned, for an ordinary drainage system to develop, to drain all the shallow lakes of the basin and join the lower Colorado. The dryness of the climate is the only obstacle.

The roll of explorers for the middle decades of the nineteenth century is a long one, and bears the names of many soldiers, engineers, and men of science, and their scattered tours and investigations led down to that comprehensive system of surveys for opening routes of travel to the Pacific Ocean which was in operation in the fifties under the authority of the War Department, of which Jefferson Davis was secretary. Profiles, climate, magnetism, geology, botany, zoölogy,

and native tribes were all made objects of study, and a half-dozen routes were followed, in the north, in the south, and across the Rockies of Colorado. In this region Gunnison sought a line by the Sangre de Cristo Range and the Coochetopa Pass of the Sawatch. This was pronounced impossible, and Lieutenant Beckwith, who took command after Gunnison's death, said, "No other line exists in the immediate vicinity of this worthy of any attention in connection with the construction of a railroad from the Mississippi River to the Great Basin." This reads oddly in the presence of the Denver and Rio Grande, threading the Royal Gorge and the Marshall and Tennessee passes, or the Colorado Midland, sending its trains by Ute Pass and the South Park, past Leadville, and over the Continental Divide.

In these early explorations the naturalists who accompanied the engineers got their knowledge as they could, often only in fragments because of haste. But there followed upon the close of the Civil War the formal geographic and geological study of many areas, by various bodies known as the Hayden, Wheeler, King, and Powell surveys, and finally by the United States Geological Survey. The union of theoretical knowledge with the lessons of experience has never had a finer illustration than in the development of the mountains and plateaus of the West.

Will man in the West or in the East be friendly to the forests? There is no greater economic question than this, and there can be in the end but one answer, for experience has taught hard lessons in some parts of our domain. The forests are on the

mountains of the Cordilleran province, and they shield the lowlands of the Pacific coast. They belong in the most vital way to the problem of irrigation, for they store and dole out the waters which otherwise would rush unhindered to the sea, carrying the soils of the slopes, and destroying the bottom lands with floods. Hence the life of millions of people depends on the saving of the forests. It is a worthy sentiment that would save from fire and ax the noble Sequoia that has been growing for two thousand years, but there is more than sentiment in it. The earth's machinery is full of mutually dependent parts, to injure one of which is to destroy all.

In the Cascade and Ashland Forest reserves of Oregon but 25,000 out of 3,000,000 acres of forest have escaped the havoc made by fires. Some of the fires belong to the period of Indian occupancy, but by far the greater fires and in greater number have occurred since the white man came. But fires are less common in recent years. Little game is left, hunting-parties are few, there is much private ownership and more precaution, and the humus layer, once destroyed, no longer harbors and spreads the blaze. The Indian's reasons for firing were: that grass might grow near his camps, or that he might have clear hunting-grounds. The white man fired the woods to attract game, to open roadways, to promote the growth of grass, or through careless leaving of camp-fires. In one case where a fire was set to allure game, a half-dozen deer were obtained and fifteen to twenty million feet of timber were destroyed, the fire raging until put out by the fall



FIG. 60. Valley Lands, ruined by Recent Floods and abandoned; Southern Appalachians. Photograph by U.S. Bureau of Forestry.

rains. One fire was set to remove a windfall log from the road, and three thousand acres of forest were burned. In some cases the soil, almost purely vegetable in constitution, is completely burned away, leaving the bare rock. Many hundred years would be required to renew the soil and replace the forest. In the Cascade Reserve the fire loss during the past forty years amounted to seven thousand million feet of mill timber.

The shake maker has wasted untold amounts of timber. For these long coarse shingles he seeks the straight, well-splitting trunks, especially of the sugar pine, leaving enormous tops to rot, or to feed forest fires.

Sheep pasturing is more ruinous than cattle grazing, and there is a conspicuous dearth of seedlings where herds and flocks have filled the forest. The sheep herders start many fires, and while the forest ranger warns the trespasser to leave the ground, he is likely to get the answer that "bullets alone will be obeyed." Shake makers chip the trunks to test the grain. The resin runs out and down the tree, and the fires follow the line of fuel up the trunk and enlarge the scars made from year to year.

The Sequoias are not as near extinction as is supposed. There are many thousands of them in the reserves of California, but these noble patriarchs must be guarded from destroying selfishness.

There is but one course for the national government, and this has been entered upon with vigor and reward. The Cascade and Sierra ranges show an almost continuous belt of reserves. Others are found



**FIG. 61.** Appalachian Mountain Field ruined by Erosion. Photograph by U.S. Bureau of Forestry.

in every Cordilleran state, scores of thousands of acres, to be kept for the common weal, to be policed, and saved — their perennial springs, their straight trunks, their ample shade, their rich soil, their refreshing silences, rescued from the wickedness of the few, for the good of all.

The national government has a like problem and a similar duty in the East. The President, the Secretary of Agriculture, the geologist, and other men of science have pressed the need home upon Congress, and within a few days of this time adjournment has been had without action upon a forest reserve in the southern Appalachians. Here are the finest hardwood forests in America. Here is one of the heaviest rainfalls in the United States, with enormous capacity for destructive floods. As in the West, so in the East, the spongy soil cover once lost is lost forever, so far as present generations are concerned. Centuries do not work as much ruin under the forest cover as is done in a single storm after the lands have been made bare. Every southeastern state is involved, either bearing the forest slopes or receiving the waters upon its lowlands. Every water power in the hilly south is put to risk, and every acre of rich soil upon the river bottom. To save the forests for their timber, their beauty, and their health-giving shades, to save them for the farms and factories, and to save them at once, is the duty of the nation.

More than \$10,000,000 was the sum of flood losses in the Appalachian states during the year 1901. With the abundant rains, wherever a slope of any steepness is cleared, it is cropped but for a few years,

the soil is washed into the streams, tillage is given up, and the field is abandoned to ever deepening gullies. Meantime the rich bottom lands below are either excavated and removed bodily by the torrents, or they are deluged with five, eight, or ten feet of stony waste, and become as useless as a gravelly river bed. Ten years of delay would be fatal. The single states cannot do the work. North Carolina owns much of the forest, but the advantage is more for Tennessee. One state cannot be expected to legislate, and tax itself for the benefit of its neighbor. As with irrigation, so here is a federal question.

These are the fresh problems of the twentieth century. We must control the mountains streams, to turn wheels, to avert floods, to make the soils fruitful; we must save the forests for themselves, for the soils, and for the fruitfulness of the lowlands. We must find, the world over, the grains and fruits that will grow with most water and least, in the hot south or cool north; we must adjust ourselves to mountain, plateau, and plain, to river and sea; and future generations better than ourselves will be able to see how geographic influences gave permanent molding to the national life.





# CHAUTAUQUA

# Home Reading Course

## 1903-1904—American Year

---

*This Home Reading Course includes*

### **THE CHAUTAUQUAN**

An illustrated magazine of things worth while. Leading features for the coming year will be as follows: nine illustrated articles on "The Racial Composition of the American People," showing how different nationalities have contributed to the development of the American nation, discussing the influences that led them to seek a home in America and the ideals and customs they brought with them; "A Reading Journey in the Borderlands of the United States," a richly illustrated, descriptive tour through Newfoundland, Canada, Alaska, Hawaii, Mexico, Central America, and the islands of the Caribbean sea (running through nine numbers); a series of nine illustrated articles on "American Sculptors and their Art," in which the development of art in America will be studied through the work of its great sculptors; in addition to the required readings, series of articles on "The Civic Renaissance," "Stories of American Promotion and Daring," "Nature Study," "Civic Betterment," "Talks about Books," etc. Yearly subscription price, \$2.00

### **LITERARY LEADERS OF AMERICA**

By Richard Burton. A new book which gives its readers not only the knowledge of who may be considered leaders, but also of what they have written, with a pleasant introduction to the personalities of the writers themselves,—Irving, Poe, Hawthorne, Emerson, Bryant, Longfellow, Holmes, Whittier, Lowell, Whitman, Lanier. Price . . . . . \$1.00

### **PROVINCIAL TYPES IN AMERICAN FICTION**

By Horace Spencer Fiske. A fascinating study of American types as they have been portrayed by novelists whose works have received permanent recognition. Aside from its popular appeal, it will serve as a helpful standard by which to judge of all literature depicting American character. Price . . . . . \$1.00

### **EVOLUTION OF INDUSTRIAL SOCIETY**

By Richard T. Ely. Many of the great problems of the day are considered in this book. "Recent Tendencies of Industrial Evolution," "Competition," "Social Progress and Race Improvement," "Monopolies and Trusts," "Industrial Peace," "Industrial Liberty," "Possibilities of Social Reform," will be treated among other subjects. Dr. Ely's scholarship and power of interpretation for the general reader make this volume especially valuable. Price . . . . . \$1.25

### **GEOGRAPHIC INFLUENCES IN AMERICAN HISTORY**

By Albert P. Brigham. A comparatively new, yet interesting and comprehensive study is that of the relation of natural configuration and resources to the life and progress of the people. Contains chapters on The Eastern Gateway of the United States; Shoreline and Hilltop in New England; The Appalachian Barrier; The Great Lakes and American Commerce; Cotton, Rice, and Cane; Prairie and Plain; Arid Lands and Forest Reserves; Mines and Mountain Life. Price . . . . . \$1.25

**AMERICAN YEAR** Book of Helps and Hints . . . . . .50

*Total Value, \$7.00*

---

*Price (when ordered together) of the magazine, the four books, and helps and hints book, \$5.00.*

---

## **The Chautauqua Press**

Springfield, Ohio      Chautauqua      New York      Chicago

# The Chautauquan

## A Magazine of Things Worth While

The Chautauquan is worth while because the editorial plan of the magazine gives every reader, as a result of a few months' reading, an intelligent and comprehensive understanding of a "key topic" or central subject of immediate and vital interest to the people, around which will be grouped other subjects of kindred nature, with current happenings treated editorially in a "Highways and Byways" department, so as to point out their relation to the great permanent factors involved in the chief topic under consideration.

America will be the "key topic" for a series of articles beginning in the September, 1903, number.

## THE RACIAL COMPOSITION OF THE AMERICAN PEOPLE

By JOHN R. COMMONS

A series of nine illustrated articles showing how the different nationalities have contributed to the development of the American nation, what influenced them to leave the Old World for the New, and the effect their residence and citizenship are having on our national life.

### OUTLINE OF CHAPTERS

- I. The Race Problem in General.
- II. Colonial Race Elements.
- III. Immigration of Different Races, 1820-1903.
- IV. Distribution of Races in United States.
- V. The Negro.
- VI. Chinese, Indians, Alaskans, Filipinos, Hawaiians.
- VII. Wages, Standard of Living, Industry, Prosperity, as affected by Races and Immigration.
- VIII. Political and Religious Effects of Immigration.
- IX. Legislation and Summary.

## A READING JOURNEY IN THE BORDERLANDS OF THE UNITED STATES

Takes the reader through Newfoundland, Canada, Alaska, Hawaii, Mexico, Central America, West Indies, Cuba, and Porto Rico. No narrations of travel or descriptions of countries and their inhabitants have ever been published that give such clear perceptions and understanding of a country's characteristics as do these famous Chautauqua Reading Journeys. Nine richly illustrated articles.

## AMERICAN SCULPTORS AND THEIR ART

In nine numbers of the magazine the artistic development of America will be studied through the work of its great sculptors, — a field in which Americans rank with the greatest of other nationalities. Special importance will be given to the illustrative features of these articles.

Special features appearing throughout the year: "The Civic Renaissance," by Charles Zueblin (Nine articles. Illustrated); "Stories of American Promotion and Daring," by Archer Butler Hulbert ("Washington: A Typical Promoter" will be the first article in this striking series); "Nature Study" supplementing the Chautauqua Junior Naturalist Club work in "Pets and Animals" (juvenile), by Alice G. McCloskey; "Survey of Civic Betterment," conducted in cooperation with the American League for Civic Improvement"; "Talk about Books"; "Outlines and Programs for Club Work" on topics related to subjects carried in the magazine.

*Yearly Subscription, \$2.00. Single Copies, 20 cents*

## The Chautauqua Press

Springfield, Ohio      Chautauqua      New York      Chicago

# CHAUTAUQUA Home Reading Course

1902-1903—English-Russian Year

---

## **THIS HOME READING COURSE INCLUDES THE CHAUTAUQUAN**

An illustrated monthly magazine containing nine articles on "The Saxon and Slav" (a comparative study of the social and political genius of the two great rivals for world supremacy); "A Reading Journey through Russia" (an illustrative descriptive tour of the land of the Czars, running through nine numbers of the magazine, the illustrations accompanying which will make a remarkable picture of the life and country of the Russians); "Studies in English" (practical papers on such topics as How to collect and arrange Material for a Paper, The Preparation of Reports for Publication, Different Kinds of Letter Writing, etc.). Subscription price . . . . . \$2.00

## **TEN ENGLISHMEN OF THE XIX CENTURY**

By James Richard Joy. Each of these ten Englishmen, from Wellington to Gladstone, stands for some great step in England's progress. Price . . . . . \$1.00

## **LITERARY LEADERS OF MODERN ENGLAND**

By W. J. Dawson. A most exceptional little volume, giving, as it does, a vivid idea of the personal qualities of Wordsworth, Tennyson, Browning, Carlyle, and Ruskin, and of their influence upon the time in which they lived. Price . . . . . \$1.00

## **A SURVEY OF RUSSIAN LITERATURE**

By Miss Isabel F. Hapgood. As the title suggests, the book presents a survey of the whole field of Russian literature, but special prominence is given to a few great writers. Price . \$1.00

## **THE WORLD'S GREAT FARM**

By Selina Gaye. The practical bent of this fascinating book on nature study will help to interpret Nature's ways of developing her great farm. Price . . . . . \$1.00

## **ENGLISH-RUSSIAN YEAR**

Book of helps and hints. Price . . . . . \$0.50

**Total value, \$6.50**

---

*Price (when ordered together) of the magazine, the four books, and book of helps and hints, \$5.00.*

---

**The Chautauqua Press**  
Springfield, Ohio      Chautauqua      New York      Chicago





**14 DAY USE**  
**RETURN TO DESK FROM WHICH BORROWED**  
**LOAN DEPT.**

This book is due on the last date stamped below, or  
on the date to which renewed.

Renewed books are subject to immediate recall.

JUN 10 1967

MAY 27 67-11 AM

REC'D LA

LD 21A-60m-2, '67  
(H241s10)476B

General Library  
University of California  
Berkeley





